

NOT A BID FORM



LANDAN LANE RECONSTRUCTION

CITY OF SPRINGDALE

PROJECT: 180737

BID DATE & TIME: FEBRUARY 4, 2020 at 10:00 AM

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
1	201	CLEARING AND GRUBBING	1	LS
2	202	CURB REMOVED	1,017	FT
3	202	CATCH BASIN OR INLET REMOVED	4	EA
4	203	EXCAVATION, AS PER PLAN (19")	1,091	CY
5	204	PROOF ROLLING	4	HR
6	204	SUBGRADE COMPACTION	2,067	SY
7	SPL	ASPHALT REJUVENTAING AGENT	2,067	SY
8	253	*SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKES WITH 3" 304	25	CY
9	301	ASPHALT CONCRETE BASE, PG64-22 (6")	341	CY
10	304	AGGREGATE BASE (10"), CRUSHED CARBONATE STONE (CCS), AS PER PLAN	569	CY
11	304	*AGGREGATE BASE, AS PER PLAN	85	CY
12	407	TACK COAT, TRACKLESS TACK	205	GAL
13	410	TRAFFIC COMPACTED SURFACE, TYPE A OR B	50	CY
14	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 (448) (1.75")	99	CY

NOT A BID FORM



LANDAN LANE RECONSTRUCTION

CITY OF SPRINGDALE

PROJECT: 180737

BID DATE & TIME: FEBRUARY 4, 2020 at 10:00 AM

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
15	448	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG64-22 (1.25")	71	CY
16	448	ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	20	SY
17	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: DRIVEWAY APRON	348	SY
18	605	6" SHALLOW PIPE UNDERDRAINS (707.41)	260	LF
19	609	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN	1,017	LF
20	609	CURB, TYPE 6, AS PER PLAN	48	LF
21	611	CATCH BASIN, NO. 3, AS PER PLAN	3	EA
22	611	CATCH BASIN, NO. 6, AS PER PLAN	1	EA
23	611	INLET RECONSTRUCTED TO GRADE, ODOT CATCH BASIN NO. 2-5, AS PER PLAN	1	EA
24	611	*INLET FRAME AND GRATE (ODOT CATCH BASIN NO. 2-5)	1	EA
25	614	MAINTAINNING TRAFFIC	1	LS
26	624	MOBILIZATION	1	LS
27	644	CENTERLINE	40	LF
28	644	STOP LINE	16	LF

NOT A BID FORM



LANDAN LANE RECONSTRUCTION

CITY OF SPRINGDALE

PROJECT: 180737

BID DATE & TIME: FEBRUARY 4, 2020 at 10:00 AM

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
29	SPL	*MANHOLE ADJUSTED TO GRADE, SANITARY SEWER	1	EA
30	SPL	*MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY SEWER MANHOLE	1	EA
31	SPL	*BRICK MASONRY, MANHOLE REPAIR, SANITARY SEWER MANHOLE	1	EA
TOTAL				