

ITEM	DESCRIPTION	QTY	UNIT
1	Mobilization / Demobilization	1	LS
2	8" Waterline (C900 DR18)	108	LF
3	6" Waterline (C900 DR18)	30	LF
4	Tracer Wire	138	LF
5	8" Gate Valve	3	EA
6	6" Gate Valve	1	EA
7	6" Hydrant	1	EA
8	Site Restoration and Appurtenances	1	LS
9	Water Storage Tank (20' Dia., 89'H)	1	LS
10	Tank Mixer	1	LS
11	Existing Tank Demolition	1	LS
12	Chain Link Fence	120	LF