


TYPICAL SECTION - FULL DEPTH REPLACEMENT
SOUTH DARBY ROAD, STA. 0+19.88 TO STA. 22+32.29

PROPOSED LEGEND

- ① SUPERPAVE ASPHALT MIXTURE DESIGN, HMA WEARING COURSE, PG64-22, 0.3 TO <3 MILLION ESALS, 9.5 MM MIX, SRL-H, 1.5" DEPTH
- ② SUPERPAVE ASPHALT MIXTURE DESIGN, HMA BINDER COURSE, PG64-22, 0.3 TO <3 MILLION ESALS, 19.00 MM MIX, 2.5" DEPTH
- ③ 12" - PENNDOT SECTION 350, NO. 2A SUBBASE MATERIAL COMPACTED 100% STANDARD PROCTOR
- ④ BITUMINOUS TACK COAT
- ⑤ GEOTEXTILE FABRIC, CLASS IV, TYPE A
- ⑥ SUBGRADE SHALL BE COMPACTED AND PREPARED ACCORDING TO PENNDOT SECTIONS 206 & 210
- ⑦ PENNDOT ITEM 651, TYPE 1A
- ⑧ PROPOSED GRADING WITH CLEAN TOP SOIL (SEED AND MULCHING)
- ⑨ RUBBERIZED ASPHALT SEALANT



ISSUED FOR:	DESIGN NO.	REVISION	DATE
ISSUE DATE: 2/21/2019	NO.		
SCALE: AS SHOWN			
DESIGNED BY: PMT			
DRAWN BY: PMT			
CHECKED BY: IAG			

CITY OF HERMITAGE
SOUTH DARBY ROAD STORMWATER AND
ROADWAY IMPROVEMENTS PROJECT
HERMITAGE, PENNSYLVANIA

ROADWAY TYPICAL SECTIONS

PROJECT NO.	181039
DISCIPLINE	CIVIL
SHEET NAME	TYP-1
SHEET	04
OF	25