

NOT A BID FORM



PROJECT: E. ALEXANDRIA PIKE BRIDGE REPLACEMENT
CAMPBELL COUNTY FISCAL COURT - ROAD DEPARTMENT
PROJECT #: 19052301-02

Item No.	Spec. No.	ITEM	Est. Qtys.	Unit of Measure
		COSTS FOR BIDDING		
1	112	MAINTENANCE OF TRAFFIC	1	LS
2	202	CLEARING AND GRUBBING	1	LS
3	203	GUARD RAIL REMOVED	30	LIN FT
4	203	CULVERT REMOVAL	1	LS
5	203	REMOVE GABION WALL	1	LS
6	207	PROOF ROLLING SUBGRADE	1	LS
7	302	CRUSHED STONE BASE	40	TON
8	302	CRUSHED AGGREGATE SIZE NO 2	15	TON
9	302	CRUSHED AGGREGATE SIZE NO 8	10	TON
10	406	FULL DEPTH PAVEMENT	80	SY
11	406	ASPHALT SURFACE COURSE AND TACK COAT	180	SY
12	408	VARIABLE DEPTH ASPHALT MILLING	180	SY
13	603	SHEETING AND SHORING	1	LS
14	603	STRUCTURAL EXCAVATION COMMON	75	CY
15	605	8' x 7' x8' Box Section	1	EA
		Setting box sections including crane	1	LS

* Denotes Contingency Item

NOT A BID FORM



PROJECT: E. ALEXANDRIA PIKE BRIDGE REPLACEMENT
CAMPBELL COUNTY FISCAL COURT - ROAD DEPARTMENT
PROJECT #: 19052301-02

Item No.	Spec. No.	ITEM	Est. Qtys.	Unit of Measure
		Backfilling culvert & wingwalls	1	LS
16	608	CURB ON EACH END OF BOXES (Includes the cost of reinforcing steel, formwork and all incidentals needed to construct the curbs)	1	LS
17	608	CONCRETE WINGWALLS (Includes the cost of reinforcing steel, formwork, preformed expansion joint filler and all incidentals needed to construct the walls)	20	CY
18	608	CONCRETE CUTOFF WALLS (Includes the cost of reinforcing steel, formwork, preformed expansion joint filler and all incidentals needed to construct the walls)	3	CY
19	703	CLASS III CHANNEL LINING	9	CY
20	713	PAVEMENT EDGE LINES AND CENTER LINES, AS PER PLAN	1	LS
21	719	GUARDRAIL, WITH DELINEATORS	260	LIN FT
22	719	GUARDRAIL END TREATMENT, TYPE 4A, INCLUDES OBJECT MARKER TYPE 3	1	EA
23	719	GUARDRAIL END TREATMENT, TYPE 7	2	EA
24	719	GUARDRAIL END TREATMENT, TYPE 2A, WITH CABLE ASSEMBLY	2	EA
25	808	WATERPROOFING TOPS AND SIDES OF CONCRETE	110	SY
26	827	EROSION CONTROL MATERIALS	1	LS

* Denotes Contingency Item

NOT A BID FORM



PROJECT: E. ALEXANDRIA PIKE BRIDGE REPLACEMENT
CAMPBELL COUNTY FISCAL COURT - ROAD DEPARTMENT
PROJECT #: 19052301-02

Item No.	Spec. No.	ITEM	Est. Qtys.	Unit of Measure
27	SPL	PORTABLE CHANGEABLE MESSAGE SIGN	60	DAYS
28	SPL	DELIVERY AND INSTALLATION OF 3 BOX SECTIONS	1	LS
29	SPL	RESTORATION	1	LS