

## ADDENDUM #1

**Job #:** 19052301-02      **Project Title** East Alexandria Pike #63

**Client:** Campbell Country Road Department

**Issue Date:** November 7, 2019

**Bid Date:** November 12, 2019

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN BY FAX (859-525-0561) TO THE ATTENTION PEGGY BELLEW OR YOU MAY RESPOND VIA EMAIL TO: [pbellew@ctconsultants.com](mailto:pbellew@ctconsultants.com).

\_\_\_\_\_  
Name / Title:

\_\_\_\_\_  
Company:

\_\_\_\_\_  
Date:

### CLARIFICATION:

Please use the attached bid tab in place of the one provided in the spec book.



PROJECT: E. ALEXANDRIA PIKE BRIDGE REPLACEMENT  
CAMPBELL COUNTY FISCAL COURT - ROAD DEPARTMENT  
PROJECT #: 19052301-02

Item No.	Spec. No.	ITEM	Est. Qtys.	Unit of Measure	Unit Cost	Item Cost
		<b>COSTS FOR BIDDING</b>				
1	112	MAINTENANCE OF TRAFFIC	1	LS		
2	202	CLEARING AND GRUBBING	1	LS		
3	203	GUARD RAIL REMOVED	30	LIN FT		
4	203	CULVERT REMOVAL	1	LS		
5	203	REMOVE GABION WALL	1	LS		
6	207	PROOF ROLLING SUBGRADE	1	LS		
7	302	CRUSHED STONE BASE	40	TON		
8	302	CRUSHED AGGREGATE SIZE NO 2	15	TON		
9	302	CRUSHED AGGREGATE SIZE NO 8	10	TON		
10	406	FULL DEPTH PAVEMENT	80	SY		
11	406	ASPHALT SURFACE COURSE AND TACK COAT	180	SY		
12	408	VARIABLE DEPTH ASPHALT MILLING	180	SY		
13	603	SHEETING AND SHORING	1	LS		
14	603	STRUCTURAL EXCAVATION COMMON	75	CY		

\* Denotes Contingency Item



**PROJECT: E. ALEXANDRIA PIKE BRIDGE REPLACEMENT  
CAMPBELL COUNTY FISCAL COURT - ROAD DEPARTMENT  
PROJECT #: 19052301-02**

Item No.	Spec. No.	ITEM	Est. Qtys.	Unit of Measure	Unit Cost	Item Cost
15	605	8'x7'x8' BOX SECTION (Includes the cost of purchasing, delivering, and placing the box, and all incidentals that come along with it)	1	LS		
16	608	CURB ON EACH END OF BOXES (Includes the cost of reinforcing steel, formwork and all incidentals needed to construct the curbs)	1	LS		
17	608	CONCRETE WINGWALLS (Includes the cost of reinforcing steel, formwork, preformed expansion joint filler, backfill and all incidentals needed to construct the walls)	20	CY		
18	608	CONCRETE CUTOFF WALLS	3	CY		
19	703	CLASS III CHANNEL LINING	9	CY		
20	713	PAVEMENT EDGE LINES AND CENTER LINES, AS PER PLAN	1	LS		
21	719	GUARDRAIL, WITH DELINEATORS	260	LIN FT		
22	719	GUARDRAIL END TREATMENT, TYPE 4A, INCLUDES OBJECT MARKER TYPE 3	1	EA		
23	719	GUARDRAIL END TREATMENT, TYPE 7	2	EA		
24	719	GUARDRAIL END TREATMENT, TYPE 2A, WITH CABLE ASSEMBLY	2	EA		
25	808	WATERPROOFING TOPS AND SIDES OF CONCRETE	110	SY		



PROJECT: E. ALEXANDRIA PIKE BRIDGE REPLACEMENT  
 CAMPBELL COUNTY FISCAL COURT - ROAD DEPARTMENT  
 PROJECT #: 19052301-02

Item No.	Spec. No.	ITEM	Est. Qtys.	Unit of Measure	Unit Cost	Item Cost
26	827	EROSION CONTROL MATERIALS	1	LS		
27	SPL	PORTABLE CHANGEABLE MESSAGE SIGN	60	DAYS		
28	SPL	PICK-UP AND INSTALLATION FOR 32 LF OF THE 40 LF OF CONCRETE BOX SECTION ( THE 32 LF IS ALREADY PURCHASED AND OWNED BY THE CITY)	1	LS		
29	SPL	RESTORATION	1	LS		
					TOTAL =	