

NOT A BID FORM

CT Consultants				
Project:		MASON ROAD STABILIZATION	Date:	10/17/19
			Project No.:	190985
ITEM NO.	SPEC. NO.	ITEM	Quantity Used	Unit of Measure
		BASE BID		
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	212/213	EROSION AND WATER POLLUTION CONTROL	1	LS
4	SPL*	FULL DEPTH PAVEMENT REPAIR	20	SY
5	302/SPL*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	15	CY
6	SPL	EXCAVATION & BACKFILL FOR CRIBBING (NO. 2 STONE CAPPED WITH DGA)	150	CY
7	SPL	CONTRACT DRILLING FOR INSTALLATION OF RAILROAD RAIL	2,400	LF
8	SPL	USED RAILROAD RAIL (130 - 136 lbs/ft) FOR PILING	2,400	LF
9	SPL	CRIBBING WALL (USED GUARDRAIL)	1,200	SF
		ALTERNATE 1		
10	719	GUARD RAIL, STEEL W-BEAM, SINGLE FACE, 6' POSTS TYPICAL	200	LF
11	719	TYPE 2A GUARD RAIL END SECTIONS	2	EA