



To: All Plan Holders of Record

From: CT Consultants, Inc.  
For the Owner

**Re: Addendum No. 2  
ADA Ramp Replacement  
City of Willoughby**

Date: May 4, 2020

This Addendum forms a part of the contract documents and modifies the original bidding documents dated March 2020 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

### **PRICES TO INCLUDE**

#### **2.3 4-INCH CONCRETE WALKS, AND 6-INCH CURB RAMPS, INCLUDING REMOVAL, AS PER PLAN**

##### **Clarification:**

Bid items shall include 4" of ODOT 304 aggregate base and micro fiber reinforcement, "PSI Fiberstrand F" shall be applied at 1.5lbs/cy (1.5" L fibers) or approved equal. No steel wire mesh shall be required for this project. Concrete shall be broom finished and edge tooled. Joints shall be hand formed and all edges and joints shall be rounded with a 1/4" radius. 1/2" preformed joint material per ODOT 705.03 shall be included and shall be applied every 30' or between sidewalk and fixed object (manhole casting, existing sidewalk, etc.).

TL:JNS/mep

Enclosures

H:\2020\200146\SPEC\Addenda\Addendum 02\Addendum 02.Doc