

Proposal Items - NOT A BID FORM

CT Consultants, Inc.		
Project:	2020 STREET PROGRAM ALEXANDRIA, KENTUCKY	Date: 05/14/2020 Project No.: 200242

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
		BROOKWOOD DR (730'), ASHWOOD LN (485'), MAPPLEWOOD CT (460'), THATCHER AVE (865'), THATCHER CT (1,115'), PAUL LN (1,050'), RAINBOW LN (385'), ENZWEILER RD (2,490'), ORLANDO DR (STORM SEWER)		
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	402/403	VARIABLE THICKNESS ASPHALT PAVEMENT LEVELING (3/4" AT CURB TO 1-1/4" AT CENTER)	9,450	SY
4	402/403	1" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	9,450	SY
5	402/403	1-1/2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	1,850	SY
6	402/403	2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	7,000	SY
7	402/403	5" ASPHALT BASE (TRENCH RESTORATION - ORLANDO DR)	175	SY
8	408	ASPHALT MILLING (BUTT JOINTS, CATCH BASINS, AND AT DRIVEWAYS AND CURB)	750	SY
9	408	CONCRETE MILLING (BUTT JOINTS AND AT CATCH BASINS)	225	SY

* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DIRECTION

CT Consultants, Inc.

Project: **2020 STREET PROGRAM
ALEXANDRIA, KENTUCKY**

Date: 05/14/2020
Project No.: 200242

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
10	SPL*	FULL DEPTH PAVEMENT REPAIR, AS PER PLAN	600	SY
11	302/SPL*	GRAVEL BASE, 6" DENSE GRADED AGGREGATE FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	100	CY
12	505*	CONCRETE DRIVEWAY REPLACEMENT (THATCHER CT)	250	SF
13	506	NEW 3" ROLLED CURB AND GUTTER (THATCHER CT)	375	LF
14	506*	4" ROLLED CONCRETE CURB & GUTTER REPLACEMENT	100	LF
15	506	NEW 6" VERTICAL CURB (ORLANDO DR)	550	LF
16	SPL	24" STOP BAR - WHITE	1	EA
17	701	12" DIAMETER STORM SEWER	395	LF
18	710	INSTALL NEW STANDARD CURB INLET - SINGLE GRATE	1	EA
19	710	INSTALL NEW STANDARD CURB INLET - DOUBLE GRATE	4	EA
20	710	INSTALL NEW STANDARD STORM MANHOLE	1	EA

* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DIRECTION