

1	103s00011	PRECONSTRUCTION VIDEO DOCUMENTATION, AS PER PLAN	1.00	LS
2	103s05001	BONDS AND INSURANCES, AS PER PLAN	1.00	LS
3	251E01001	PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	400.00	SY
4	253E02001	PAVEMENT REPAIR, AS PER PLAN	79.00	CY
5	254E01001	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN	4,771.00	SY
6	407E20205	TACK COAT, TRACKLESS TACK	573.00	GAL
7	422E10001	SINGLE CHIP SEAL, TYPE A, AS PER PLAN	4,771.00	SY
8	441E50001	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22, AS PER PLAN	164.00	CY
9	441E50301	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448), AS PER PLAN	197.00	CY
10	452e10112	6 INCH NON-REINFORCED CONCRETE DRIVES AND APRONS, CLASS QC MS, INCLUDING REMOVAL, AS PER PLAN	120.00	SY
11	608e10011	4 INCH CONCRETE WALK, INCLUDING REMOVAL, AS PER PLAN	800.00	SF
12	608e13301	6 INCH CONCRETE WALK, WITH INTEGRAL VEHICULAR CURB, AS PER PLAN	200.00	SF
13	609e24520	CURB, TYPE 4-C, INCLUDING REMOVAL, AS PER PLAN	1,000.00	FT
14	611e99152	INLET ADJUSTED TO GRADE, METHOD D.1., (brick) AS PER PLAN	9.00	EACH
15	611e99656	MANHOLE ADJUSTED TO GRADE, METHOD D.1 (brick), AS PER PLAN	9.00	EACH
16	611E99820	SPECIAL - MISCELLANEOUS METAL	2,000.00	LB
17	614E11001	MAINTAINING TRAFFIC, AS PER PLAN	1.00	LS
18	623E39500	MONUMENT BOX ADJUSTED TO GRADE	1.00	EACH
19	638e10811	VALVE BOX ADJUSTED TO GRADE, RISER RING, AS PER PLAN	5.00	EACH
20	642E00500	STOP LINE, TYPE 1	71.00	FT
21	642E00600	CROSSWALK LINE, TYPE 1	278.00	FT
22	999s99998	CONTINGENCY/DISCRETIONARY ALLOWANCE	1.00	LS