



To: All Plan Holders of Record

From: CT Consultants, Inc.  
for the Owner

**Re: Addendum No. 1  
Genoa 2020 Street Program  
Village of Genoa**

Date: July 14, 2020

This Addendum forms a part of the contract documents and modifies the original bidding documents dated July 2020 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

**PROJECT SPECIFICATIONS / DETAILS:**

- Bid Line #4, Item 251 Partial Depth Pavement Repair: The bid price shall be based on a repair depth of 2-1/2"
- Bid Item #5, Item 253 Full Depth Pavement Repair : The bid price shall be based on a repair depth of 4-1/2" of Asphalt Concrete over 8" of #304 Aggregate Base

**BID FORM SPREADSHEET**

An Excel spreadsheet of the bid form is available from Becker Impressions for the bidders use. This spreadsheet is made available as a courtesy. *It is the bidder's responsibility to verify that all aspects of the spreadsheet are correct and match the published bid form.*

RH/rgf  
Attachments



2020 PAVING PROGRAM (N. MAIN ST., FROM 15TH ST. TO SR51)

VILLAGE OF GENOA, OHIO

PROJECT #200266

BID OPENING DATE: JULY 22, 2020 @ 11:00 AM

Item No.	Spec. No.	ITEM	Estimated Quantity	Unit of Measure	UNIT COST	UNIT COST TOTAL
1	202	WALK AND CURB RAMP REMOVED	808	SF		
2	202	CURB AND GUTTER REMOVED	144	FT		
3	204	PROOF ROLLING	2	HR		
4	251	PARTIAL DEPTH PAVEMENT REPAIR, (2-1/2")	50	SY		
5	253	FULL DEPTH PAVEMENT REPAIR, (4-1/2")	50	SY		
6	254	PAVEMENT PLANING, ASPHALT CONCRETE (1-1/2")	3,941	SY		
7	407	TACK COAT	372	GAL		
8	441	ASPHALT CONCRETE SURFACE, TYPE 1 (448), PG64-22 (1-1/2" THICK)	172	CY		
9	608	CURB RAMP	536	SF		
10	608	5" CONCRETE WALK	173	SF		
11	608	6" CONCRETE WALK (in Traffic Island)	99	SF		
12	609	COMBINATION CURB AND GUTTER, TYPE 2	97	FT		
13	609	CURB, TYPE 6	47	FT		
14	614	MAINTAINING TRAFFIC	1	LS		
15	632	DETECTOR LOOP, AS PER PLAN	4	EA		
16	632	LOOP DETECTOR TIE-IN	4	EA		
17	632	CENTER LINE, TYPE 1	0.18	MI		
18	642	CHANNELIZING LINE, 8", TYPE 1	115	FT		
19	642	TRANSVERSE / DIAGONAL LINE, 24", TYPE 1	112	FT		
20	642	ISLAND MARKING, TYPE 1	72	SF		
21	642	LANE ARROW, TYPE 1	3	EA		



**2020 PAVING PROGRAM (N. MAIN ST., FROM 15TH ST. TO SR51)**  
**VILLAGE OF GENOA, OHIO**  
**PROJECT #200266**  
**BID OPENING DATE: JULY 22, 2020 @ 11:00 AM**

Item No.	Spec. No.	ITEM	Estimated Quantity	Unit of Measure	UNIT COST	UNIT COST TOTAL
22	642	WORD ON PAVEMENT, 96", TYPE 1	1	EA		
23	642	LANE ARROW, TYPE 1	3	EA		
24	642	DOTTED LINE, 4", TYPE 1	62	FT		
25	642	STOP LINE, 24", TYPE 1	85	FT		
26	642	CROSSWALK, TYPE 1	459	FT		
27	624	MOBILIZATION	1	LS		
28	659	SEEDING AND MULCHING, APP	1	LS		
<b>TOTAL CONTRACT BID</b>						