

1	103s00011	PRECONSTRUCTION VIDEO DOCUMENTATION, AS PER PLAN	1.00	LS
2	201E21801	TREE REMOVED, 18 INCH SIZE, AS PER PLAN	11.00	EACH
3	201E26533	STUMP REMOVED, AS PER PLAN	11.00	EACH
4	204e13131	EXCAVATION OF SUBGRADE AND EMBANKMENT WITH GRANULAR MATERIAL, CCS, AS PER PLAN, CONTINGENCY, AS DIRECTED	140.00	CY
5	251e01301	PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	10.00	CY
6	253s03100	TYPE "A" PAVEMENT REPLACEMENT (CONCRETE), ROADWAY, AS PER PLAN	5.00	SY
7	253s03200	TYPE "B" PAVEMENT REPLACEMENT (ASPHALT OVER CONCRETE), ROADWAY, AS PER PLAN	100.00	SY
8	254E01001	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN	3,900.00	SY
9	255e10170	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS, T=8", AS PER PLAN	475.00	SY
10	407E20205	TACK COAT, TRACKLESS TACK	600.00	GAL
11	409s95000	ASPHALT PRESERVATIVE SEAL, AS PER PLAN	3,900.00	SY
12	441E50001	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22, AS PER PLAN	220.00	CY
13	441E50201	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), AS PER PLAN	165.00	CY
14	450s00010	SPECIAL - CONCRETE SEALING SURFACE TREATMENT, SINAK, AS PER PLAN	5,200.00	SY
15	450e41010	SPECIAL - PAVEMENT REINFORCING FABRIC - FIBERGLASS/POLYESTER BLEND, AS PER PLAN	3,900.00	SY
16	452e10121	6 INCH NON-REINFORCED CONCRETE DRIVES AND APRONS, CLASS QC MS, INCL. FIBER REINFORCING, INCLUDING REMOVAL, AS PER PLAN	425.00	SY
17	603s98143	10 INCH CONDUIT POINT REPAIR, AS PER PLAN	1.00	EACH
18	603s98181	CONDUIT POINT REPAIRS, LATERAL RECONNECTION, AS PER PLAN	2.00	EACH
19	605E05211	4 INCH UNCLASSIFIED PIPE UNDERDRAIN, WITH FABRIC WRAP, AS PER PLAN	400.00	FT
20	608e10011	4 INCH CONCRETE WALK, INCLUDING REMOVAL, AS PER PLAN	5,000.00	SF
21	609e26011	CURB, TYPE 6, INCLUDING REMOVAL, AS PER PLAN	400.00	FT
22	611e01593	6 INCH SANITARY SEWER, PVC, AS PER PLAN	200.00	FT
23	611e01594	6 INCH SANITARY SEWER, DIP, AS PER PLAN	200.00	FT
24	611e01700	6 INCH STORM SEWER, AS PER PLAN	300.00	FT
25	611e05221	12" STORM SEWER, AS PER PLAN	13.00	FT
26	611e97201	CONDUIT, MISC.: CONNECTION TO EXISTING PIPE	1.00	EACH
27	611e98625	CATCH BASIN WITH SUMP & TRAP, AS PER PLAN	2.00	EACH
28	611e98627	CATCH BASIN ADJUSTED TO GRADE, METHOD D.1 (brick), AS PER PLAN	7.00	EACH
29	611e98636	CATCH BASIN PARTIALLY RECONSTRUCTED TO GRADE, AS PER PLAN	5.00	VERT FT
30	611e99656	MANHOLE ADJUSTED TO GRADE, METHOD D.1 (brick), AS PER PLAN	8.00	EACH
31	611e99672	MANHOLE PARTIALLY RECONSTRUCTED TO GRADE, AS PER PLAN	5.00	VERT FT
32	611E99820	SPECIAL - MISCELLANEOUS METAL	7,300.00	LB
33	614E11001	MAINTAINING TRAFFIC, AS PER PLAN	1.00	LS
34	623E39500	MONUMENT BOX ADJUSTED TO GRADE	1.00	EACH
35	630E85101	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION, AS PER PLAN	3.00	EACH
36	638e00010	ABANDON EXISTING WATER MAIN, AS PER PLAN	1.00	LS
37	638e00016	CONNECT NEW WATER MAIN TO EXISTING WATER MAIN, AS PER PLAN	1.00	EACH
38	638e04906	1 INCH COPPER SERVICE BRANCH (LONG), AS PER PLAN	27.00	EACH
39	638e04907	1 INCH COPPER SERVICE BRANCH (SHORT), AS PER PLAN	28.00	EACH
40	638e06126	LEAD WATER SERVICE REPLACEMENT, FROM CURB BOX/METER TO HOUSE VALVE/METER, AS DIRECTED	250.00	FT
41	638E07900	8 INCH GATE VALVE AND VALVE BOX	2.00	EACH
42	638e10220	6 INCH FIRE HYDRANT ASSEMBLY, INCLUDING 6 INCH VALVE AND VALVE BOX, TYPE B, AS PER PLAN	5.00	EACH
43	638e10705	FIRE HYDRANT & VALVE BOX REMOVED AND DISPOSED, AS PER PLAN	5.00	EACH
44	638E10801	VALVE BOX ADJUSTED TO GRADE, AS PER PLAN	1.00	EACH
45	638e10811	VALVE BOX ADJUSTED TO GRADE, RISER RING, AS PER PLAN	1.00	EACH
46	638E40206	8 INCH WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, PUSH-ON JOINTS AND CAST IRON MECHANICAL JOINT FITTINGS, AS PER PLAN	1,320.00	FT
47	638e44123	WATER METER AND METER BOX, AS PER PLAN	1.00	EACH
48	638e44212	FLUSHING ASSEMBLY, AS PER PLAN	1.00	EACH
49	659s10010	LAWN RESTORATION INCL. LINEAL GRADING & TOPSOIL, AS PER PLAN	1.00	LS
50	690E12010	GEOTEXTILE FABRIC, 712.09 TYPE D	800.00	SY
51	690s12530	SPECIAL - VOID REDUCING ASPHALT MEMBRANE (VRAM)	1,350.00	FOOT
52	832s30025	TEMPORARY SEDIMENT AND EROSION CONTROL, AS PER PLAN	1.00	LS
53	999S99993	GAS COMPANY CHARGES ALLOWANCE	1.00	LS
54	999s99998	CONTINGENCY/DISCRETIONARY ALLOWANCE	1.00	LS