

**PROPOSAL TO VILLAGE OF JOHNSTOWN
FOR CROTON ROAD WATERLINE EXTENSION**

BASE BID

PROJECT NO. 20034508

REF. NO	COC REF NO	DESCRIPTION - BASE BID	QTY	UNIT
1	201	CLEARING AND GRUBBING, AS PER PLAN	1	LS
2	202	FENCE REMOVED FOR REUSE, AS PER PLAN	214	LF
3	202	CURB AND GUTTER REMOVED	10	LF
4	253	PAVEMENT REPAIR (ASPHALT DRIVEWAY)	20	SY
5	253	PAVEMENT REPAIR (GRAVEL DRIVEWAY)	104	SY
6	254	PAVEMENT PLANING, ASPHALT CONCRETE	466	SY
7	407	TACK COAT (.06 GAL/SY)	28	GAL
8	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 (T=1.25")	17	CY
9	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448), PG64-22 (T=1.75")	23	CY
10	609	COMBINATION CURB AND GUTTER	10	LF
11	614	MAINTAINING TRAFFIC	1	LS
12	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	1	LS
13	624	MOBILIZATION	1	LS
14	801	6" WATER PIPE AND FITTINGS	125	LF
15	801	12" WATER PIPE AND FITTINGS (DR 18 CL235 C905 PVC)	49	LF
16	801	16" WATER PIPE AND FITTINGS (DR 18 CL235 C905 PVC)	10737	LF
17	802	6" VALVE AND APPURTENANCES	14	EA
18	802	12" VALVE AND APPURTENANCES	1	EA
19	802	16" BUTTERFLY VALVE AND APPURTENANCES	11	EA
20	809	6" FIRE HYDRANT	10	EA
21	SPEC	8'-6" X 8' METER VAULT	1	EA

REF. NO	COC REF NO	DESCRIPTION - BASE BID	QTY	UNIT
22	SPEC	6" DOUBLE CHECK ASSEMBLY	1	EA
23	SPEC	SITE RESTORATION	1	LS
24	SPEC	SEDIMENT AND EROSION CONTROL	1	LS
25	SPEC	HDD PIPE INSTALLATION	60	LF
26	SPEC	SURVEY COORDINATES	1	LS

REF. NO	COC REF NO	DESCRIPTION - ALTERNATES	QTY	UNIT
A1	201	12" WATER PIPE AND FITTINGS (DIP ANSI CLASS 53)	49	LF
A2	202	16" WATER PIPE AND FITTINGS (DIP ANSI CLASS 53)	10737	LF