

---

***SECTION 5***  
***SPECIFICATIONS***

---

## SECTION 011100 - SUMMARY OF WORK

### PART 1 - GENERAL

#### 1.1 LOCATION OF THE PROJECT

- A. The project is located in the City of Conneaut, Ashtabula County, Ohio on Buffalo Street, from Adams Street to Jefferson Street.

#### 1.2 PROJECT DESCRIPTION

- A. The project consists of the following:

The replacement of a 10” sanitary sewer with new 10” sewer, steel casing bore under a railroad, manholes, televising, erosion control and site restoration.

#### 1.3 SPECIFICATIONS

- A. In general, these Specifications describe the work to be performed by the various trades, other than work specifically excluded. It shall be the responsibility of the Contractor and Subcontractors to perform all work incidental to their trade, whether or not specific mention is made of each item, unless such incidentals are included under another Item.
- B. It is advised that the Contractor and all Subcontractors familiarize themselves with the contents of the complete Specifications, particularly for the trades preceding, following, related or adjacent to their work.

#### 1.4 DRAWING SCHEDULE

- A. The work to be done under this Contract is shown on the following Drawings:

<u>Title</u>	<u>Sheet No.</u>
Cover Sheet	1
General Notes	2
Details	3
Survey Control	4
Existing Conditions	5
Plan and Profile	6

END OF SECTION 011100

## SECTION 011419 – USE OF SITE

### PART 1 - GENERAL

#### 1.1 GENERAL

- A. The Contractor will be allowed the use of as much of the site designated for the improvements as is necessary for his operation.

#### 1.2 USE OF STREETS

- A. During the progress of the work, the Contractor shall make ample provisions for both vehicle and pedestrian traffic on any public street and shall indemnify and save harmless the Owner from any expense whatsoever due to their operations over said streets. The Contractor shall also provide free access to all the fire hydrants, water, and gas valves located along the line of his work. Gutters and waterways must be kept open or other provisions made for the removal of storm water. Street intersections may be blocked only one-half at a time, and the Contractor shall lay and maintain temporary driveways, bridges and crossings, such as in the opinion of the Engineer are necessary to reasonably accommodate the public.
- B. In the event of the Contractor's failure to comply with these provisions, the Owner may cause the same to be done, and may deduct the cost of such work from any monies due the Contractor under this Agreement, but the performance of such work by the Owner at its instance shall serve in no way to release the Contractor from his general or particular liability for the safety of the public or the work.
- C. The Contractor shall repair at no cost to the Owner, all existing roads, parking areas, grassed areas that are damaged due to the execution of his work. The Contractor shall remove daily all mud, soil and debris that may be tracked onto existing streets, drives, or walks by his equipment or that of subcontractors or suppliers.

#### 1.3 CLOSING STREETS TO TRAFFIC

The Contractor may, with the approval of the Engineer, close streets, or parts of streets, to vehicular traffic. The streets are to remain closed as long as the construction work or the condition of the finished work requires or as determined by the Engineer. The Engineer shall be the judge of how many streets or parts of streets it is necessary for the Contractor to close at any time, and may refuse to permit the closing of additional streets to traffic until the majority of the work on the closed streets is completed and they are opened to traffic.

#### 1.4 RIGHTS-OF-WAY

- A. Whenever it is required to perform work within the limits of public or private property or in rights-of-way, such work shall be done in conformity with all agreements between the Owner and the owners of such. Care shall be taken to avoid injury to the premises entered, which premises shall be left in a neat and orderly condition by the removal of rubbish and the grading of surplus materials, and the restoration of said public or private property to the same general conditions as pertained at the time of entry for work to be performed under this contract.
- B. The Contractor shall not (except after consent from the proper parties) enter or occupy with men, tools or equipment, any land outside the rights-of-way or property of the Owner.
- C. When the Contractor performs construction within 10 ft. of a right-of-way or easement line, he shall place tall stakes properly identified at points of change in width or direction of the right-of-way or easement line and at points along the line so that at least two stakes can be seen distinctly from any point on the line.

#### 1.5 EASEMENTS

- A. Where the work is to be constructed upon easements, such easements will be secured by the Owner without cost to the Contractor. The Contractor shall not enter upon or occupy any private property outside of the limits of the easements furnished.
- B. Care shall be taken to avoid injury to the premises entered, which premises shall be left in a neat and orderly condition by the removal of rubbish and the grading of surplus materials, and the restoration of said public or private property to the same general conditions as pertained at the time of entry for work to be performed under this contract.

#### 1.6 PROTECTING EXISTING BUILDINGS, STRUCTURES AND ROADWAYS

- A. The Contractor shall, at his own expense, shore up and protect any buildings, roadways, utilities or other public or private structures which may be encountered or endangered in the prosecution of the work, and that may not be otherwise provided for, and he shall repair and make good any damages caused to any such property by reason of his operations. All existing fences removed due to the prosecution of the work shall be replaced by the Contractor. No extra payment will be made for said work or material, but the cost of this work must be included in the price stipulated for the work to be done under this contract.

#### 1.7 SITE FACILITIES

- A. The Contractor shall furnish and place sufficient quantities of portable toilet facilities at locations convenient for use by the Contractor's personnel, Subcontractors, the Engineer, and the Owner.

1.8 RESTORATION

- A. On all contract items that require and include surface restoration including repairs to driveways and roads outside trench limits, an amount equal to 10% of the unit price bid for sewer and/or waterline items will be considered the value of this work.
- B. As work is completed, the payment for each contract item will be reduced by the 10% until full performance of all contract requirements.
- C. Partial release of the 10% restoration money may be made by the Engineer commensurate with his determination of the value of said work.
- D. If, in the opinion of the Engineer, the value of the restoration exceeds 10% of the contract line item, he may require a greater amount to be held but not in excess of 25%.
- E. The amount held for restoration shall not be considered retainage of completed work but rather the value of work not yet performed and therefore not eligible for payment.
- F. On lump sum items or contracts, the value of the restoration work will be determined by the approved schedule of values submitted by the Contractor.

END OF SECTION 011419

## SECTION 012513 – PRODUCT SUBSTITUTION PROCEDURES

### PART 1 - GENERAL

#### 1.1 MATERIALS AND EQUIPMENT

- A. In the specifications and on the Engineer's drawings, are specified and shown certain pieces of equipment and materials deemed most suitable for the service anticipated. This is not done to eliminate other equipment and materials equally as good and efficient. The Contractor shall prepare his bid on the particular materials and equipment specified. Following the award of the contract, should the Contractor desire to use other equipment and materials, he shall submit to the Owner a written request for such change and state the advantage to the Owner and the savings or additional cost involved by the proposed substitution. The determination as to whether or not such change will be permitted rests with the Owner and the Engineer.

END OF SECTION 012513

## SECTION 013119 - PROJECT MEETINGS

### PART 1 - GENERAL

#### 1.1 PRECONSTRUCTION MEETING

- A. Prior to the Contractor beginning any work on the project, the Owner will schedule and hold a preconstruction meeting to discuss all aspects of the contract work.
- B. The Contractor shall be present and be prepared to comment in detail on all aspects of his work.
- C. The Contractor shall bring to the preconstruction meeting a proposed construction progress schedule, erosion control plan, quality control program, asphalt mix designs (JMF), etc. Approval of each by the Engineer is required prior to the start of any work.
- D. Included in the construction progress schedule shall be an implementation sequence of the proposed erosion control efforts required by the contract.

END OF SECTION 013119

## SECTION 013223.02 – SURVEY AND LAYOUT DATA

### PART 1 - GENERAL

#### 1.1 REFERENCE POINTS AND STAKING

- A. The Owner shall provide engineering surveys for construction to establish reference points which, in his judgment, are necessary to enable the Contractor to proceed with the work. The Contractor shall be responsible for surveying and laying out the work and shall protect and preserve the established reference points and shall make no changes or relocations without the prior written approval of the Engineer. He shall report to the Engineer whenever any reference point is lost or destroyed or requires relocation because of necessary changes in grades or locations. The Contractor shall replace and accurately relocate all reference points so lost, destroyed or moved.

#### 1.2 LAYOUT OF WORK

- A. The Contractor shall lay out his work and be responsible for correct locations, elevations and dimensions of all work executed by him under this Contract. The Contractor must exercise proper precautions to verify the figures shown on the Drawings before laying out the work and will be held responsible for any error resulting from his failure to exercise such precaution. The Contractor shall employ a competent surveyor to establish lines and grades to insure the new construction aligns with any existing work.

END OF SECTION 013223.02



## SECTION 013236 – VIDEO MONITORING AND DOCUMENTATION

### PART 1 - GENERAL

#### 1.1 SCOPE

- A. Provide all labor, materials, equipment, and services, and perform all operations necessary to furnish to the Owner a complete color audio-video DVD record of the surface features within the proposed construction zone of influence. This record shall include, but not be limited to, all audio-video DVDs, storage cases, video logs, and indexes. The purpose of this coverage shall be to accurately document the pre-construction condition of these surface features.

#### 1.2 QUALIFICATIONS

- A. The video DVD documentation shall be done by a responsible commercial firm known to be skilled and regularly engaged in the business of pre-construction color audio-video DVD documentation. The firm shall furnish such information as the Owner deems necessary to determine the ability of that firm to perform the work in accordance with the Contract specifications.

#### 1.3 PRODUCTS

- A. The color audio-video recording delivered to the Owner shall be on a high quality DVD format.

END OF SECTION 013236

SECTION 013319.01 - FIELD TEST REPORTING  
- AGGREGATE, SOILS, CONCRETE AND ASPHALT

PART 1 - GENERAL

1.1 SUMMARY

- A. The Contractor shall be responsible for the quality of all materials incorporated into the project work and shall be responsible for all costs for testing and certification of same.
- B. The Contractor shall provide the engineer with a Quality Control Plan in which his testing methods/procedures are defined. Said Plan shall meet with the approval of the Engineer and include identification of laboratories, types of testing, and the tentative amount and scheduling of each.

All certification of tests and/or gradations for material to be utilized in the work and all quality control testing shall be performed by an independent laboratory (not affiliated with, owned by, or managed by the Contractor). The laboratory shall be accredited by the AASHTO Materials Reference Laboratory for the type of testing performed.

- C. The Owner may perform field Quality Assurance testing; however, such testing shall not relieve the Contractor from the responsibility of Quality Control testing or from supplying certificates from manufacturers or suppliers to demonstrate compliance with the specifications. It is intended that the testing by the Contractor and the Owner be complimentary toward a quality project; however, the Contractor may not assume the Owner will test or that any tests will be done in lieu of the Contractor's own Quality Control testing. In the same sense, the Contractor may not rely on Owner Quality Assurance testing as a basis of acceptance or approval of his work nor may any Owner-performed testing be reflected in his submitted plan.

1.2 TEST CRITERIA

- A. The following tests at a minimum shall be included with the Contractor's Quality Control Plan in accordance with the specifications:
  - 1. Aggregates
    - a. For each material and/or different source, the laboratory shall perform soundness, gradation, and other tests for all parameters specified. Aggregates incorporated into concrete or asphalt mixes shall also be tested for moisture content daily.
  - 2. Compaction Tests
    - a. Compaction tests or field density tests shall be taken on all embankment, trench backfill, subgrade, and subbase materials.

- b. Minimum testing shall be as follows:  
Embankment testing shall be at least one (1) test/5,000 SF of each lift; Trench backfill testing shall be at least one (1) test/50 LF of each lift; Subgrade and/or subbase testing shall be at least one (1) test/200 LF of pavement or 5,000 SF of slabs; subject to greater frequency due to soil conditions or Engineer's direction.
  - c. Proctors or relative density tests shall be performed as often as necessary for the differing soils or granular materials utilized. Proctors shall be run with a minimum of 5 points. Test reports shall show the wet (bulk) weight, dry weight, wet (bulk) density, dry density, moisture content weight and moisture content percentage. Both the dry curve and the wet curve shall be plotted.
3. Concrete Mix Design
- a. For each type of concrete, the laboratory shall perform the necessary mix design providing all test data as required by the specifications.
4. Concrete Field and Laboratory Tests
- a. The laboratory shall cast concrete cylinders and test beams:
    - 1. One set of four cylinders per 50 CY with a minimum of two sets per day. The cylinders shall be broken: one at 7 days, two at 28 days, one at 56 days, unless otherwise directed by the Engineer.
    - 2. One beam per 50 CY with a minimum of two beams per day.
  - b. Temperature and unit weight shall be run on fresh concrete at intervals sufficient for the type of structure being placed and a minimum of once per day. Bulk weight, bucket weight, (tare), net weight, bucket factor (bucket volume) and unit weight shall be recorded on the fresh concrete report. Slump and air content tests shall be taken a minimum of one test per 20 CY and at least once per day.
  - c. All field and laboratory testing shall be performed by technicians certified by the American Concrete Institute (ACI) for the type of testing performed.
  - d. Initial cure of all cylinders shall be in a temperature controlled cure box or temperature controlled water tank with a hi-low thermometer. Hi-low temperature readings shall be recorded on the fresh concrete report.
5. Asphalt Mix Design
- a. For each type of asphalt mix, submit job mix formula (JMF) prepared by an ODOT pre-qualified laboratory from tests performed on the aggregates proposed for use.
  - b. Sample and test for gradation and bitumen content per ODOT 441.

### 1.3 LABORATORY REPORTS

- A. Reports of laboratory and field tests will be distributed to the Engineer, Owner, and Suppliers within 24 hours of completion.

END OF SECTION 013319.01

## SECTION 013323 - SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

### PART 1 - GENERAL

#### 1.1 GENERAL

- A. The Contractor shall submit detailed drawings, acceptable catalog data, specifications and material certifications for all equipment and materials specified or required for the proper completion of the work.
- B. The intent of these items is to demonstrate compliance with the design concept of the work and to provide the detailed information necessary for the fabrication, assembly and installation of the work specified. It is not intended that every detail of all parts of manufactured equipment be submitted, however sufficient detail will be required to ascertain compliance with the specifications and establish the quality of the equipment proposed.

Shop Drawings shall be sufficiently clear and complete to enable the Engineer/Architect and Owner to determine that items proposed to be furnished conform to the specifications and that items delivered to the site are actually those that have been reviewed.

- C. It is emphasized that the Engineer/Architect's review of Contractor's submitted data is for general conformance to the contract drawings and specifications but subject to the detailed requirements of drawings and specifications. Although the Engineer/Architect may review submitted data in detail, such review is an effort to discover errors and omissions in Contractor's drawings. The Engineer/Architect's review shall in no way relieve the Contractor of his obligation to properly coordinate the work and to Engineer/Architect the details of the work in such manner that the purposes and intent of the contract will be achieved. Such review by the Engineer/Architect shall not be construed as placing on him or on the Owner any responsibility for the accuracy and for proper fit, functioning or performance of any phase of the work included in the contract.
- D. Shop Drawings shall be submitted in proper sequence and with due regard to the time required for checking, transmittal and review so as to cause no delay in the work. The Contractor's failure to transmit appropriate submittals to the Engineer/Architect sufficiently in advance of the work shall not be grounds for time extension.
- E. The Contractor shall submit Shop Drawings for all fabricated work and for all manufactured items required to be furnished in the Contract in accordance with the General Provisions and as specified herein. Shop Drawings shall be submitted in sufficient time to allow at least twenty-one (21) calendar days after receipt of the Shop Drawings from the Contractor for checking and processing by the Engineer/Architect.
- F. It is the responsibility of each Prime Contractor to furnish to all other Prime Contractors and especially the General Construction Contractor reviewed Shop Drawings for guidance in interfacing the various trades; i.e., sleeves, inserts, anchor bolts, terminations, and space requirements.

- G. No work shall be performed requiring Shop Drawings until same have been reviewed by Engineer/Architect.
- H. Accepted and reviewed Shop Drawings shall not be construed as approval of changes from Contract plan and specification requirements.
- I. The Engineer/Architect will review the first and second Shop Drawing item submittals at no cost to the Contractor. Review of the third submittal and any subsequent submittal will be at the Contractor's expense. Payment will be deducted from the Contract amount at a rate of 2.8 times direct labor cost plus expenses.

## 1.2 SUBMITTAL PROCEDURE

- A. All required submissions shall be made to the Engineer/Architect by the Prime Contractor(s) only. Any data prepared by subcontractors and suppliers and all correspondence originating with subcontractors, suppliers, etc., shall be submitted through the Contractor.
- B. Contractor shall review and approve all Shop Drawings prior to submission. Contractor's approval shall constitute a representation to Owner and Engineer/Architect that Contractor has either determined and verified all quantities, dimensions, field construction criteria, materials, catalog numbers, and similar data or assumes full responsibility for doing so, and that Contractor has reviewed or coordinated each Shop Drawing or sample with the requirements of the work and the Contract Documents.
- C. Submittal Preparation: Mark each submittal with a permanent label or page for identification. Provide the following information on the label for proper processing and recording of action taken:
  - 1. Location
  - 2. Project Name
  - 3. Contract
  - 4. Name and Address of Engineer/Architect
  - 5. Name and Address of Contractor
  - 6. Name and Address of Subcontractor
  - 7. Name and Address of Supplier
  - 8. Name of Manufacturer
  - 9. Number and Title of appropriate Specification Section
  - 10. Drawing Number and Detail References, as appropriate.
  - 11. Submittal Sequence or Log Reference Number.
    - a. Provide a space on the label for the Contractor's review and approval markings and a space for the Engineer/Architect's "Action Stamp".
- D. Each Shop Drawing, sample and product data submitted by the Contractor shall have affixed to it the following Certification Statement including the Contractor's Company name and signed by the Contractor:

Certification Statement: By this submittal, I hereby represent that I have determined and verified all field measurements, field construction criteria, materials, dimensions, catalog numbers and similar data and I have checked and coordinated each item with other applicable approved shop drawings and all Contract requirements.

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Company

- E. Shop Drawings shall be submitted in not less than six (6) copies to the Engineer/Architect at the address specified at the Preconstruction Conference. Single mylar or sepia reproducible copies of simple Shop Drawings may be submitted with prior approval of the Engineer/Architect.
- F. At the time of each submission, Contractor shall in writing identify any deviations that the Shop Drawings or samples may have from the requirements of the Contract Documents.
- G. Drawings shall be clean, legible and shall show necessary working dimensions, arrangement, material finish, erection data, and like information needed to define what is to be furnished and to establish its suitability for the intended use. Specifications may be required for equipment or materials to establish any characteristics of performance where such are pertinent. Suitable catalog data sheets showing all options and marked with complete model numbers may, in certain instances, be sufficient to define the articles which it is proposed to furnish.
- H. For product which require submittal of samples, furnish samples so as not to delay fabrication, allowing the Engineer reasonable time for the consideration of the samples submitted. Properly label samples, indicating the material or product represented, its place of origin, the names of the vendor and Contractor and the name of the project for which it is intended. Ship samples prepaid. Accompany samples with pertinent data required to judge the quality and acceptability of the sample, such as certified test records and, where required for proper evaluation, certified chemical analyses.

### 1.3 REVIEW PROCEDURE

- A. Engineer/Architect will review with reasonable promptness all properly submitted Shop Drawings. Such review shall be only for conformance with the design concept of the Project and for compliance with the information given in the plans and specifications and shall not extend to means, methods, sequences, techniques or procedures of construction or to safety precautions or programs incident thereto.
- B. The review of a separate item as such will not constitute the review of the assembly in which the item functions. The Contractor shall submit entire systems as a package.
- C. All Shop Drawings submitted for review shall be stamped with the Engineer/Architect's action and associated comments.

- D. Except for submittals for record, information or similar purposes, where action and return is required or requested, the Engineer/Architect will review each submittal, mark to indicate action taken, and return accordingly. Compliance with specified characteristics is the Contractor's responsibility.

Action Stamp: The Engineer/Architect will stamp each submittal with a uniform, self-explanatory action stamp. The stamp will be appropriately marked, as follows, to indicate the action taken:

1. If Shop Drawings are found to be in general compliance, such review will be indicated by marking the first statement.
  2. If only minor notes in reasonable number are needed, the Engineer/Architect will make same on all copies and mark the second statement. Shop Drawings so marked need not be resubmitted.
  3. If the submitted Shop Drawings are incomplete or inadequate, the Engineer/Architect will mark the third statement, request such additional information as required, and explain the reasons for revision. The Contractor shall be responsible for revisions, and/or providing needed information, without undue delay, until such Shop Drawings are acceptable. Shop Drawings marked with No. 3 shall be completed resubmitted.
  4. If the submitted Shop Drawings are not in compliance with the Contract Documents, the Engineer/Architect will mark the fourth statement. The Contractor will be responsible to submit a new offering conforming to specific products specified herein and/or as directed per review citations.
- E. No submittal requiring a Change Order for either value or substitution or both, will be returned until the Change Order is approved or otherwise directed by the Owner.



## APPLICATION FOR USE OF SUBSTITUTE ITEM

TO: \_\_\_\_\_

PROJECT: \_\_\_\_\_

SPECIFIED ITEM:

Page	Paragraph	Description
A.		The undersigned requests consideration of the following as a substitute item in accordance with Article 6.05 of the General Conditions.
B.		Change in Contract Price (indicate + or -) \$ _____
C.		Attached data includes product description, specifications, drawings, photographs, references, past problems and remedies, and performance and test data adequate for evaluation of the request; applicable portions of the data are clearly identified. For consideration of the attached data as SHOP DRAWINGS, submittal shall be in accordance with requirements of Section 013323.
D.		Attached data also includes a description of changes to the Contract Documents that the proposed substitution will require for its proper installation.

The undersigned certifies that the following paragraphs, unless modified by attachments are correct:

1. The proposed substitute does not affect dimensions shown on Drawings.
2. The undersigned will pay for changes to the building design, including engineering design, detailing, and construction costs caused by the requested substitution.
3. The proposed substitution will have no adverse affect on other contractors, the construction schedule, or specified warranty requirements. (If proposed substitution affects construction schedule, indicate below using + or -)

\_\_\_\_\_ CONSECUTIVE CALENDAR DAYS

4. Maintenance and service parts will be locally available for the proposed substitution.

The undersigned further states that the function, appearance, and quality of the proposed substitution are equivalent or superior to the specified item, and agrees to reimburse the OWNER for the charges of the ENGINEER for evaluating this proposed substitute item.

E. Signature:

Firm:

Address:

Telephone:

Date:

Attachments:

For use by ENGINEER:

\_\_\_\_\_ Accepted as evidenced by affixed SHOP DRAWING REVIEW stamp.

\_\_\_\_\_ Accepted as evidenced by included CHANGE ORDER.

\_\_\_\_\_ Not accepted as submitted. See Remarks.

\_\_\_\_\_ Acceptance requires completion of submittal as required for SHOP DRAWINGS.

\_\_\_\_\_ Not accepted. Do not resubmit.

By:

Date:

Remarks:

# APPLICATION FOR USE OF "OR-EQUAL" ITEM

TO: \_\_\_\_\_

PROJECT: \_\_\_\_\_

SPECIFIED ITEM:

Page	Paragraph	Description
------	-----------	-------------

A. The undersigned requests consideration of the following as an "or-equal" item in accordance with Article 6.05 of the General Conditions.

B. Change in Contract Price (indicate + or -) \$ \_\_\_\_\_

C. Attached data includes product description, specifications, drawings, photographs, references, past problems and remedies, and performance and test data adequate for evaluation of the request; applicable portions of the data are clearly identified. For consideration of the attached data as SHOP DRAWINGS, submittal shall be in accordance with requirements of Section 013323.

D. Signature:

Firm:

Address:

Telephone: \_\_\_\_\_

Date: \_\_\_\_\_

Attachments: \_\_\_\_\_

For use by ENGINEER:

\_\_\_\_\_ Accepted as evidenced by affixed SHOP DRAWING REVIEW stamp.

\_\_\_\_\_ Accepted as evidenced by included CHANGE ORDER.

\_\_\_\_\_ Not accepted as submitted. See Remarks.

\_\_\_\_\_ Acceptance requires completion of submittal as required for SHOP DRAWINGS.

\_\_\_\_\_ Not accepted. Do not resubmit.

By: \_\_\_\_\_ Date: \_\_\_\_\_

Remarks: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

END OF SECTION 013323

## SECTION 013326 – PRODUCT TESTING AND CERTIFYING

### PART 1 - GENERAL

#### 1.1 QUALITY OF MATERIALS

- A. Where the specifications call for mill or shop tests, the Contractor shall furnish duplicate copies of attested manufacturer's certificates showing details of quality or performance sufficient to demonstrate conformity to contract requirements. Mill, shop or witness tests shall be subject to view by the Engineer's representative, but the Engineer's representation shall not relieve the Contractor from the necessity of furnishing certificates specified. The Engineer shall be notified by the Contractor in writing, sufficiently in advance of the time of making tests, so that proper arrangements may be made. Waiving of witness of tests by the Engineer may be in writing only by the Engineer. All costs for travel, lodging, food and transportation that are necessary for the Engineer's representative and the Owner's representative to attend witness tests shall be included in the Contractor's bid for those item(s) specifically designated as being subject to witness testing.
- B. Unless otherwise specified, all materials, equipment and articles shall be erected, installed, applied, or connected, used, cleaned and conditioned in accordance with the printed instructions and directions of the manufacturer.
- C. The installation shall be so made that its several component parts will function together as a workable system. It shall be complete with all accessories necessary for its operation and shall be left with all equipment properly adjusted and in working order.
- D. The work shall be executed in conformity with the best practice and so as to contribute to efficiency of operation, minimum maintenance, accessibility and sightliness. It shall also be executed so that the installation will conform and accommodate itself to the building structure, its equipment and usage.
- E. Whenever in the contract documents a particular brand, make of material, device or equipment is shown or specified, such brand, make of material, device or equipment is to be regarded merely as a standard and such trade name shall be followed by "or equal".

#### 1.2 QUALITY ASSURANCE

- A. The equipment and materials to be furnished under this Contract shall be the products of well established and reliable firms which have had ample experience for at least five (5) years in the manufacture of equipment or materials similar in design and of equal quality to that specified. If required, the manufacturer shall submit a list of installations of similar equipment which have been in successful operation for at least five (5) years.

END OF SECTION 013326

## SECTION 013543 - ENVIRONMENTAL PROTECTION

### PART 1 - GENERAL

#### 1.1 UNNECESSARY NOISE, DUST AND ODORS

- A. The Contractor's performance of this contract shall be conducted so as to eliminate all unnecessary noise, dust and odors.

#### 1.2 SEWAGE, SURFACE AND FLOOD FLOWS

- A. The Contractor shall take whatever action is necessary to provide all necessary tools, equipment and machinery to adequately handle all sewage, surface flows and flood flows which may be encountered during the performance of the work. The entire cost of and liability for handling such flows is the responsibility of the Contractor and shall be included in the price for the appropriate item.

#### 1.3 WORK IN FREEZING WEATHER

- A. Written permission from the Engineer shall be obtained before any work is performed which, in the judgment of the Engineer, may be affected by frost, cold, or snow. When work is performed under such conditions, the Contractor shall provide facilities for heating the materials and for protecting the finished work.

#### 1.4 POLLUTION CONTROL

- A. It shall be the responsibility of the Contractor to prevent or limit pollution of air and water resulting from his operations.
- B. The Contractor shall perform work required to prevent soil from eroding or otherwise entering onto all paved areas and into natural watercourses, ditches, and public sewer systems. This work shall conform to all local ordinances and/or regulations, if any, and if not otherwise regulated by local ordinances or regulations shall at a minimum conform to the Ohio EPA General Storm Water NPDES Permit for Construction Activities and the Ohio Department of Natural Resources Rainwater and Land Development manual. This work may consist of but not be limited to construction and continual maintenance of silt fence, bio bag filters, sedimentation traps, stilling basins, check dams, temporary seeding, temporary mulching, erosion mats and other means to clarify waters containing suspended materials from excavations, embankments, cleared and grubbed or stripped areas, stockpiles, well points, and disposal sites and shall be commensurate with the contractor's schedule, sequence of work, means and methods. If a SWPPP plan is not required for the project, the contractor shall at a minimum submit a plan of his proposed erosion control prevention methods for approval by the Owner and/or other regulatory authorities having jurisdiction prior to starting any construction activities which may cause erosion.

- C. The Contractor shall perform work required to prevent dust attributable to his operations from entering the atmosphere. Dust on unsurfaced streets or parking areas and any remaining dust on surfaced streets shall be controlled with water and/or calcium chloride dust palliative as needed.
- D. Any material removed from sanitary or storm sewers shall be disposed in accordance with all applicable regulations.

END OF SECTION 013543

## SECTION 014126 - GENERAL REGULATIONS AND PERMITS

### PART 1 - GENERAL

#### 1.1 REGISTRATION

All Contractors and subcontractors shall be registered with the Building Department having jurisdiction. Contact the Building Department for additional registration information.

#### 1.2 ARCHAEOLOGICAL DISCOVERIES

Contractors and subcontractors are required under O.R.C. Section 149.53, to notify the Ohio Historical Society and the Ohio Historic Site Preservation Board of Archaeological Discoveries located in the project area, and to cooperate with those entities in archaeological and historic surveys and salvage efforts if such discoveries are uncovered within the project area.

Contact: Ohio's State Historic Preservation Office  
Diana Welling, Resource Protection & Review Department Manager  
Phone: 1-614-298-2000  
Email: [dwelling@ohiohistory.org](mailto:dwelling@ohiohistory.org)

Should archaeological discoveries or other activities delay progress of the work, an adjustment in contract time will be made.

END OF SECTION 014126



## SECTION 014223 - INDUSTRY STANDARDS

### PART 1 - GENERAL

#### 1.1 ABBREVIATIONS

- A. Abbreviations, as used, designate the following:

AASHTO	-	American Association of State Highway and Transportation Officials
ACI	-	American Concrete Institute
AIEE	-	American Institute of Electrical Engineers
AISC	-	American Institute of Steel Construction
ANSI	-	American National Standards Institute
ASTM	-	American Society of Testing and Materials
AWWA	-	American Water Works Association
CMS	-	Construction and Material Specifications
NEMA	-	National Electrical Manufacturers Association
ODOT	-	Ohio Department of Transportation
ORC	-	Ohio Revised Code
UL	-	Underwriters Laboratories, Inc.

#### 1.2 REFERENCE TO OTHER SPECIFICATIONS

- A. Where reference is made to specifications such as ASTM, AWWA or AASHTO, the latest edition shall be used, unless otherwise noted on the plans or in the specifications.

#### 1.3 CODES AND STANDARDS

- A. All work provided for by these specifications must be installed according to the provisions of the State and local building codes, subject to inspection and acceptance by the State and local inspectors.

END OF SECTION 014223

## SECTION 014323 – QUALIFICATIONS OF TRADESMEN

### PART 1 - GENERAL

#### 1.1 CHARACTER OF WORKMEN AND EQUIPMENT

- A. The Contractor shall employ competent and efficient workmen for every kind of work. Any person employed on the work who shall refuse or neglect to obey directions of the Engineer or his representative, or who shall be deemed incompetent or disorderly, or who shall commit trespass upon public or private property in the vicinity of the work, shall be dismissed when the Engineer so orders, and shall not be re-employed unless express permission be given by the Engineer. The methods, equipment and appliances used on the work and the labor employed shall be such as will produce a satisfactory quality of work, and shall be adequate to complete the contract within the specified time limit.
- B. In hiring of employees for the performance of work under this Contract, or any Subcontract hereunder, no Contractor or Subcontractor, nor any person acting on behalf of such Contractor or Subcontractor, shall, by reason of race, sex, creed or color, discriminate against any citizen of the State of Ohio in the work to which the employment relates. No Contractor, Subcontractor, nor any person on his behalf shall, in any manner, discriminate against or intimidate any employee hired for the performance of work under this contract on account of race, creed, sex or color.

END OF SECTION 014323

## SECTION 015136 - TEMPORARY WATER AND DISTRIBUTION

### PART 1 - GENERAL

#### 1.1 WATER

- A. The Contractor shall be responsible for an adequate supply of water suitable for his use for construction and drinking. At his own expense, he shall provide and maintain adequate supplies and supply lines in such locations and installed in such a manner as may be satisfactory to the Engineer.

END OF SECTION 015136

## SECTION 015213 - FIRST AID

### PART 1 - GENERAL

#### 1.1 AID TO THE INJURED

The Contractor shall keep in his office and on the work site, all articles necessary for giving "First Aid to the Injured." He shall also have standing arrangements for the immediate removal and hospital treatment of any employee or other person who may be injured on the work site.

END OF SECTION 015213

## SECTION 015526 - TEMPORARY TRAFFIC CONTROL DEVICES

### PART 1 - GENERAL

#### 1.1 BARRICADES, SIGNS AND LIGHTS

- A. The Contractor shall employ watchmen on the work when and as necessary. The Contractor shall erect and maintain such strong and suitable barriers and such lights as will effectively prevent the occurrence of any accident to health, limb or property. Lights shall be maintained between the hours of one-half (1/2) hour after sunset and one-half (1/2) hour before sunrise.
- B. No manhole, trench, excavation will be left open awaiting connection or removal at a later date by the Contractor's forces or others but shall be temporarily backfilled and resurfaced if applicable with a temporary pavement passable to traffic at no additional cost to the Owner.
- C. In addition to other safety requirements, a minimum of four (4) foot high fence will be incorporated around any shaft or manhole or other excavation left open at the end of a day's work.

#### 1.2 MAINTENANCE OF TRAFFIC

- A. The Contractor is required to provide maintenance of traffic in conformance with the Ohio Manual of Uniform Traffic Control Devices and Item 614 of the current Construction and Material Specifications of the Ohio Department of Transportation.
- B. This work shall include providing suitable and satisfactorily trained and properly attired flagmen for use at any location where existing roadway is narrowed to a width of less than 2 full lanes (18 feet).
- C. The Contractor is also responsible for maintaining local access to all residences and businesses along the route of the sewer and to provide whatever temporary materials are necessary to provide a safe, adequate drive surface.
- D. At all boring locations, Contractor shall provide suitable flashers, barricades, and traffic control devices as may be deemed necessary by the Engineer or the responsible authority in the case of the Department of Transportation, Turnpike Commission, or Conrail. This may extend to maintain facilities on a 24-hour basis until such time as the areas are completely backfilled.

END OF SECTION 015526

## SECTION 015713 - TEMPORARY EROSION CONTROL

### PART 1 - GENERAL

#### 1.1 SECTION INCLUDES

- A. Furnishing all labor, materials, tools, equipment and services for the temporary soil erosion and sediment control work as indicated.
- B. Coordinating the temporary pollution and erosion control with work of all other trades.
- C. Reducing to the greatest extent practicable the area and duration of exposure of readily erodible soils.
- D. Protecting the soils by use of temporary vegetation or mulch or by accelerating the establishment of permanent vegetation.
- E. Mechanically retarding the rate of runoff from the construction site and control disposal of runoff.
- F. Trapping all sediment resulting from construction in temporary or permanent debris basins.
- G. Using temporary measures to keep erosion under control if construction is suspended for any appreciable length of time.
- H. Providing protection against chemical, fuel, or lubricant spills, and sewage pollutants.
- I. Protecting project and existing structures from surface water damage due to utility line excavations.
- J. Controlling soil erosion and sedimentation by use of silt fences, dikes, ditches, slope protection, sediment pits, basins, dams, slope drains, coarse aggregate, mulches, sod, grasses, filter fabrics, and other erosion control devices or methods.

### PART 2 - PRODUCTS

#### 2.1 SILT FENCE

- A. Temporary silt fences shall be adequately supported as detailed on the drawings.

## PART 3 - EXECUTION

### 3.1 CONSTRUCTION REQUIREMENTS

- A. In the event of conflict between these requirements and pollution control laws, rules, or regulations or other Federal, State or local agencies, the more restrictive laws, rules or regulations shall apply.
- B. Temporary erosion control features shall be acceptably maintained and shall subsequently be removed or replaced when directed by the Engineer.
- C. Removed materials shall become the property of the Contractor and shall be disposed of off the site at the Contractor's expense.

### 3.2 PERFORMANCE

- A. If, in the opinion of the Engineer and Owner, proper control of soil erosion and sedimentation is not being provided by the Contractor, the Owner may take all necessary steps to provide corrective measures and the cost of such services will be deducted from any money which may be due or become due the Contractor.
- B. Control work performed for protection of construction areas outside the construction site, such as borrow and waste areas, haul roads, equipment and material storage sites, and temporary plant sites shall be considered as a subsidiary obligation of the Contractor, with all necessary control costs included in the contract price.
- C. In the event that temporary erosion and sediment control measures are required due to the Contractor's negligence, carelessness, or failure to install permanent controls as a part of the work as scheduled, and are ordered by the Engineer, such temporary work shall be performed by the Contractor at his expense.

END OF SECTION 015713

## SECTION 016600 - PRODUCT HANDLING AND PROTECTION

### PART 1 - GENERAL

#### 1.1 DELIVERY AND STORAGE OF MATERIALS

- A. The Contractor shall be responsible for delivery and storage of all materials.
- B. The Contractor shall coordinate with the Engineer on the arrangement for storing construction materials and equipment. Deliveries of all construction materials and equipment should be made at suitable times.
- C. The Contractor shall store all materials required for the performance of this contract at sites designated by the Engineer.
- D. All stockpiles shall be neat, compact, completely safe, and barricaded with warning lights if necessary.
- E. Precautions shall be taken so that no shade trees, shrubs, flowers, sidewalks, driveways or other facilities will be damaged by the storage of materials. The Contractor shall be responsible for the restoration of all stockpile sites to their original condition.
- F. Materials, tools and machinery shall not be piled or placed against shade trees, unless they shall be amply protected against injury therefrom. All materials, tools, machinery, etc. stored upon public thoroughfares must be provided with red lights at night time so as to warn the traffic of such obstruction.
- G. Materials shall be so stored as to assure the preservation of their quality and fitness for the work. Stored materials, even though approved before storage, shall again be inspected prior to their use in the work. Stored materials shall be located so as to facilitate their prompt inspection. Approved portions of the construction site may be used for storage purposes and for the placing of the Contractor's plant and equipment, but any additional space required therefore must be provided by the Contractor at his expense. Private property shall not be used for storage purposes without written permission of the property owner or lessee, and copies of such written permission shall be furnished the Engineer. All storage sites shall be restored to their original condition by the Contractor at his expense.

END OF SECTION 016600



## SECTION 017800 - FINAL COMPLIANCE AND SUBMITTALS

### PART 1 - GENERAL

- 1.1 The following forms and related sign-offs shall be documented in accordance with provisions of the contract. These forms shall be completed by the Contractor and approved by the Owner before final retainer is approved for release. Forms for Items A to E will be attached to the Contractor's executed copy of the contract.
- A. Certificate of Substantial Completion (To be submitted at time of Substantial Completion).
  - B. Contractor's Certification of Completion.
  - C. Contractor's Affidavit of Prevailing Wage.
  - D. Consent of Surety Company for Final Payment.
  - E. Affidavit of Final Acceptance Date and Correction Period.
  - F. Before the OWNER will approve and accept the work and release the retainer, the CONTRACTOR will furnish the OWNER a written report indicating the resolution of any and all property damage claims filed with the CONTRACTOR by any party during the construction period. The information to be supplied shall include, but not be limited to, name of claimant, date filed with CONTRACTOR, name of insurance company and/or adjuster handling claim, how claim was resolved and if claim was not resolved for the full amount, a statement indicating the reason for such action.

END OF SECTION 017800

## SECTION 017821 - CLEANING AND PROTECTION

### PART 1 - GENERAL

#### 1.1 GENERAL

- A. On or before the completion date for the work, the Contractor shall tear down and remove all temporary structures built by him, all construction plant used by him, and shall repair and replace all parts of existing embankments, fences or other structures which were removed or injured by his operations or by the employees of the Contractor. The Contractor shall thoroughly clean out all buildings, sewers, drains, pipes, manholes, inlets and miscellaneous and appurtenant structures, and shall remove all rubbish leaving the grounds in a neat and satisfactory condition.
- B. As circumstances require and when ordered by the Engineer, the Contractor shall broom sweep and/or hose-wash the hard surface of the road, or any driveway or sidewalk on which construction activity under this contract has resulted in dirt or any other foreign material being deposited.
- C. Failure to comply with this requirement when ordered by the Engineer or his representative, may serve as cause for the Engineer to stop the work and to withhold any monies due the Contractor until such order has been complied with to the satisfaction of the Engineer.
- D. As the work progresses, and as may be directed, the Contractor shall remove from the site and dispose of debris and waste material resulting from his work. Particular attention shall be given to minimizing any fire and safety hazard from form materials or from other combustibles as may be used in connection with the work, which should be removed daily.
- E. During and after installation, the Contractor shall furnish and maintain satisfactory protection to all equipment against injury by weather, flooding or breakage thereby permitting all work to be left in a new condition at the completion of the contract.

END OF SECTION 017821

## SECTION 017839 - PROJECT RECORDS, DRAWINGS

### PART 1 - GENERAL

#### 1.1 RECORD DRAWINGS

- A. The Contractor shall furnish an authentic set of marked-up drawings showing the installation insofar as the installation shall have differed from the Engineer's drawings. The drawings shall be delivered to the Engineer for making revisions to the original drawings immediately after final acceptance by the Owner.
- B. The Contractor shall furnish dimensioned drawings indicating locations of all underground mechanical and electrical facilities.

#### 1.2 SERVICE CONNECTION RECORDS

- A. The Contractor shall record the location of all service and property connections, new or existing, made to utilities constructed under this contract. Such records shall be turned over to the Owner upon completion of the work. The cost of making such records shall be included in the various unit or lump sum prices stipulated for the various items of the work.
- B. The location of each sewer connection as measured along the sewer from the nearest downstream manhole and its description with respect to the sewer shall be recorded. The record shall include the depth of new stubs for future connections and the depth of existing connections as measured from the surface grade. Also, the use of any vertical riser pipe shall be noted.
- C. The location of each water connection as measured along the water line from the nearest fire hydrant.

END OF SECTION 017839

## SECTION 024116 – STRUCTURE DEMOLITION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. This section includes all demolition of existing structures and removal of pavement, piping, and equipment necessary to clear space for new construction and/or to rehabilitate existing construction.

#### 1.3 REQUIREMENTS OF REGULATORY AGENCIES

- A. State and local code requirements shall control the disposal of debris resulting from the removal operation.

#### 1.4 PROTECTION

- A. Structures shall be removed in such a manner as not to damage portions of the existing structure which are to remain in place.

### PART 2 - PRODUCTS (NOT APPLICABLE)

### PART 3 - EXECUTION

#### 3.1 MANHOLES, CATCH BASINS, INLETS AND SIMILAR STRUCTURES

- A. Existing drainage structure designated by the Engineer to be removed shall be completely removed.
- B. Catch basins, inlets, and similar structures designated to be abandoned shall be removed to an elevation of at least 3 ft. below the finished subgrade or ground surface. The remaining void shall be filled with selected backfill material compacted to 100% optimum density per ASTM D 698.
- C. Manholes designated by the Engineer to be abandoned shall be adjusted to 1' below proposed ground grade and the casting welded closed or an 8" reinforced concrete slab placed over the manhole.

- D. Live sewers connected to structures removed or abandoned shall be rebuilt through the area with new pipe. Sewer flow shall be maintained between removal and replacement operations. Abandoned sewers shall be sealed and made watertight with approved precast stoppers or masonry bulkheads.
- E. All castings salvaged from abandoned or removed drainage structures shall remain the property of the Owner and shall be cleaned and transported by the Contractor to a site designated by the Engineer or incorporated in the work where called for on the Drawings, scheduled, or so directed.

### 3.2 DISPOSAL OF DEBRIS

- A. All debris resulting from demolition operations; i.e., broken concrete, masonry, pipe, miscellaneous metal, trees and brush, equipment, etc., shall be disposed of off-site.
- B. The Contractor shall police the hauling of debris to insure that all spillage from haul trucks is promptly and completely removed.

### 3.3 BACKFILLING

- A. All trenches, holes, and pits resulting from the removal and abandonment of any structure or obstruction shall be backfilled and compacted.

END OF SECTION 024116

## SECTION 030000 - CONCRETE WORK

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
  - 1. Section 013319 – Field Testing Requirements

#### 1.2 SUMMARY

- A. This Section specifies cast-in place concrete, including form work, reinforcing, mix design, placement procedures and finishes.
  - 1. Extent of concrete work is shown on drawings.
  - 2. Concrete paving and walks are specified in Division 2.
  - 3. Precast concrete is specified in other Division-3 sections.
  - 4. Mechanical finishes and concrete floor toppings are specified in other Division-3 sections.

#### 1.3 SUBMITTALS

- A. Product Data: Submit data for proprietary materials and items, including reinforcement and forming accessories, admixtures, patching compounds, waterstops, joint systems, curing compounds, dry-shake finish materials, and others as requested by Engineer.
- B. Shop Drawings; Reinforcement: Submit original shop drawings prepared for fabrication, bending, and placement of concrete reinforcement. Comply with ACI Detailing Manual showing bar schedules, stirrup spacing, diagrams of bent bars, arrangement of concrete reinforcement. Include special reinforcement required for openings through concrete structures.
- C. Shop Drawings; Form work: Submit shop drawings prepared by a registered Professional Engineer for fabrication and erection of forms for specific finished concrete surfaces. Show form construction including jointing, special form joint or reveals, location and pattern of form tie placement, and other items which affect exposed concrete visually.
  - 1. Engineer's review is for general architectural applications and features only. Design of form work for structural stability and efficiency is Contractor's responsibility.
- D. Samples: Submit samples of materials as requested by Engineer, including names, sources, and descriptions.
- E. Laboratory Test Reports: Submit laboratory test reports for concrete materials and mix design tests.

1. The proposed mix design submittal(s) shall follow the procedures of Chapter 5, Sections 5.2 to 5.3 of ACI-318.
2. Reference should be made to ACI-211.5R "Guide for Submittal of Concrete Proportions" for the required submittal information. Sample forms for presenting the necessary information can be found in the addendum at the end of this section. Example Form B should follow a completed Example A in the submittal when laboratory trial batches are used to document a water-cementitious materials ratio curve.
3. Additional data summarizing the past performance records should be an integral part of the submittal if the submittal is based on past performance with the proposed materials and proportions.

F. **Materials Certificates:** Provide materials certificates in lieu of materials laboratory test reports when permitted by Engineer. Materials certificates shall be signed by manufacturer and Contractor, certifying that each material item complies with, or exceeds, specified requirements. Provide certification from admixture manufacturers that chloride content complies with specification requirements.

#### 1.4 QUALITY ASSURANCE

A. **Codes and Standards:** Comply with provisions of following codes, specifications, and standards, latest revisions, except where more stringent requirements are shown or specified:

1. ACI 301 "Specifications for Structural Concrete for Buildings."
2. ACI 318 "Building Code Requirements for Reinforced Concrete."
3. Concrete Reinforcing Steel Institute (CRSI), "Manual of Standard Practice."
4. ACI 347 "Guide to Form work for Concrete."
5. ACI 117, "Specifications for Tolerances for Concrete Construction and Materials."

B. **Materials and installed work** may require testing and retesting at anytime during progress of work. Tests, including retesting of rejected materials for installed work, shall be done at Contractor's expense.

C. **Engage a testing agency** acceptable to Engineer to perform initial material evaluation and certification tests for mix designs and to design concrete mixes.

D. **Mockup:** Cast mockup of size indicated or as required to demonstrate typical joints, form tie spacing, and proposed surface finish, texture, and color. Maintain sample panel exposed to view for duration of project, after Engineer's acceptance of visual qualities.

1. Demolish mockup and remove from site when directed by Engineer.

E. **Pre-installation Conference:** Conduct conference at project site to comply with requirements of Division 1 Section "Project Meetings" and the following:

1. At least 35 days prior to submitting design mixes, conduct a meeting to review detailed requirements for preparing concrete design mixes and to determine procedures for satisfactory concrete operations. Review requirements for submittals,

status of coordinating work, and availability of materials. Establish preliminary work progress schedule and procedures for materials, inspection, testing and certifications.

Require representatives of each entity directly concerned with cast-in-place concrete to attend conference, including, but not limited to, the following:

- a. Contractor's Superintendent
- b. Agency responsible for concrete design mixes.
- c. Agency responsible for field quality control.
- d. Ready-mix concrete producer.
- e. Concrete Subcontractor
- f. Primary admixture manufactures.

## 1.5 PROJECT CONDITIONS

- A. Protection of Footings Against Freezing: Cover completed work at footing level with sufficient temporary or permanent cover as required to protect footings and adjacent subgrade against possibility of freezing; maintain cover for time period as necessary.
- B. Protect adjacent finish materials against spatter during concrete placement.

## PART 2 - PRODUCTS

### 2.1 FORM MATERIALS

- A. Forms for Exposed Finish Concrete: Plywood, metal, metal-framed plywood faced, or other acceptable panel-type materials, to provide continuous, straight, smooth, exposed surfaces. Furnish in largest practicable sizes to minimize number of joints and to conform to joint system shown on drawings.
  1. Use plywood complying with U.S. Product Standard PS-1 "B-B (Concrete Form) Plywood," Class I, Exterior Grade or better, mill-oiled and edge-sealed, with each piece bearing legible inspection trademark.
- B. Forms for Unexposed Finish Concrete: Plywood, lumber, metal, or other acceptable material. Provide lumber dressed on at least two (2) edges and one side for tight fit.
- C. Forms for Textured Finish Concrete: Units of face design, size, arrangement, and configuration to match Engineer's control sample. Provide solid backing and form supports to ensure stability of textured form liners.
- D. Forms for Cylindrical Columns and Supports: Metal, fiberglass reinforced plastic, or paper or fiber tubes. Construct paper or fiber tubes of laminated plies using water-resistant adhesive with wax-impregnated exterior for weather and moisture protection. Provide units with sufficient wall thickness to resist loads imposed by wet concrete without deformation.
- E. Form Coatings: Provide commercial formulation form-coating compounds that will not bond with, stain, nor adversely affect concrete surfaces, and will not impair subsequent treatments of concrete surfaces.



- F. Form Ties: Factory-fabricated, adjustable-length, snapoff metal or glass fiber-reinforced plastic form ties, designed to prevent form deflection and to prevent spalling concrete upon removal. Provide units which will leave no metal closer than 1-1/2" to the exposed surface.
  - 1. Provide ties which, when removed, will leave holes not larger than 1" diameter in concrete surface.
  - 2. All form ties shall have a factor of safety of two (2) to determine the recommended safe working load.

## 2.2 REINFORCING MATERIALS

- A. Reinforcing Bars: ASTM A 615, Grade 60, deformed.
- B. Galvanized Reinforcing Bars: ASTM A 767, Class II (2.0 oz. zinc psf) hot-dip galvanized, after fabrication and bending.
- C. Epoxy-Coated Reinforcing Bars: ASTM A 775.
  - 1. Repair of damaged epoxy-coating - When required, damaged epoxy-coating shall be repaired with patching material conforming to ASTM A 775. Repair shall be done in accordance with the patching material manufacturer's recommendations.
- D. Steel Wire: ASTM A 82, plain, cold-drawn steel.
- E. Welded Wire Fabric: ASTM A 185, welded steel wire fabric. (Flat sheets only)
- F. Welded Deformed Steel Wire Fabric: ASTM A 497.
- G. Epoxy - Coated Welded Wire Fabric: ASTM A884, Class A.
- H. Supports for Reinforcement: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded wire fabric in place. Use wire bar type supports complying with CRSI specifications.
  - 1. For slabs-on-grade, use supports with sand plates or horizontal runners where base material will not support chair legs.
  - 2. For exposed-to-view concrete surfaces, where legs of supports are in contact with forms, provide supports with legs which are plastic protected (CRSI, Class 1) or stainless steel protected (CRSI, Class 2).

## 2.1 CONCRETE MATERIALS

- A. Portland Cement: ASTM C 150, Type I, II or I/II and ASTM C595M, Type IP, unless otherwise specified. (See Table I, Concrete Requirements).
  - 1. Use one brand of cement throughout project, unless otherwise acceptable to Engineer.

- B. Fly Ash: ASTM C 618, Class F.
1. Limit use of fly ash to not exceed 25% of cement content by weight.
- C. Ground Granulated Blast-Furnace Slag: ASTM C989, Grade 100 or 120.
1. Limit use of granulated blast-furnace slag to not exceed 30% of cement content by weight.
- D. Normal Weight Aggregates: ASTM C 33, and as herein specified. Provide aggregates from a single source for exposed concrete, with nominal maximum aggregate size of 1 inch.
1. For exterior exposed surfaces, do not use fine or coarse aggregates containing spalling-causing deleterious substances.
  2. Local aggregates not complying with ASTM C 33 but which have shown by special test or actual service to produce concrete of adequate strength and durability may be used when acceptable to Engineer.
  3. Combined Aggregate Gradation: Well graded from coarsest to finest with not more than 18 percent and not less than 8 percent retained on an individual sieve, except that less than 8 percent may be retained on coarsest sieve and on No. 50 (0.3-mm) sieve, and less than 8 percent may be retained on sieves finer than No. 50 (0.3 mm).
- E. Lightweight Aggregates: ASTM C 330.
- Maximum nominal aggregate size of 1 inch.
- F. Water: Drinkable and complying with ASTM C94.
- G. Air-Entraining Admixture: ASTM C 260, certified by manufacturer to be compatible with other required admixtures.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. "Air-Mix"; Euclid Chemical Co.
    - b. "Sika Aer"; Sika Corp.
    - c. "MB-VR or MB-AE"; Master Builders.
- H. Water-Reducing Admixture: ASTM C 494, Type A, and containing not more than 0.1 percent chloride ions.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. "WRDA"; W.R. Grace.
    - b. "Eucon WR-75"; Euclid Chemical Co.
    - c. "Pozzolith Normal"; Master Builders.
- I. High-Range Water-Reducing Admixture (Super Plasticizer): ASTM C 494, Type F and containing not more than 0.1 percent chloride ions.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. "Sikament 300"; Sika Chemical Corp.
  - b. "Eucon 37"; Euclid Chemical Co.
  - c. "Rheobuild or Polyheed"; Master Builders.
  
- J. Water-Reducing, Non-Chloride Accelerator Admixture: ASTM C 494, Type E, and containing not more than 0.1 percent chloride ions.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. "Accelguard 80"; Euclid Chemical Co.
    - b. "Pozzutec 20"; Master Builders.
    - c. "Daraset"; W.R. Grace & Co.
  
- K. Water-Reducing, Retarding Admixture: ASTM C 494, Type D, and containing not more than 0.1 percent chloride ions.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. "Pozzolith"; Master Builders.
    - b. "Eucon Retarder 75"; Euclid Chemical Co.
    - c. "Plastiment"; Sika Chemical Co.
  
- L. Corrosion-Inhibiting Admixture: Commercially formulated, anodic inhibitor or mixed cathodic and anodic inhibitor; capable of forming a protective barrier and minimizing chloride reactions with steel reinforcement in concrete.
  1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
  2. Products: Subject to compliance with requirements, provide one of the following:
    - a. Catexol 1000CL; Axim Concrete Technologies.
    - b. MCI 2000 or MCI 2005; Cortec Corporation.
    - c. DCI or DCI-S; W.R. Grace & Co., Construction Products Div.
    - d. Rheocrete 222+; Master Builders, Inc.
    - e. FerroGard-901; Sika Corporation.
  
- M. Prohibited Admixtures: Calcium chloride thyocyanates or admixtures containing more than 0.1 percent chloride ions are not permitted.
  
- N. Fiber Reinforcement:
  1. Synthetic fiber reinforcing shall be added to the concrete for the areas so indicated in the drawings. Only fibers designed and manufactured specifically for use in concrete shall be acceptable as secondary reinforcement, complying with ASTM C1116, not less than 3/4 inch long.

2. The fibers may be added at the batch plant. The incorporation of said fibers shall be documented on the delivery ticket from the ready mix producer. Fibers shall be added to the concrete in strict accordance with manufacturer's printed instructions. The minimum dosage rate shall be 1.5 lbs/cubic yard.
3. Nylon fibers containing 100% virgin nylon monofilaments shall be utilized to impart a "non-hairy" surface to the finished concrete.
4. Products: Subject to compliance with requirements, provide the following fibrous reinforcement or approved equal:
  - a. Nycon Fiber; Nycon, Inc.
  - b. Nylo-Mono; Forta Corp.
  - c. Fibrasol N; Axim Concrete Technologies

## 2.2 RELATED MATERIALS

- A. Reglets: Where resilient or elastomeric sheet flashing or bituminous membranes are terminated in reglets, provide reglets of not less than 26 gage galvanized sheet steel. Fill reglet or cover face opening to prevent intrusion of concrete or debris.
- B. Waterstops: Provide waterstops at construction joints and other joints as indicated and specified in Section 030000.02.
- C. Granular Base: Evenly graded mixture of fine and coarse aggregates to provide, when compacted, a smooth and even surface below slabs on grade.
- D. Vapor Retarder: Provide vapor retarder cover, ASTM E1745 Class C, over prepared base material where indicated below slabs on grade. Use only materials which are resistant to deterioration when tested in accordance with ASTM E 154, as follows:
  1. Polyethylene sheet not less than 10 mils thick.
  2. Water resistant barrier paper consisting of heavy Kraft papers laminated together with glass fiber reinforcement and over-coated with black polyethylene on each side.
    - a. Product: Subject to compliance with requirements, provide Moistop Ultra 10 by Fortifiber Corporation, Stego Wrap 10-mil by Stego Industries or equal.
- E. Non-Shrink Grout: CRD-C 621 and ASTM C-1107, factory pre-mixed grout.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Non-metallic
      - 1) "Set Grout"; Master Builders.
      - 2) "Euco-NS"; Euclid Chemical Co.
      - 3) "Five Star Grout"; U.S. Grout Corp.

- F. Non-slip Aggregate Finish: Provide fused aluminum oxide grits, or crushed emery, as abrasive aggregate for non-slip finish with emery aggregate containing not less than 50 percent aluminum oxide and not less than 25 percent ferric oxide. Use material that is factory-graded, packaged, rust-proof, and non-glazing, and is unaffected by freezing, moisture, and cleaning materials.
- G. Colored Wear-Resistant Finish: Packaged, dry, combination of materials, consisting of Portland cement, graded quartz aggregate, coloring pigments, and plasticizing admixture. Use coloring pigments that are finely ground, non-fading mineral oxides, interground with cement. Color as selected by Engineer, unless otherwise indicated.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. "Colorcron"; Master Builders.
    - b. "Surflex"; Euclid Chemical Co.
    - c. "Lithochrome"; L.M. Scofield Co.
- H. Absorptive Cover: Burlap cloth made from jute or kenaf, weighing approximately 9 oz. per sq. yd., complying with AASHTO M 182, Class 2.
- I. Moisture-Retaining Cover: One of the following, complying with ASTM C 171.
1. Waterproof paper.
  2. Polyethylene film.
  3. Polyethylene-coated burlap.
- J. Liquid Membrane-Forming Curing Compound: Liquid type membrane- forming curing compound complying with ASTM C 309, Type I, Class A. Moisture loss not more than 0.55 kg./sq. m. when applied at 200 sq ft./gal.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. "Masterkure"; Master Builders.
    - b. "Ecocure"; Euclid Chemical Co.
    - c. "Horn Clear Seal"; A.C. Horn, Inc.
- K. Underlayment Compound: Freeflowing, self-leveling, pumpable cementitious base compound for applications from 1 inch thick to feathered edges.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. "Flo-Top"; Euclid Chemical Co.
    - b. "Underlayment 110," Master Builders, Inc.
    - c. "Thoro Underlayment Self-Leveling"; Thoro System Products.
- L. Bonding Compound: Polyvinyl acetate or acrylic base.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Polyvinyl Acetate (Interior Only):
    - 1) "Euco Weld"; Euclid Chemical Co.
    - 2) "Weldcrete"; Larsen Products Corp.
    - 3) "Everweld"; L&M Construction Chemicals, Inc.
  - b. Acrylic or Styrene Butadiene:
    - 1) "Day-Chem AD Bond"; Dayton Superior Corp.
    - 2) "Everbond"; L & M Construction Chemicals.
    - 3) "SBR Latex"; Euclid Chemical Co.
- M. Epoxy Adhesive: ASTM C 881, two component material suitable for use on dry or damp surfaces. Provide material "Type," "Grade," and "Class" to suit project requirements.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. "Epoxtite Binder 2390"; A.C. Horn, Inc.
    - b. "Sikadur 32 Hi-Mod"; Sika Chemical Corp.
    - c. "Euco Epoxy 452 or 620"; Euclid Chemical Co.

## 2.3 PROPORTIONING AND DESIGN OF MIXES

- A. Prepare design mixes for each type and strength of concrete by either laboratory trial batch or field experience methods as specified in ACI 301 and ACI 211. If the trial batch method is used, use an independent testing facility acceptable to Engineer for preparing and reporting proposed mix designs. The testing facility shall not be the same as used for field quality control testing unless otherwise acceptable to Engineer.
  1. Limit use of fly ash to not exceed 25 percent of cement content by weight.
- B. Submit written reports to Engineer and Structural Engineer of each proposed mix for each class of concrete at least 15 days prior to start of work. Do not begin concrete production until mixes have been reviewed by Engineer.
- C. Design mixes to provide normal weight concrete with the following properties, as indicated in Table I.:

TABLE 1

## CONCRETE REQUIREMENTS

Concrete Class	Cement Type	Min. 28-Day Compressive Strength PSI	*Max. Water-Cement Ratio	Min. Cement Content Sacks	Slump Min.	Inch Max.	Entrained Air %
A	I	4000	0.45	6	-	-	6±1
B	I	2000	0.74	4-1/2	2	6	5±1-1/2
C	I	4000	0.50	6.38	1	4	6±2
D	II or IP	4000	0.45	6	-	-	6±1

\*Maximum Water - Cementitious Materials Ratio

1. All reinforced concrete shall be Class A, except as otherwise specified or shown on the drawings.
  2. Concrete used for mud mats, fill and channeling in manholes and chambers shall be Class B unless otherwise noted on the drawings.
  3. Class C concrete conforming to ODOT 499 (Class C) shall be used for all concrete pavement, curbing, driveways, and sidewalks, unless noted otherwise on the drawings.
  4. Class B concrete may be used for encasing pipelines, fill, and pipe bedding.
  5. Class B concrete shall be used as concrete fill in concrete tanks for shaping or sloping bottoms.
    - a. The following steps shall be taken for installation of the Class B concrete:
      - 1) Scrub concrete slabs and/or walls with a stiff wire brush and streams of clean water as a minimum, to remove laitance.
      - 2) Apply a bonding agent in accordance with the manufacturer's surface preparation and application recommendations.
      - 3) The Class B concrete shall then be placed and screeded to bring the surface to final grade.
  6. Class D concrete shall be used for sewerage treatment plants and sewerage pump stations, as noted on the drawings.
- D. Lightweight Concrete: Lightweight aggregate and concrete shall conform to ASTM C 330. Proportion mix to produce concrete with a minimum compressive strength of 3000 psi at 28 days and a calculated equilibrium unit weight of 110 pcf plus or minus 3 pcf as determined by ASTM C 567. Concrete slump at the point of placement shall be the minimum necessary for efficient mixing, placing, and finishing. Maximum slump shall be 6 inches for pumped concrete and 5 inches elsewhere. Air entrain concrete exposed to weather according to ACI 301 requirements.

- E. Adjustment to Concrete Mixes: Mix design adjustments may be requested by Contractor when characteristics of materials, job conditions, weather, test results, or other circumstances warrant; at no additional cost to Owner and as accepted by Engineer. Laboratory test data for revised mix design and strength results must be submitted to and accepted by Engineer before using in work.
- F. Admixtures:
1. Use high range water-reducing admixture (super plasticizer) in Classes A and D concrete unless noted otherwise.
  2. Use non-chloride accelerating admixture in concrete slabs placed at ambient temperatures below 50 deg F (10 deg C).
  3. Use air-entraining admixture in all concrete, unless otherwise indicated. Add air-entraining admixture at manufacturer's prescribed rate to result in concrete at point of placement having total air content within limits shown in Table I.
  4. Use admixtures for water-reducing and set-control in strict compliance with manufacturer's directions.
  5. Slump Limits: Proportion and design mixes to result in concrete slump at point of placement as shown in Table I:
    - a. Concrete containing HRWR admixture (super-plasticizer): Not more than 8" after addition of HRWR to site-verified 2"-3" slump concrete.

## 2.4 CONCRETE MIXING

- A. Job-Site Mixing: Mix materials for concrete in appropriate drum type batch machine mixer. For mixers of one cu. yd., or smaller capacity, continue mixing at least 1-1/2 minutes, but not more than 5 minutes after ingredients are in mixer, before any part of batch is released. For mixers of capacity larger than one cu. yd., increase minimum 1-1/2 minutes of mixing time by 15 seconds for each additional cu. yd., or fraction thereof.
1. Provide batch ticket for each batch discharged and used in work, indicating project identification name and number, date, mix type, mix time, quantity, and amount of water introduced.
- B. Ready-Mix Concrete: Comply with requirements of ASTM C 94, and as herein specified.
1. During hot weather, or under conditions contributing to rapid setting of concrete, a shorter mixing time than specified in ASTM C 94 may be required.
    - a. When air temperature is between 85 deg F (30 deg C) and 90 deg F (32 deg C), reduce mixing and delivery time from 1-1/2 hours to 75 minutes, and when air temperature is above 90 deg F (32 deg C), reduce mixing and delivery time to 60 minutes.



## PART 3 - EXECUTION

### 3.1 GENERAL

- A. Coordinate the installation of joint materials and vapor retarders with placement of forms and reinforcing steel.

### 3.2 FORMS

- A. Design, erect, support, brace, and maintain form work to support vertical and lateral, static, and dynamic loads that might be applied until such loads can be supported by concrete structure. Construct form work so concrete members and structures are of correct size, shape, alignment, elevation, and position. Maintain form work construction tolerances complying with ACI 347.
- B. Design form work to be readily removable without impact, shock, or damage to cast-in-place concrete surfaces and adjacent materials.
- C. Construct forms to sizes, shapes, lines, and dimensions shown, and to obtain accurate alignment, location, grades, level and plumb work in finished structures. Provide for openings, offsets, sinkages, keyways, recesses, moldings, rustications, reglets, chamfers, blocking, screeds, bulkheads, anchorages and inserts, and other features required in work. Use selected materials to obtain required finishes. Solidly butt joints and provide back-up at joints to prevent leakage of cement paste.
- D. Fabricate forms for easy removal without hammering or prying against concrete surfaces. Provide crush plates or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces where slope is too steep to place concrete with bottom forms only. Kerf wood inserts for forming keyways, reglets, recesses, and the like, to prevent swelling and for easy removal.
- E. Provide temporary openings where interior area of form work is inaccessible for cleanout, for inspection before concrete placement, and for placement of concrete. Securely brace temporary openings and set tightly to forms to prevent loss of concrete mortar. Locate temporary openings on forms at inconspicuous locations.
- F. Chamfer exposed corners and edges as indicated, using wood, metal, PVC, or rubber chamfer strips fabricated to produce uniform smooth lines and tight edge joints.
- G. Provisions for Other Trades: Provide openings in concrete form work to accommodate work of other trades. Determine size and location of openings, recesses, and chases from trades providing such items. Accurately place and securely support items built into forms.
- H. Cleaning and Tightening: Thoroughly clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, or other debris just before concrete is placed. Retightening forms and bracing after concrete placement if required to eliminate mortar leaks and maintain proper alignment.

### 3.3 VAPOR RETARDER INSTALLATION

- A. Following leveling and tamping of granular base for slabs on grade, place vapor retarder sheeting with longest dimension parallel with direction of pour.
- B. Lap joints 6" and seal with manufacturer's recommended mastic or pressure-sensitive tape.

### 3.4 PLACING REINFORCEMENT

- A. Comply with Concrete Reinforcing Steel Institute's recommended practice for "Placing Reinforcing Bars," for details and methods of reinforcement placement and supports, and as herein specified.
  - 1. Avoiding cutting or puncturing vapor retarder during reinforcement placement and concreting operations. Repair damages before placing concrete.
- B. Clean reinforcement of loose rust and mill scale, earth, ice, and other materials which reduce or destroy bond with concrete.
- C. Accurately position, support, and secure reinforcement against displacement by form work, construction, or concrete placement operations. Locate and support reinforcing by metal chairs, runners, bolsters, spacers, and hangers, as required.
- D. Place reinforcement to obtain at least minimum coverages for concrete protection. Arrange, space, and securely tie bars and bar supports to hold reinforcement in position during concrete placement operations. Set wire ties so ends are directed into concrete, not toward exposed concrete surfaces.
- E. Install welded wire fabric in longest lengths as practicable. Lap adjoining pieces at least one full mesh and lace splices with wire. Offset end laps in adjacent widths to prevent continuous laps in either direction.
- F. Epoxy - Coated Reinforcing Steel:
  - 1. Epoxy-coated reinforcing bars supported from form work shall rest on coated wire bar supports, or on bar supports made of dielectric material or other acceptable materials. Wire bar supports shall be coated with dielectric material for a minimum distance of 2 inches from the point of contact with the epoxy-coated reinforcing bars. Reinforcing bars used as support bars shall be epoxy-coated. In walls having epoxy-coated reinforcing bars, spreader bars where specified by the Engineer, shall be epoxy-coated. Proprietary combination bar clips and spreaders used in walls with epoxy-coated reinforcing bars shall be made of corrosion-resistant material.
  - 2. Epoxy-coated reinforcing bars - Equipment for handling epoxy-coated bars shall have protected contact areas. Bundles of coated bars shall be lifted at multiple pick-up points to minimize bar-to-bar abrasion from sags in the bundles. Coated bars or

bundles of coated bars shall not be dropped or dragged. Coated bars shall be stored on protective cribbing. Fading of the color of the coating shall not be cause for rejection of epoxy-coated reinforcing bars. Coating damage due to handling, shipment and placing need not be repaired in cases where the damaged area is 0.1 square inches or smaller. Damaged areas larger than 0.1 square inches shall be repaired in accordance with the epoxy material manufacturer's recommendations. The maximum amount of damage including repaired and unrepaired areas shall not exceed 2 percent of the surface area in each linear foot of each bar.

### 3.5 JOINTS

- A. Construction Joints: Locate and install construction joints as indicated or, if not indicated, locate so as not to impair strength and appearance of the structure, as acceptable to Engineer.
  - 1. Provide keyways at least 1-1/2" deep in construction joints in walls, slabs, and between walls and footings; accepted bulkheads designed for this purpose may be used for slabs.
  - 2. Place construction joints perpendicular to main reinforcement. Continue reinforcement across construction joints, except as otherwise indicated.
- B. Waterstops: Provide waterstops in construction joints as indicated. Install waterstops to form continuous diaphragm in each joint. Make provisions to support and protect exposed waterstops during progress of work. Fabricate field joints in waterstops in accordance with manufacturer's printed instructions.
- C. Isolation Joints in Slabs-on-Ground: Construct isolation joints in slabs-on-ground at points of contact between slabs-on-ground and vertical surfaces, such as column pedestals, foundation walls, grade beams, and elsewhere as indicated.
  - 1. Joint filler and sealant materials are specified in Section 030000.02 of these specifications.
- D. Contraction (Control) Joints in Slabs-on-Ground: Construct contraction joints in slabs-on-ground to form panels of patterns as shown. Use inserts 1/4 of slab depth, unless otherwise indicated.
  - 1. Form contraction joints by inserting premolded plastic strips into fresh concrete until top surface of strip is flush with slab surface.
  - 2. Follow the directions of Insert Manufacturer for finishing the slab and joints.
- E. If joint pattern not shown, provide joints not exceeding 15' in either direction and located to conform to bay spacing wherever possible (at column centerlines, half bays, third-bays).
  - 1. Joint sealant material is specified in Section 030000.02 of these specifications.

### 3.6 INSTALLATION OF EMBEDDED ITEMS

- A. General: Set and build into work anchorage devices and other embedded items required for other work that is attached to, or supported by, cast-in-place concrete. Use setting drawings, diagrams, instructions, and directions provided by suppliers of items to be attached thereto. Electrical conduit shall not be embedded in concrete.
- B. Install reglets to receive top edge of foundation sheet waterproofing, and to receive thru-wall flashings in outer face of concrete frame at exterior walls, where flashing is shown at lintels, relieving angles, and other conditions.
- C. Edge Forms and Screed Strips for Slabs: Set edge forms or bulkheads and intermediate screed strips for slabs to obtain required elevations and contours in finished slab surface. Provide and secure units to support screed strips using strike-off templates or compacting type screeds.

### 3.7 PREPARATION OF FORM SURFACES

- A. Clean re-used forms of concrete matrix residue, repair and patch as required to return forms to acceptable surface condition.
- B. Coat contact surfaces of forms with an approved, nonresidual, low-VOC, form-coating compound before placing reinforcement.
- C. Thin form-coating compounds only with thinning agent of type, amount, and under conditions of form-coating compound manufacturer's directions. Do not allow excess form-coating material to accumulate in forms or to come into contact with in-place concrete surfaces against which fresh concrete will be placed. Apply in compliance with manufacturer's instructions.
- D. Coat steel forms with a non-staining, rust-preventative form oil or otherwise protect against rusting. Rust-stained steel form work is not acceptable.

### 3.8 CONCRETE PLACEMENT

- A. Preplacement Inspection: Before placing concrete, inspect and complete form work installation, reinforcing steel, and items to be embedded or cast-in. Notify other crafts to permit installation of their work; cooperate with other trades in setting such work. Moisten wood forms immediately before placing concrete where form coatings are not used.
  - 1. Apply temporary protective covering to lower 2' of finished walls adjacent to poured floor slabs and similar conditions, and guard against spattering during placement.
- B. General: Comply with ACI 304 "Recommended Practice for Measuring, Mixing, Transporting, and Placing Concrete," and as herein specified.

1. Deposit concrete continuously or in layers of such thickness that no concrete will be placed on concrete which has hardened sufficiently to cause the formation of seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as herein specified. Deposit concrete as nearly as practicable to its final location to avoid segregation.
- C. Placing Concrete in Forms: Deposit concrete in forms in horizontal layers not deeper than 24" and in a manner to avoid inclined construction joints. Where placement consists of several layers, place each layer while preceding layer is still plastic to avoid cold joints.
1. Consolidate placed concrete by mechanical vibrating equipment supplemented by hand-spading, rodding, or tamping. Use equipment and procedures for consolidation of concrete in accordance with ACI 309.
  2. Do not use vibrators to transport concrete inside forms. Insert and withdraw vibrators vertically at uniformly spaced locations not farther than visible effectiveness of machine. Place vibrators to rapidly penetrate placed layer and at least 6" into preceding layer. Do not insert vibrators into lower layers of concrete that have begun to set. At each insertion limit duration of vibration to time necessary to consolidate concrete and complete embedment of reinforcement and other embedded items without causing segregation of mix.
- D. Placing Concrete Slabs: Deposit and consolidate concrete slabs in a continuous operation, within limits of construction joints, until the placing of a panel or section is completed.
1. Consolidate concrete during placing operations so that concrete is thoroughly worked around reinforcement and other embedded items and into corners.
  2. Bring slab surfaces to correct level with straightedge and strikeoff. Use bull floats or darbies to smooth surface, free of humps or hollows. Do not disturb slab surfaces prior to beginning finishing operations.
  3. Maintain reinforcing in proper position on chairs during concrete placement operations.
- E. Cold Weather Placing: Protect concrete work from physical damage or reduced strength which could be caused by frost, freezing actions, or low temperatures, in compliance with ACI 306 and as herein specified.
1. When air temperature has fallen to or is expected to fall below 40 deg F (4 deg C), uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50 deg F (10 deg C), and not more than 80 deg F (27 deg C) at point of placement.
    - a. The concrete shall be maintained within this temperature range for not less than seven (7) days.
  2. Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials or against cold reinforcing steel.

3. Do not use calcium chloride, salt, and other materials containing antifreeze agents or chemical accelerators, unless otherwise accepted in mix designs.
- F. Hot Weather Placing: When hot weather conditions exist that would seriously impair quality and strength of concrete, place concrete in compliance with ACI 305 and as herein specified.
1. Cool ingredients before mixing to maintain concrete temperature at time of placement below 90 deg F (32 deg C). Mixing water may be chilled, or chopped ice may be used to control temperature provided water equivalent of ice is calculated to total amount of mixing water. Use of liquid nitrogen to cool concrete is Contractor's option.
  2. Cover reinforcing steel with water-soaked burlap if it becomes too hot, so that steel temperature will not exceed the ambient air temperature immediately before embedment in concrete.
  3. Fog spray forms, reinforcing steel, and subgrade just before concrete is placed.
  4. Use water-reducing retarding admixture when required by high temperatures, low humidity, or other adverse placing conditions, as acceptable to Engineers.

### 3.9 FINISH OF FORMED SURFACES

- A. Rough Form Finish: For formed concrete surfaces not exposed-to-view in the finish work or by other construction, unless otherwise indicated. This is the concrete surface having texture imparted by form facing material used, with tie holes and defective areas repaired and patched and fins and other projections exceeding 1/4" in height rubbed down or chipped off.
- B. Smooth Form Finish: For formed concrete surfaces exposed-to-view, or that are to be covered with a coating material applied directly to concrete, or a covering material applied directly to concrete, such as waterproofing, dampproofing, veneer plaster, painting, or other similar system. This is an as-cast concrete surface obtained with selected form facing material, arranged orderly and symmetrically with a minimum of seams. Repair and patch defective areas with fins or other projections completely removed and smoothed; provide smooth rubbed finish to smooth form finish. Refer to "Concrete Surface Repairs."
- C. Smooth Rubbed Finish: Provide smooth rubbed finish to scheduled concrete surfaces, which have received smooth form finish treatment.
1. Scarify or roughen entire surface by grinding or similar effective means.
  2. Combined one part Portland cement to 1-1/2 parts fine sand by volume and a 50:50 mixture of acrylic or styrene butadiene-based bonding admixture and water to form the consistency of thick paint. Blend standard Portland cement and white Portland cement, amounts determined by trial patches, so that final color of dry grout will match adjacent surfaces.
  3. Thoroughly wet concrete surfaces and apply grout to coat surfaces and fill small holes. Remove excess grout by scraping and rubbing with clean burlap. Keep damp by fog spray for at least 36 hours after rubbing.

4. Repeat the above process if necessary to fill voids or bug holes and obtain a consistent match to adjacent surfaces, subject to acceptance of the Engineer.
- D. Grout Cleaned Finish: Provide grout cleaned finish on scheduled concrete surfaces which have received smooth form finish treatment.
1. Scarify or roughen entire surface by grinding or similar effective means.
  2. Apply Thoroseal plaster mix coating by Thoro System Products or approved equivalent with an approximate thickness of 1/8-inch to 1/4-inch.
  3. Follow the manufacturer's recommendations and guidelines regarding surface preparation, application methods and curing.
  4. Repeat the above process if necessary to fill voids or bug holes and obtain a consistent match to adjacent surfaces, subject to acceptance of the Engineer.
- E. Related Unformed Surfaces: At tops of walls, horizontal offsets, and similar unformed surfaces occurring adjacent to formed surfaces, strike-off smooth and finish with a texture matching adjacent formed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces, unless otherwise indicated.

### 3.10 MONOLITHIC SLAB FINISHES

- A. Scratch Finish: Apply scratch finish to monolithic slab surfaces that are to receive concrete floor topping or mortar setting beds for tile, Portland cement terrazzo, and other bonded applied cementitious finish flooring material, and as otherwise indicated.
1. After placing slabs, plane surface to tolerances for floor flatness F(F) 15 and floor levelness F(L) 13, measured according to ASTM E 1155. Slope surfaces uniformly to drains where required. After leveling, roughen surface before final set, with stiff brushes, brooms, or rakes.
- B. Float Finish: Apply float finish to monolithic slab surfaces to receive trowel finish and other finishes as hereinafter specified, and slab surfaces which are to be covered with membrane or elastic waterproofing, membrane or elastic roofing, or sand-bed terrazzo, and as otherwise indicated.
1. After screeding, consolidating, and leveling concrete slabs, do not work surface until ready for floating. Begin floating when surface water has disappeared or when concrete has stiffened sufficiently to permit operation of power-driven floats, or both, Consolidate surface with power-driven floats, or by hand-floating if area is small or inaccessible to power units. Check and level surface plane to tolerances of F(F) 18 F(L) 15. Cut down high spots and fill low spots. Uniformly slope surfaces to drains. Immediately after leveling, refloat surface to a uniform, smooth, granular texture.
- C. Trowel Finish: Apply trowel finish to monolithic slab surfaces to be exposed-to-view, and slab surfaces to be covered with resilient flooring, carpet, ceramic or quarry tile, paint, or other thin film finish coating system.

1. After floating, begin first trowel finish operation using a power-driven trowel. Begin final troweling when surface produces a ringing sound as trowel is moved over surface. Consolidate concrete surface by final hand-troweling operation, free of trowel marks, uniform in texture and appearance, and with surface leveled to tolerances of F(F), 20 and F(L) 17, measured according to ASTM E1155. Grind smooth surface defects which would telegraph through applied floor covering system.
- D. Trowel and Fine Broom Finish: Where ceramic or quarry tile is to be installed with thin-set mortar, apply trowel finish as specified, then immediately follow with slightly scarifying surface by fine brooming.
- E. Non-Slip Broom Finish: Apply non-slip broom finish to exterior concrete platforms, steps, and ramps, and elsewhere as indicated.
1. Immediately after float finishing, slightly roughen concrete surface by brooming with fiber bristle broom perpendicular to main traffic route. Coordinate required final finish with Engineer before application.
- F. Non-slip Aggregate Finish: Apply non-slip aggregate finish to concrete stair treads, platforms, ramps, sloped walks, and elsewhere as indicated.
1. After completion of float finishing, and before starting trowel finish, uniformly spread 25 lbs. of dampened non-slip aggregate per 100 sq. ft. of surface. Tamp aggregate flush with surface using a steel trowel, but do not force below surface. After broadcasting and tamping, apply trowel finishing as herein specified.
  2. After curing, lightly work surface with a steel wire brush, or an abrasive stone, and water to expose non-slip aggregate.
- G. Colored Wear-Resistant Finish: Provide colored wear-resistant finish to monolithic slab surface indicated.
1. Apply dry shake materials for colored wear-resistant finish at rate of not less than 100 lbs. per 100 sq. ft., unless greater amount is recommended by material manufacturer.
  2. Immediately following first floating operation, uniformly distribute approximately 2/3 of required weight of dry shake material over concrete surface, and embed by means of power floating. Follow floating operation with second shake application, uniformly distributing remainder of dry shake material with overlapping applications, and embed by power floating.
  3. After completion of broadcasting and floating, apply trowel finish as herein specified. Cure slab surface with curing compound recommended by dry shake hardener manufacturer. Apply curing compound immediately after final finishing.

### 3.11 CONCRETE CURING AND PROTECTION

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. Protect concrete from rapid moisture loss before and during finishing operations.



1. The evaporation graph, Figure 1, of ACI 308 - Curing Concrete, shall be used to determine the evaporation rate during concrete placement. If the rate of evaporation equals or exceeds 0.2 lbs/sq.ft./hr., steps shall be taken to prevent excessive evaporation from the surface.
  2. Start initial curing as soon as free water has disappeared from concrete surface after placing and finishing.
    - a. Initial curing may be any of the methods listed herein that maintain a satisfactory moisture content and temperature.
  3. Begin final curing procedures, if they differ from initial curing, immediately following initial curing and before concrete has dried. Continue curing for at least seven (7) days in accordance with ACI 301 procedures. Avoid rapid drying at end of final curing period.
- B. Curing Methods: Perform curing of all structural concrete as herein specified.
1. Provide moisture curing by following methods.
    - a. Keep concrete surface continuously wet by covering with water.
    - b. Continuous water-fog spray.
    - c. Cover concrete surface with specified absorptive cover, thoroughly saturating cover with water and keeping continuously wet. Place absorptive cover to provide coverage of concrete surfaces and edges, with 4" lap over adjacent absorptive covers.
  2. Provide moisture-cover curing as follows:
    - a. Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width with sides and ends lapped at least 3" and sealed by waterproof tape or adhesive. Immediately repair any holes or tears during curing period using cover material and waterproof tape.
- C. Provide curing and sealing compound to pavement, walks, and curbs only, as follows:
1. Apply specified curing and sealing compound to concrete slabs as soon as final finishing operations are complete (within 2 hours) and after surface water sheen has disappeared. Apply uniformly in continuous operation by power-spray or roller in accordance with manufacturer's directions. Recoat areas subjected to heavy rainfall within three (3) hours after initial application. Maintain continuity of coating and repair damage during curing period.
- D. Curing Formed Surfaces: Cure formed concrete surfaces, including undersides of beams, supported slabs, and other similar surfaces by moist curing with forms in place for full curing period or until forms are removed. If forms are removed, continue curing by methods specified above, as applicable.

- E. Curing Unformed Surfaces: Cure unformed surfaces, such as slabs, floor topping, and other flat surfaces by moist curing methods.
  - 1. Final cure concrete surfaces to receive liquid floor hardener or finish flooring by use of moisture-retaining cover, unless otherwise directed.

### 3.12 SHORES AND SUPPORTS

- A. Comply with ACI 347 for shoring and reshoring in multistory construction, and as herein specified.
- B. Extend shoring from ground to roof for structures four (4) stories or less, unless otherwise permitted.
- C. Extend shoring at least three (3) floors under floor or roof being placed for structures over four (4) stories. Shore floor directly under floor or roof being placed, so that loads from construction above will transfer directly to these shores. Space shoring in stories below this level in such a manner that no floor or member will be excessively loaded or will induce tensile stress in concrete members where no reinforcing steel is provided. Extend shores beyond minimums to ensure proper distribution of loads throughout structure.
- D. Remove shores and reshore in a planned sequence to avoid damage to partially cured concrete. Locate and provide adequate reshoring to safely support work without excessive stress or deflection.
  - 1. Keep reshores in place a minimum of 15 days after placing upper tier, and longer if required, until concrete has attained its required 28-day strength and heavy loads due to construction operations have been removed.

### 3.13 REMOVAL OF FORMS

- A. Formwork not supporting weight of concrete, such as sides of beams, walls, columns, and similar parts of the work, may be removed after cumulatively curing at not less than 50 deg F (10 deg C) for five (5) days after placing concrete, provided concrete is sufficiently hard to not be damaged by form removal operations, and provided curing and protection operations are maintained.
- B. Formwork supporting weight of concrete, such as beam soffits, joists, slabs, and other structural elements, may not be removed in less than 14 days or until concrete has attained at least 75 percent of design minimum compressive strength at 28 days. Determine potential compressive strength of in-place concrete by testing field-cured specimens representative of concrete location or members. Lab cured cylinders will not be considered.
- C. Form facing material may be removed five (5) days after placement, only if shores and other vertical supports have been arranged to permit removal of form facing material without loosening or disturbing shores and supports.

### 3.14 RE-USE OF FORMS

- A. Clean and repair surfaces of forms to be re-used in work. Split, frayed, delaminated, or otherwise damaged form facing material will not be acceptable for exposed surfaces. Apply new form coating compound as specified for new form work.
- B. When forms are extended for successive concrete placement, thoroughly clean surfaces, remove fins and laitance, and tighten forms to close joints. Align and secure joint to avoid offsets. Do not use "patched" forms for exposed concrete surfaces, except as acceptable to Engineer.

### 3.15 MISCELLANEOUS CONCRETE ITEMS

- A. Filling-In: Fill-in holes and openings left in concrete structures for passage of work by other trades, unless otherwise shown or directed, after work of other trades is in place. Mix, place, and cure concrete as herein specified, to blend with in-place construction. Provide other miscellaneous concrete filling shown or required to complete work.
- B. Curbs: Provide monolithic finish to interior curbs by stripping forms while concrete is still green and steel-troweling surfaces to a hard, dense finish with corners, intersections, and terminations slightly rounded.
- C. Equipment Bases and Foundations: Provide machine and equipment bases and foundations, as shown on drawings. Set anchor bolts for machines and equipment with template at correct elevations, complying with certified diagrams or templates of manufacturer furnishing machines and equipment.
  - 1. Grout base plates and foundations as indicated, using specified non-shrink grout. Use non-metallic grout for exposed conditions, unless otherwise indicated.
- D. Steel Pan Stairs: Provide concrete fill for steel pan stair treads and landings and associated items. Cast-in safety inserts and accessories as shown on drawings. Screed, tamp, and finish concrete surfaces as scheduled. Cure concrete as herein specified.
- E. Reinforced Masonry: Provide concrete grout conforming to ASTM C476 for reinforced masonry lintels and bond beams where indicated on drawings and as scheduled. Maintain accurate location of reinforcing steel during concrete placement.

### 3.16 CONCRETE SURFACE REPAIRS

- A. Patching Defective Areas: Repair and patch defective areas with cement mortar immediately after removal of forms, when acceptable to Engineer.
  - 1. Saw-cut out honeycomb, rock pockets, voids over 1/4" in any dimension, down to solid concrete but, in no case to a depth of less than 1." Make edges of cuts slightly undercut to the concrete surface. Thoroughly clean, dampen with water, and brush-coat the area to be patched with specified bonding agent. Place patching mortar after bonding compound has dried.

2. For exposed-to-view surfaces, blend white Portland cement and standard Portland cement so that, when dry, patching mortar will match surrounding color. Provide test areas at inconspicuous location to verify mixture and color match before proceeding with patching. Compact mortar in place and strike-off slightly higher than surrounding surface.
- B. Repair of Formed Surfaces: Remove and replace concrete having defective surfaces if defects cannot be repaired to satisfaction of Engineer. Surface defects, as such, include color and texture irregularities, cracks, spalls, air bubbles, honeycomb, rock pockets; fins and other projections on surface; and stains and other discolorations that cannot be removed by cleaning. Flush out form tie holes, fill with Portland Cement patching mortar, or precast cement cone plugs secured in place with bonding agent. When other materials are used, apply them in accordance with manufacturer's recommendations.
1. Repair concealed formed surfaces, where possible, that contain defects that affect the durability of concrete. If defects cannot be repaired, remove and replace concrete.
  2. Repair of Unformed Surfaces: Test unformed surfaces, such as monolithic slabs, for smoothness and verify surface plane to tolerances specified for each surface and finish. Correct low and high areas as herein specified. Test unformed surfaces sloped to drain for trueness of slope, in addition to smoothness using a template having required slope.
  3. Repair finished unformed surfaces that contain defects which affect durability of concrete. Surface defects, as such, include crazing, cracks in excess of 0.01" wide or which penetrate to reinforcement or completely through non-reinforced sections regardless of width, spalling, pop-outs, honeycomb, rock pockets, and other objectionable conditions.
  4. Correct high areas in unformed surfaces by grinding, after concrete has cured at least 14 days.
  5. Correct low areas in unformed surfaces during or immediately after completion of surface finishing operations by cutting out low areas and replacing with fresh concrete. Finish repaired areas to blend into adjacent concrete. Proprietary patching compounds may be used when acceptable to Engineer.
  6. Repair defective areas, except random cracks and single holes not exceeding 1" diameter, by cutting out and replacing with fresh concrete. Remove defective areas to sound concrete with clean, square cuts and expose reinforcing steel with at least 3/4" clearance all around. Dampen concrete surfaces in contact with patching concrete and apply bonding compound. Mix patching concrete of same materials to provide concrete of same type or class as original concrete. Place, compact, and finish to blend with adjacent finished concrete. Cure in same manner as adjacent concrete.
  7. Repair isolated random cracks and single holes not over 1" in diameter by dry-pack method. Groove top of cracks and cut-out holes to sound concrete and clean of dust, dirt, and loose particles. Dampen cleaned concrete surfaces and apply bonding compound. Mix dry-pack, consisting of one part Portland cement to 2-1/2 parts fine aggregate passing a No. 16 mesh sieve, using only enough water as required for handling and placing. Place dry pack after bonding compound has dried. Compact dry-pack mixture in place and finish to match adjacent concrete. Keep patched area continuously moist for not less than 72 hours.

8. Perform structural repairs with prior approval of Engineer or Structural Engineer for method and procedure, using specified epoxy adhesive and mortar.
9. Repair methods not specified above may be used, subject to acceptance of Engineer.
10. Underlayment Application: Leveling of floors for subsequent finishes may be achieved by use of specified underlayment material.

### 3.17 THROUGH SECTION CONCRETE CRACK REPAIRS

#### A. Sealing through wall or slab cracks.

1. Seal cracks for a water-tight or structurally bonded repair with epoxy or chemical grouting procedures.
  - a. The Contractor shall make proper repairs with epoxy injection or chemical injection with a moisture reactive hydrophilic polyurethane foam grout, as directed by the Engineer.

### 3.18 MUD MATS

- #### A. Where called for on the plans or as directed by the Engineer, the Contractor shall construct concrete mud mats immediately after cleaning the excavation bottom, to preserve the bearing surface condition. Concrete for mud mats shall be not less than 3 in. thick. Bottom of excavation shall be free of water, mud and loose material prior to mud mat placement. See Section 310000.
1. Mud mat concrete shall be cast against the side walls of all excavations to completely seal the bottom.

ADDENDUM  
EXAMPLE FORM A

CONCRETE SUPPLIER: \_\_\_\_\_

PROJECT: \_\_\_\_\_ CONTRACTOR: \_\_\_\_\_

MIXTURE ID: \_\_\_\_\_ SPECIFIED f'c: \_\_\_\_\_ PSI

MATERIAL MIXTURE PROPORTIONS lbs-mass/cu.yd. (pcy)

1.0 Cement Type \_\_\_\_\_ Source: \_\_\_\_\_

Sp. Gr. \_\_\_\_\_ pcy \_\_\_\_\_ cu. ft.

1.1 Other Cementitious Materials: \_\_\_\_\_ Class: \_\_\_\_\_ Source: \_\_\_\_\_

Sp. Gr. \_\_\_\_\_ pcy \_\_\_\_\_ cu. ft.

2.0 Aggregate (No. 1) Type: \_\_\_\_\_ Size: \_\_\_\_\_ Source: \_\_\_\_\_

SSD Sp. Gr. \_\_\_\_\_ pcy \_\_\_\_\_ cu. ft.

Dry Rodded Unit Wt.: \_\_\_\_\_ pcf

Alternate (No. 1) Lightweight Aggregate Type: \_\_\_\_\_ Size: \_\_\_\_\_ Source: \_\_\_\_\_

Sp. Gr. Factor \_\_\_\_\_ over dry pcy \_\_\_\_\_ cu. ft.

Loose Unit Wt. \_\_\_\_\_ pcf Estimated Wet \_\_\_\_\_ pcf

2.1 Aggregate (No. 2) Type: \_\_\_\_\_ Size: \_\_\_\_\_ Source: \_\_\_\_\_

SSD Sp. Gr. \_\_\_\_\_ pcy \_\_\_\_\_ cu. ft.

Dry Rodded Unit Wt.: \_\_\_\_\_ pcf (If Fine Sized - FM \_\_\_\_\_)

2.2 Aggregate (Nos. 3, 4, n) Type: \_\_\_\_\_ Size: \_\_\_\_\_ Source: \_\_\_\_\_

SSD Sp. Gr. \_\_\_\_\_ pcy \_\_\_\_\_ cu. ft.

Dry Rodded Unit Wt.: \_\_\_\_\_ pcf

3.0 Water: \_\_\_\_\_ gal. \_\_\_\_\_ pcy \_\_\_\_\_ cu. ft.

EXAMPLE FORM A (CONTINUED)

4.0 Admixtures expressed as fluid ounces/cubic yard, and estimated range

Source: \_\_\_\_\_ Name: \_\_\_\_\_ Type \_\_\_\_\_ oz

Source: \_\_\_\_\_ Name: \_\_\_\_\_ Type \_\_\_\_\_ oz

Source: \_\_\_\_\_ Name: \_\_\_\_\_ Type \_\_\_\_\_ oz

Total Admixture Liquid Vol. \_\_\_\_\_ cu. ft.

(\*) Note: Show volume in 4.0 if not included in cubic feet of air or water.

5.0 Other Materials - fibers, color pigment or other additions

Sp. Gr. \_\_\_\_\_ pcy \_\_\_\_\_ cu. ft.

Total Mixture Mass and Volume: \_\_\_\_\_ pcy \_\_\_\_\_ cu. ft.

Fresh Concrete Properties

Coarse & Fine Aggregate Gradation

		Percent Passing					
		Sieve Size	Aggregate No.				
			1	2	3	4	Combined
Slump _____ +/- _____ in.							
Unit Weight _____ pcf		2 in.	_____	_____	_____	_____	_____
Air Content _____ +/- _____ %		1-1/2 in.	_____	_____	_____	_____	_____
		1 in.	_____	_____	_____	_____	_____
		3/4 in.	_____	_____	_____	_____	_____
		1/2 in.	_____	_____	_____	_____	_____
If Trail Batch Data -		3/8 in.	_____	_____	_____	_____	_____
Identify Batch No. _____		No. 4	_____	_____	_____	_____	_____
Batch Date _____		No. 8	_____	_____	_____	_____	_____
Concrete Temp. _____ °F	No. 16	_____	_____	_____	_____	_____	_____
Comp. Strength-Average _____ °F	No. 30	_____	_____	_____	_____	_____	_____

EXAMPLE FORM A (CONTINUED)

7 day avg. _____ psi	No. 50	_____	_____	_____	_____	_____
28 day avg. _____ psi	No. 100	_____	_____	_____	_____	_____
	No. 200	_____	_____	_____	_____	_____

Comments: \_\_\_\_\_  
\_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Title: \_\_\_\_\_

Organization: \_\_\_\_\_



EXAMPLE FORM B

CONCRETE SUPPLIER: \_\_\_\_\_

MATERIAL                      TRAIL BATCH NUMBER - proportions per cubic yard

1                      2                      3                      4

1.0    Cement Source: \_\_\_\_\_

Type \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb

1.1    Other Cementitious Material Sources: \_\_\_\_\_

Type \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb

2.0    Aggregate No. 1    Size \_\_\_\_\_      Source: \_\_\_\_\_

SSD \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb

Alternate No. 1 Lightweight Aggregates Type \_\_\_\_\_      Source: \_\_\_\_\_

Sp. Gr. Factor \_\_\_\_\_

Oven Dry      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb

Wet      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb

2.1    Aggregate No. 2    Size \_\_\_\_\_      Source: \_\_\_\_\_

SSD \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb

2.2    Aggregate Nos. 3, 4, n)    Size \_\_\_\_\_      Source: \_\_\_\_\_

SSD \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb

3.0    Water      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb      \_\_\_\_\_ lb

4.0    Admixtures Source: \_\_\_\_\_

\_\_\_\_\_ Type \_\_\_\_\_      \_\_\_\_\_ oz      \_\_\_\_\_ oz      \_\_\_\_\_ oz      \_\_\_\_\_ oz

\_\_\_\_\_ Type \_\_\_\_\_      \_\_\_\_\_ oz      \_\_\_\_\_ oz      \_\_\_\_\_ oz      \_\_\_\_\_ oz

\_\_\_\_\_ Type \_\_\_\_\_      \_\_\_\_\_ oz      \_\_\_\_\_ oz      \_\_\_\_\_ oz      \_\_\_\_\_ oz

EXAMPLE FORM B (CONTINUED)

5.0 Other Materials

\_\_\_\_\_ Type \_\_\_\_\_ lb \_\_\_\_\_ lb \_\_\_\_\_ lb \_\_\_\_\_ lb

Total Mass: \_\_\_\_\_ lb \_\_\_\_\_ lb \_\_\_\_\_ lb \_\_\_\_\_ lb

Total Mass/cy: \_\_\_\_\_ pcy \_\_\_\_\_ pcy \_\_\_\_\_ pcy \_\_\_\_\_ pcy

Relative Cubic Yard Volume: \_\_\_\_\_ cy \_\_\_\_\_ cy \_\_\_\_\_ cy \_\_\_\_\_ cy

Water-Cementitious Material Ratio:

Fresh Concrete Properties

TRAIL BATCH NUMBER

	<u>## -1</u>	<u>## -2</u>	<u>## -3</u>	<u>## -4</u>
Slump-inches	_____	_____	_____	_____
Air-Content %	_____	_____	_____	_____
Unit Wt. pcf	_____	_____	_____	_____
Concrete Temp. °F	_____	_____	_____	_____
Compressive Strength Results (ASTM C192, C39) or Other Specified Test Requirements				
7 days	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
Average (7 day)	_____	_____	_____	_____

EXAMPLE FORM B (CONTINUED)

28 days

_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Average (28 day)

_____	_____	_____	_____
-------	-------	-------	-------

Water-Cementitious Material Ratio:

_____	_____	_____	_____
-------	-------	-------	-------

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Title: \_\_\_\_\_

Organization: \_\_\_\_\_

END OF SECTION 030000

## SECTION 030000.02 - EXPANSION AND CONSTRUCTION JOINTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to the work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. This work includes furnishing and installing all joints where necessary.
- B. In general, the work may include the following types of joints:
  - 1. Types A, D, E, F, H and J Expansion Joint
  - 2. Types B and L Waterstop Construction Joint
  - 3. Types C and G Isolation Joints
  - 4. Type K Construction Joint
  - 5. Type CJ Control Joint
- C. Refer to the contract drawings and specifications for locations and details of the joints to be used.

### PART 2 - PRODUCTS

#### 2.1 MATERIALS

- A. The non-extruding preformed filler for joint Types A, C, D, E, F, J, L, and M shall conform to the requirements of “Standard Specifications for Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction” ASTM D 1752, Type I, Sponge Rubber. Preformed filler shall be “Sponge Rubber” as manufactured by W.R. Meadows Company, Everlastic 1300 Series concrete gray sponge by Williams Products, Inc. or equal.
- B. The preformed filler for joint Type H shall conform to the requirements of ASTM D 1752, Type III, self-expanding cork. Self-expanding cork shall be as manufactured by W.R. Meadows Company, or equal.
- C. Preformed filler strips up to one (1) inch thickness shall be made as a single piece. Strips greater than one (1) inch thickness shall be fabricated by cementing together a minimum number of pieces. All cementing or vulcanizing shall be done at the point of manufacture.
- D. The joint sealer shall be cold applied in accordance with manufacturer’s recommendations.
  - 1. Where the joint is not in contact with water, “No-Trak” as manufactured by A.C. Horn, Inc., “Gardox” by W.R. Meadows, Inc., or equal, shall be used.

2. Where the joint is in contact with water, "Sikaflex-IA" as manufactured by Sika Corporation, or equal shall be used.
- E. Extruded polyvinyl chloride (PVC) waterstops for Type "C" joint shall be nine (9) inches in width, not less than three-eighths (3/8) inch in thickness; Type "L" joint shall be four (4) inches wide, not less than three-sixteenths (3/16) inch in thickness; Types "G" and "J" joint shall be six (6) inches in width, not less than three-eighths (3/8) inch in thickness and all waterstops shall be of corrugated construction. Types "C", "G", and "J" shall have a center bulb and corrugated ends. The waterstops shall be made continuous by use of factory made fittings and field jointing by heat welding in accordance with the manufacturer's recommendations. PVC waterstops shall be as manufactured by Vinylex Corporation, Greenstreak Products, or equal. Provide a test report for each lot of waterstops shipped to the job site.
- F. Type "B" joints shall be as detailed on the drawings. The preformed plastic waterstops shall meet or exceed all requirements of Federal Specifications SS-S-210A, "Sealing Compound for Expansion Joints". Such preformed plastic waterstop shall be "Snyko-Flex" waterstop manufactured by Synko-Flex Products, 2100 Travis Street, Houston, Texas, or an approved equivalent.
- G. Elastomeric bearing pad in joint Type "G" shall be 50 durometer Everlastic 1200 Series Neoprene as manufactured by William Products, Inc., or equal.
- H. Type "K" joint shall be constructed as detailed on the drawings.
- I. Type "CJ" premolded insert shall be "Speed-E-Joint" by W.R. Meadows, or equal.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Form work shall be designed to hold the preformed filler in alignment within the joint during and after concrete is poured. General description of the joints are as follows:
  1. Type "A", "D", "E" and "F" expansion joints shall consist of non-extruding preformed filler only to separate the adjoining faces of concrete without the use of a waterstop. The top shall be finished by a joint sealer for slabs. Unless otherwise shown, preformed filler shall be three-fourths (3/4) inch thick and shall be of a width equal to the faces of concrete which it is separating. Where required, the preformed filler shall be attached to concrete by the use of an approved adhesive. Apply bond breaker to edge of preformed filler material only, prior to placing joint sealer. The joint sealer shall bond only to the concrete surfaces.
  2. Type "B" waterstop construction joint shall consist of a standard construction joint and waterstop as detailed on the drawings.
  3. Types "C" and "J" joint shall consist of preformed filler material, waterstop and joint sealer as detailed on the drawings.
  4. Type "G" joint shall consist of an elastomeric bearing pad and waterstop as detailed on the drawings.

5. Type "H" joint shall consist of self-expanding cork to separate the adjoining faces of concrete without the use of a waterstop. The top shall be finished by a joint sealer.
  6. Type "CJ" Control joints shall be made by inserting a removable preformed insert to create a joint which is then filled with a joint sealer, if required.
  7. Type "K" joint shall consist of a standard construction joint, a saw cut, and joint sealer as detailed on the drawings.
- B. PVC waterstops shall be wired to the reinforcing steel every 12" to prevent misalignment during concreting.

END OF SECTION 030000.02

## SECTION 034000.02 - PRECAST CONCRETE MANHOLES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. Under this section, the Contractor shall furnish and construct precast concrete manholes, including drops and manhole stacks of types and at locations shown on the Drawings and/or scheduled.
- B. This section includes additional excavation to widen and deepen sewer trenches for manhole construction, furnishing and installing concrete of classes called for, brick, Portland cement mortar, reinforcing steel, precast concrete pipe, integral base sections, bottom riser sections, transition sections, riser sections, eccentric cones, flat slab tops and adjusting rings, flexible manhole connections, pipe for drop connections, plugging lifting holes, pointing joints, forming channels through manhole bottoms, making watertight connections to new and existing sewers, and other work incidental to manhole construction.

#### 1.3 QUALITY ASSURANCE

- A. In addition to requirements of these specifications, comply with manufacturer's instructions and recommendations for work.

#### 1.4 DEFINITIONS

- A. The various types of manholes are as shown on the Drawings or in the Standard Details.

#### 1.5 SUBMITTALS

- A. Manufacturer's Shop Drawings and Certificates
  - 1. Precast Concrete Manhole Sections and Specials
  - 2. Flexible Joints
- B. Supplier's Certificates
  - 1. Reinforced Concrete Pipe Manhole Sections.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

#### A. Precast Concrete Pipe Manhole Sections

1. Precast concrete pipe manhole sections, transition sections, eccentric cones, flat slab tops, and adjusting rings shall conform to ASTM Specification C 478. Reinforcing in transition sections shall be equal to that specified for wall sections of the larger diameter.
2. Joints shall be O-ring type conforming to ASTM Specification C 443.
3. The standard length of riser sections shall be 48 in. Lengths of 32 in. or 16 in. shall be used to meet required dimensions and as specified.
4. Openings for connecting pipes in riser sections, bottom riser sections, and integral base sections, and for access in flat slabs shall be preformed or cored by the manufacturer. Cut-out openings shall be made immediately after the pipe is removed from the casting form. All cored openings for sewer pipe connections shall have flexible joints.
5. Specified manhole steps shall be factory installed to provide a continuous ladder of 16 in. c/c rung spacing. Steps shall be placed in the forms and cast in pipe wall or placed immediately after the pipe is removed from casting and carefully mortared in place with nonshrink mortar to insure a watertight joint. If the outer surface of the pipe wall is pierced, the patch shall be completely covered with a bituminous sealer.
6. Where pressure tight manhole frames and covers are called for, threaded inserts shall be cast in eccentric cones or flat slab tops and holes formed or cored in adjusting rings to match bolt size and spacing specified for manhole casting.

B. Manhole frames, covers, and steps utilized shall comply with their respective specification.

#### C. Mortar

1. Mortar used for the structures herein specified shall conform to Specifications for Mortar for Unit Masonry, ASTM Designation C 270 Type S, containing no masonry cement. The mortar shall be composed of one part Portland cement to two parts sand by volume.
2. Materials for nonshrinking grout shall conform to CRD-C "Corps of Engineers Specifications for Non- Shrink Grout". Approved products are "Sauereisen F-100 Grout" by Sauereisen Cements Co.; "Five Star Grout" by U.S. Grout Corporation; "Masterflow 713" by Master Builders; "Euco N-S" by Euclid Chemical Company.

D. All cast-in-place concrete used for forming channels in manhole bottoms shall be Class B as specified in the Section 030000.

E. Reinforcing steel used in cast-in-place concrete shall meet the requirements of Section 030000.



- F. Flexible joints for precast manhole pipe openings herein specified shall conform to ASTM designation C 923, "A-Lok" Type as manufactured by A-Lok Products; or an approved equivalent.
- G. The pipe and size for manhole drops shall conform to the Standard Details and its respective specification contained herein.
- H. Brick used for catch basin and manhole construction shall conform to Specifications for Sewer and Manhole Brick (made from clay or shale), ASTM Designation C 32, and shall be Grade "MS" unless otherwise specified.

## PART 3 - EXECUTION

### 3.1 LOCATION AND CONSTRUCTION

- A. Location and type of manhole installed shall be as shown on the Drawings or directed.
- B. Construction shall be in conformance with details shown on the Drawings and as specified under this section.

### 3.2 INSTALLATION OF INTEGRAL BASE SECTIONS

- A. Class B concrete shall be poured so as to provide a minimum of 4-in. thick pad under the entire area of the manhole base. Place the manhole on the pad before the concrete is completely set so that final leveling adjustment can be made.
- B. 6" Granular backfill bedding can be used in lieu of Class B concrete.

### 3.3 CHANNELING MANHOLE BOTTOMS

- A. The bottoms of all manholes shall be channeled to conduct flow in the planned direction. Channels shall be the true shape of the lower half of the sewer pipe and shall match inverts of connecting pipe at the manhole wall.
- B. In integral base sections (only) channels may be constructed using brick and Portland cement mortar. Mortar shall be 3/4-in. thick minimum between bricks and between bricks and concrete and 1-in. thick minimum on all exposed surfaces.

### 3.4 PRECAST CONCRETE RISER SECTIONS

- A. The shortest length of riser section to be incorporated into the manhole shall be installed immediately below the flat slab top.
- B. Pipe section joints shall be pointed and lifting holes filled with nonshrinking mortar.

### 3.5 SPECIAL PROVISIONS

- A. The intent of this section is to identify requirements only associated with improvements, or rehabilitation of existing sewerage manholes.
- B. The installation of bottom riser sections shall be as follows:
  - 1. The base shall be of Class A concrete as specified in Section 030000 9 in. thick minimum placed on undisturbed earth.
  - 2. The cut-out riser section shall be blocked in place above the pipe and the concrete base poured in place. Concrete shall be extended above the lower rim of the riser wall as required to provide a watertight seal around the entire circumference of the riser section.
  - 3. On straight runs the Contractor may carry the sewer pipe through the manhole and break out the top half after the fill concrete has set. In all cases the sewer pipe shall extend through the manhole wall to the inside face.
- C. All manholes for sanitary sewers shall have an application of Thoro-Seal or other approved coating (any color but gray).

END OF SECTION 034000.02

## SECTION 310000 - EARTHWORK

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. The Work covered by this Section shall include all excavation, trenching and related work for the construction of the designated structures and pipelines, backfill and other incidental work.
- B. The Work covered by this Section consists of:
  - 1. making all necessary excavations for the construction of all Work;
  - 2. preparing subgrade for foundations, slabs, walks, and pavements;
  - 3. doing all pumping, fluming, and dewatering necessary to keep the trenches and other excavation free from water;
  - 4. providing for uninterrupted flow of existing drains and sewers, and the disposal of water from any sources during the progress of the Work;
  - 5. supporting and protecting all trench walls, structures, pipes, conduits, culverts, posts, poles, wires, fences, buildings and other public and private property adjacent to the Work;
  - 6. removing and replacing existing sewers, culverts, pipelines and bulkheads where necessary;
  - 7. removing after completion of the Work all sheeting and shoring or other soil support materials not necessary to support the sides of trenches;
  - 8. removing and disposing all surplus excavated material;
  - 9. doing all backfilling and grading, of compacting backfill to limits specified or ordered by the Engineer;
  - 10. restoring all property damaged as a result of the Work involved in this Contract.
- C. The Work includes transporting surplus excavated materials not needed for backfill at the location where the excavation is made, to other parts of the Work where filling is required, and disposal of all types of surplus material off the site.

#### 1.2 RELATED DOCUMENTS AND SECTIONS

- A. Section 013319 – Field Testing Requirements
- B. Section 015713 - Temporary Erosion Control
- C. Section 030000 - Concrete Work
- D. Section 321000 - Pavement Replacement

#### 1.3 DEFINITIONS

- A. Backfill: Soil or granular materials used to fill an excavation.

1. Initial Backfill: Backfill placed beside and over pipe in a trench, not including haunches to support sides of pipe.
  2. Final Backfill: Backfill placed over initial backfill to fill a trench.
- B. Bedding: Layer placed over the excavated subgrade in a trench before laying pipe.
- C. Borrow: Satisfactory soil imported for use as fill or backfill.
- D. Excavation: Removal and disposal of material encountered above subgrade or foundation elevations.
1. Additional Excavation: Excavation below subgrade or foundation elevations as directed by Engineer.
  2. Trench: Narrow linear excavation
  3. Unauthorized Excavation: Excavation below subgrade or foundation elevations or beyond indicated dimensions without direction by Engineer. Unauthorized excavation, as well as remedial work directed by Engineer, shall be without additional compensation.
  4. Unclassified Excavation: Excavation to subgrade elevations regardless of the character of surface or subsurface conditions encountered, including rock, soil materials and obstructions.
- E. Embankment: A structure consisting of soil, granular material, shale, rock, or other approved material, constructed in layers to a predetermined elevation and cross-section.
- F. Granular materials: Natural aggregate, such as broken or crushed rock, gravel, or sand that can be readily incorporated into an 8-inch layer, and in which at least 65% by weight of the grains or particles are retained in a No. 200 sieve.
- G. Laboratory Dry Weight: The maximum laboratory dry weight shall be the weight provided by the laboratory when the sample is tested in accordance with ASTM D-698 Method A, C, or D.
- H. Optimum Moisture: The water content at which the maximum density is produced in a soil by a given compaction effort (ASTM D-698).
- I. Pavement Prism: Also referred to as the zone of influence. The area below a line drawn 45 degrees to the horizontal from the surface at the edge of pavement, sidewalk or curb.
- J. Pipe Embedment: The material placed in a trench surrounding a pipe or conduit consisting of the foundation, bedding, haunching, and initial backfill.
- K. Rock: Rock material in beds, ledges, unstratified masses, and conglomerate deposits and boulders of rock material one (1) cu. yd. or more in volume that when tested by an independent geotechnical testing agency, according to ASTM D 1586, exceeds a standard penetration resistance of 100 blows/2 inches.

- L. Shale: Laminated material, formed by the consolidation in nature of soil, having a finely stratified structure. For the purpose of these specifications, the following bedrock types shall also be considered shale: mudstone, claystone, siltstone and hard clay.
- M. Soil: All earth materials, organic or inorganic, which have resulted from natural processes such as weathering, decay, and chemical reaction.
- N. Structures: Buildings, footings, foundations, retaining walls, slabs, tanks, curbs, pavement, mechanical and electrical appurtenances, or other man-made stationary features constructed above or below the ground surface.
- O. Subgrade: Surface or elevation remaining after completing excavation, or top surface of a fill or backfill immediately below subbase, drainage course, or topsoil materials.
- P. Utilities: On-site underground pipes, conduits, ducts, and cables, as well as underground services within buildings.

#### 1.4 SUBMITTALS

- A. Comply with all provisions of Section 013323, Shop Drawings and Submittals.
- B. Product Data: For the following:
  - 1. Source-locations of all materials shall be identified to the Engineer.
  - 2. Source quality laboratory test of all fill materials as required to show compliance with material specifications.
- C. Shop Drawings: Submit information for the following items:
  - 1. Protection methods anticipated (*prepared and stamped by a professional engineer, registered in the State of Ohio*).
  - 2. Excavation procedures (*prepared and stamped by a professional engineer, registered in the State of Ohio*).

#### 1.5 REFERENCES

- A. AASHTO M 43 Standard Specification for Size of Aggregate for Road and Bridge Construction
- B. ASTM C-150 Standard Specification for Portland Cement
- C. ASTM C-618 Standard Specification for Fly Ash and Raw or Calcined Natural Pozzolan for Use as a Mineral Admixture in Portland Cement Concrete
- D. ASTM D-698 Standard Test Methods for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures Using 5.5-lb (2.49-kg) Rammer and 12-in. (305-mm) Drop

- E. ASTM D-1586 Standard Method for Penetration Test and Split-Barrel Sampling of Soils
- F. ASTM D-2487 Standard Test Method for Classification of Soils for Engineering Purposes
- G. ASTM D-4253 Standard Test Method for Maximum Index Density and Unit Weight of Soils Using a Vibratory Table
- H. ASTM D-4254 Standard Test Method for Minimum Index Density and Unit Weight of Soils and Calculation of Relative Density
- I. State of Ohio - Department of Transportation - Construction and Material Specifications, Item 304, Aggregate Base.
- J. State of Ohio - Department of Transportation - Construction and Material Specifications, Material Detail 703.16, Suitable Materials for Embankment Construction.
- K. State of Ohio - Department of Transportation - Construction and Material Specifications, Material Detail 703.02.A.2, Fine Aggregate for Portland Cement Concrete

## 1.6 QUALITY ASSURANCE

- A. Comply with all provisions of Section 014323 – Qualifications of Tradesmen.
- B. Comply with all provisions of Section 014126 – General Regulations and Permits.
- C. Before and during installation, the Contractor shall comply with provisions under Section 013119 – Project Meetings.

## 1.7 PROJECT CONDITIONS

- A. Environmental Requirements
  - 1. All work to be performed in accordance with section 013543 – Environmental Protection
- B. Existing Conditions
  - 1. Existing ground elevations of the site are shown by figures and/or by contours on the Drawings. The contours and elevations of the present ground are believed to be reasonably correct, but do not purport to be absolutely so, and, together with any schedule of quantities, are presented only as an approximation. The Contractor shall satisfy himself, however, by actual examination on the site of the Work, as to the existing elevations and contours, and the amount of work required.

- C. Existing Utilities
  - 1. Do not interrupt utilities serving facilities occupied by Owner or others unless permitted in writing by Engineer and then only after arranging to provide temporary utility services according to requirements indicated.
  - 2. Notify Engineer not less than two days in advance of proposed utility interruptions.
  - 3. Do not proceed with utility interruptions without Engineer's written permission.
  - 4. Contact utility-locator service for area where Project is located before excavating.

## 1.8 DELIVERY, STORAGE AND HANDLING

- A. Deliver products to the site, store and protect under provisions of Section 016600, Product Handling and Protection.
- B. Comply with all provisions of Section 013543, Environmental Protection.

## 1.9 PROHIBITION OF EXPLOSIVES

- A. The use of explosives is not permitted.

## 1.10 FIELD MEASUREMENTS

- A. The Contract Drawings may indicate locations where certain utilities, structures or facilities might possibly interfere with the installation of new improvements. The Contractor shall dig such exploratory test pits as may be necessary to determine the exact location and elevation of the indicated subsurface structure and shall make acceptable provision for their protection, support and maintenance in operation. The Engineer shall be provided advance notification when and where excavation for test pits will take place. The Contractor shall provide the Engineer a record of field locations of all listed utilities, structures or facilities a minimum of five (5) days prior to initiating construction of the project. Locations and elevations are to be provided by a Surveyor registered in the State of Ohio.

## PART 2 - PRODUCTS

### 2.1 GRANULAR PIPE EMBEDMENT

- A. Crushed gravel or crushed limestone meeting AASHTO M 43 gradation shall be used for bedding, haunching, and initial backfill as shown on the Drawings.

### 2.2 ONSITE BACKFILL

- A. Excavated soil material, capable of meeting specified compaction, and approved by the Engineer for use as backfill in designated locations.

- B. Based upon subsurface investigation, the Owner does not guarantee the onsite soils in its present state consists of the proper moisture content to achieve the specified compaction without drying or adding water.
- C. Unsuitable Backfill Material
  - 1. Onsite materials that are unsuitable for backfill, unless otherwise specifically shown in the Drawings, include rock or other materials greater than six (6) inches in their largest dimension, pavement, rubbish, debris, wood, metal, plastic, frozen earth, and the following soils classified per ASTM D-2487:

Symbol	Description
OL	Organic silts and organic silty clays of low plasticity
MH	Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts
CH	Inorganic clays of high plasticity, fat clays
OH	Organic clays of medium to high plasticity
PT	Peat, muck, and other highly organic soils

### 2.3 SPECIAL BACKFILL MATERIAL (ODOT Item 304)

- A. Special backfill material shall meet the gradation requirements of ODOT Item 304 and shall consist of crushed gravel or crushed limestone in combination with natural sand or stone. The aggregate shall meet the following gradation requirements:

Sieve	Total Percent Passing
2 inch	100
1 inch	70-100
¾ inch	50-90
No. 4	30-60
No. 30	9-33
No. 200	0-15

### 2.4 LOW STRENGTH MORTAR BACKFILL

- A. Low Strength Mortar shall comply with ODOT Item 613.
- B. Submit test data that demonstrates that the proposed mix has a strength of 50 to 100 PSI at 28 days.
- C. Each load shall be tested with 3 cylinders for strength test broken at 3, 7, and 28 days until the Engineer is assured that the mix will be between 50 to 100 PSI at 28 days. Thereafter, one set of strength tests shall be taken every 50 CY.

It is intended that the sand be fine enough to stay in suspension in the mixture to the extent required for proper flow. The Engineer reserves the right to reject the sand if a flowable mixture cannot be produced.



- D. Mortar Mix Proportioning
1. The initial trial mixture shall be as follows:

Quantity of Dry Materials per Cubic Yard

Cement	100 lbs.
Fly Ash	250 lbs.
Sand (SSD)*	2700 lbs.
Water	500 lbs.

\* saturated-surface dry

2. These quantities of materials are expected to yield approximately 1 cubic yard of mortar of the proper consistency. Adjustments of the proportions may be made providing the total absolute volume of the materials is maintained.

## 2.5 EMBANKMENTS

- A. Soils suitable for use in an embankment must conform to ODOT 703.16 and are restricted as follows:
1. Maximum laboratory dry weight shall not be less than 90 pounds per cubic foot, except that soils having maximum dry weights of less than 100 pounds per cubic foot shall not be used in the top 12 inches of embankment.
  2. Soil having a liquid limit in excess of 49 are considered as unsuitable for use in an embankment.
  3. Silt from excavation or borrow identified as Ohio Classification A-4b shall be considered suitable for use in an embankment only when placed at least 3 feet below the surface of the subgrade.
  4. No slag, recycled Portland cement concrete or recycled asphaltic concrete products are suitable for use in an embankment.
  5. Do not use any suitable material that cannot be incorporated in an 8-inch lift in the top 2 feet of the embankment.
  6. Do not use shale, hard shale, or siltstone in the top 2 feet of embankment.
  7. Do not use materials that cannot be satisfactorily placed and compacted to a stable and durable condition.
  8. Material excavated in the work that contains excessive moisture is unsuitable for embankment construction unless dried. Dry or aerate such material before incorporating in the work. The Contractor may elect to waste this material, instead of drying it.
  9. Granular material Type E as specified in ODOT 703.16.C, is not allowed.
  10. No petroleum contaminated soils are suitable for use in an embankment.

## 2.6 ENGINEERED FILL

- A. Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940. The aggregate shall meet the following gradation requirements:

Sieve	Total Percent Passing
2 inch	100
1½ inch	95-100
¾ inch	70-92
3/8 inch	50-70
No. 4	35-55
No. 30	12-25
No. 200	0-8

## PART 3 - EXECUTION

### 3.1 PROTECTION

- A. Excavation; Temporary Sheeting, Shoring, and Bracing
  1. All excavation shall be in accordance with the Occupation Safety and Health Administration (OSHA) regulations.
  2. The Contractor shall furnish and install adequate sheeting, shoring, and bracing to maintain safe working conditions, and to protect newly built work and all adjacent neighboring structures from damage by settlement.
  3. Bracing shall be arranged so as not to place a strain on portions of completed work until construction has proceeded enough to provide ample strength. Sheeting and bracing may be withdrawn and removed at the time of backfilling, but the Contractor shall be responsible for all damage to newly built work and adjacent and neighboring structures.
  4. All sheeting shall be removed unless specifically authorized in writing by the Engineer to be left in place.
  
- B. Construction Sheeting Left in Place
  1. The Contractor shall furnish, install, and leave in place construction sheeting and bracing when specified or when indicated or shown on the Drawings.
  2. Any construction sheeting and bracing which the Contractor has placed to facilitate his work may be ordered in writing by the Engineer to be left in place. The right of the Engineer to order sheeting and bracing left in place shall not be construed as creating an obligation on his part to issue such orders. Failure of the Engineer to order sheeting and bracing left in place shall not relieve the Contractor of his responsibility under this Contract.

### 3.2 REPLACING, MOVING AND REPAIRING OF EXISTING UTILITIES

- A. The Contractor shall:
  1. replace, move, repair and maintain all utilities and all other structures encountered in the work
  2. coordinate and communicate with applicable utility companies

3. repair all damage done to any of the said structures and appurtenances through his acts or neglect and shall keep them in repair during the life of this contract. The Contractor shall in all cases leave them in as good condition as they were previous to the commencement of the work and to the satisfaction of the Engineer.

### 3.3 DEWATERING

- A. Drainage and Removal of Water
  1. The Contractor shall dispose of water from the Work in a suitable manner without damage to adjacent property or structures.
  2. The Contractor shall, when ordered by the Engineer, construct tight bulkheads across trench and provide pumps suitable for the removal of any water which may be encountered or which may accumulate in the trenches. Unless otherwise provided for in the Contract Documents, drainage water will not be permitted to flow through the conduit.
  3. The trench shall be kept free from sewage and storm, surface, and subsurface water to at least 2 feet below the bottom of the excavation.
  4. Where open water courses, ditches, or drain pipes are encountered during the progress of the Work, the Contractor shall provide protection and securing of the continuous flow in such courses or drains and shall repair any damage that may be done to them.

### 3.4 EXCAVATION CLASSIFICATION

- A. All excavated materials are unclassified as defined in Article 1.3.

### 3.5 GENERAL EXCAVATION

- A. All necessary excavation for buildings, structures, pavements, and site improvements shall be performed to accommodate the completion of all related Contract Work.
- B. The Drawings show the horizontal and the lower limits of structures. The methods and equipment used by the Contractor when approaching the bottom limits of excavation shall be selected to provide a smooth surface and to prevent disturbing the soil below the bottom limits of excavation. All soil loosened during excavation shall be removed from the bottom of the excavation.
- C. Conform to elevations and dimensions shown within a tolerance of plus or minus 0.10 feet, and extending a sufficient distance from footings and foundations to permit placing and removal of concrete formwork, installation of services, other construction, and for inspection.
- D. Excavation which is carried below the bottom limits of structures shall be classified as Unauthorized Excavation, unless said excavation below bottom limits of structures has been authorized by the Engineer prior to each occurrence.

### 3.6 TRENCH EXCAVATION

- A. Excavation for trenches in which pipelines, sewers, and conduits are to be installed shall provide adequate space for workmen to space and joint pipe properly, but in every case the trench shall be kept to a minimum width. The width of trench shall not exceed the limits shown on the Drawings.
- B. Excavation shall be to the depth necessary for placing of granular bedding material under the pipe as shown on the Drawings. If over-excavation occurs, the trench bottom shall be filled to grade with compacted granular bedding material.
- C. Trenching operations shall not be performed beyond the distance that will be backfilled and compacted the same day.
- D. In general, backfilling shall begin as soon as the conduit is in approved condition to receive it and shall be carried to completion as rapidly as possible. New trenching shall not be started when earlier trenches need backfilling or the surfaces of streets or other areas need to be restored to a safe and proper condition.

### 3.7 EXCAVATION OF UNSUITABLE MATERIALS

- A. Unsuitable materials existing below the Contract bottom limits for excavation shall be removed as directed by the Engineer. Such excavation shall not exceed the vertical and lateral limits as prescribed by the Engineer.
- B. In utility trenches, the voids left by removal of unsuitable excavated material shall be filled with AASHTO M 43 No. 1 and No. 2 aggregate conforming to the material requirements of Article 2.1 of this Section.
- C. In excavations other than utility trenches, the voids left by removal of unsuitable excavated material shall be filled with material consisting of either: (1) Special Backfill Material; (2) Class B concrete; or (3) Low Strength Mortar Backfill, whichever is ordered by the Engineer.
- D. Removal of unsuitable excavated material and its replacement as directed will be paid on basis of Contract Conditions relative to Changes in Work unless specific unit prices have been established for excavation of unsuitable material.

### 3.8 DISPOSAL OF UNSUITABLE AND SURPLUS MATERIAL

- A. It shall be the responsibility of the Contractor to dispose of all surplus material that cannot be used in backfill or embankments at his expense outside the limits of the project. Unsuitable excavated material, including rock or large boulders, shall be disposed of outside the limits of the project.
- B. Surplus material may be wasted adjacent to or incorporated in the regular construction only when ordered in writing by the Engineer.

### 3.9 BACKFILL

#### A. Pipelines, Sewers and Conduits

1. All pipe shall have bedding extending the width of the trench with depth in conformance with the Drawings. The bedding material shall be thoroughly compacted by tamping until no further densification is possible.
2. Pipe cover material shall be used for filling above the pipe bedding along the sides of the pipe and to a height of twelve (12) inches over the top of the pipe. The pipe cover material shall be brought up evenly on both sides of the pipe to eliminate the possibility of lateral displacement of the pipe and shall be thoroughly compacted by tamping until no further densification is possible. Care shall be taken to spade the aggregate under the pipe haunch below the spring line.
3. All trenches and excavations shall be backfilled immediately after pipe is laid therein, unless otherwise directed by the Engineer.
4. After the pipe cover has been placed and compacted around the pipe as specified above, the remainder of the trench may be backfilled by machine. The backfill material shall be deposited in eight (8) inch horizontal layers, and each layer shall be thoroughly compacted to the specified density by approved methods before a succeeding layer is placed. In no case will backfilling material from a bucket be allowed to fall directly on a pipe and in all cases the bucket must be lowered so that the shock of the falling earth will not cause damage.

#### B. Structures

1. Backfilling shall not commence before concrete has attained specified strength. Do not use equipment for backfilling and compaction operations against structures that will overload the structure.
2. Backfilling around and over structures shall be carefully placed and tamped with tools of suitable weight to a point one (1) foot above the top of same. Additional backfill may be required to protect the structure from damage from heavy equipment. Backfill shall be placed in uniform layers not exceeding eight (8) inches in depth. Each layer shall be placed, then carefully and uniformly compacted to the specified density so as to eliminate the possibility of displacement of the structure.
3. After the backfill has been placed and compacted around the structure to the height specified above, the remainder may be backfilled by machine. The backfill material shall be deposited in eight (8) inch horizontal layers, and each layer shall be thoroughly compacted to the specified density by approved methods before a succeeding layer is placed. In no case will backfilling material from a bucket be allowed to fall directly on a structure, and in all cases the bucket must be lowered so that the shock of the falling earth will not cause damage.

- C. Where any new, proposed, or future pavement, driveway, parking lot, curb, curb and gutter, or walk is to be placed over a backfilled area, Special Backfill material shall be used for any portion of the trench falling within the pavement prism.

- D. Where it is necessary to undercut or replace existing utility conduits and/or service lines, the excavation beneath such lines shall be backfilled the entire length with approved Granular Pipe Embedment Material compacted in place in eight (8) inch layers to the required density. The approved Granular Pipe Embedment Material shall extend outward from the spring line of the conduit a distance of two (2) feet on either side and thence downward at its natural slope.

### 3.10 LOW STRENGTH MORTAR BACKFILL

- A. Low strength mortar backfill shall be discharged from the mixer as recommended by the supplier and approved by the Engineer.
- B. Low strength mortar backfill may be placed in the trench in as few lifts as may be practical.
- C. Secure conduit or pipelines before placing low strength mortar backfill to prevent conduits and pipelines from floating during backfilling.
- D. For low strength mortar backfill placed against existing structures of unknown strength, backfill material shall be brought up uniformly in maximum 12 inch lifts and allowed to cure for a minimum of 24 hours or until it can carry a person's weight without leaving imprints before the next lift is placed.
- E. Low strength mortar backfill shall be brought up to subgrade elevation or the pavement prism, whichever may be applicable.

### 3.11 EMBANKMENT

- A. In making fill for embankment, the surface of the existing ground shall be cleared, grubbed, stripped of organic material, plowed, compacted according to the requirements specified in this Section, and stepped on slopes so as to enable bond or firm bearing for the new fill. The materials for these fills shall be selected of approved materials free from organic matter and placed in horizontal layers not exceeding eight (8) inches in thickness when loose, each layer being thoroughly compacted. Materials shall not be placed when fill or foundation is frozen.
- B. Where fill is to be placed on side slopes steeper than one (1) vertical to six (6) horizontal, steps shall be formed into the slope before any embankment is placed. These steps shall be cut at vertical intervals at no more than two (2) feet and shall have a horizontal dimension of not less than three (3) feet.
- C. As fill progress, the top shall be kept crowned or sloped for drainage. No pavement shall be placed upon embankment until it meets compaction testing requirements.
- D. Fills that abut or contain concrete or masonry structures shall be placed with care to avoid undue or unbalanced loads on these structures.

- E. Following the completion of embankment, all slopes shall be neatly and evenly dressed to proper elevation, grade and dimension.

### 3.12 SUBGRADE

- A. All soil subgrade shall be prepared in accordance with this subsection.
- B. Drainage
  - 1. The surface of the subgrade shall be maintained in a smooth condition to prevent ponding of water after rains to insure the thorough drainage of the subgrade surface at all times.
- C. Unsuitable Subgrade
  - 1. Where unsuitable subgrade or subgrade not meeting the required bearing capacity is encountered in cuts, due to no fault or neglect of the Contractor, in which satisfactory stability cannot be obtained by moisture control and compaction, the unstable material shall be excavated to the depth required by the Engineer.
  - 2. Suitable material required for the embankment to replace the undercut will be paid on basis of Contract Conditions relative to changes in Work.
  - 3. Where soft subgrade in cuts is due to the failure of the Contractor to maintain adequate surface drainage as required in this article, or is due to any other fault or neglect of the Contractor, the unstable condition shall be corrected as outlined above at no expense to the Owner.
- D. Full Width New Pavement Construction
  - 1. After the surface of the subgrade has been shaped to approximate cross section grade, and before any pavement, base or subbase material is placed thereon, the subgrade shall be compacted. When the rolling is completed, all surface irregularities shall be corrected and the surface of the subgrade shall be shaped as necessary to conform to the grade and cross section shown on the Drawings within the tolerance set forth in this Section and shall be so maintained until the overlying course is in place.

### 3.13 TOLERANCES

- A. The Contractor shall check the work under this item with templates, slope boards or other devices satisfactory to the Engineer. The completed work shall conform to the Drawings within the following tolerances:
  - 1. For subgrade, the surface shall at no place vary more than ½ inch from a ten-foot straight edge applied to the surface parallel to the centerline of the pavement, nor more than ½ inch from subgrade elevation established by construction layout stakes.

### 3.14 CONSTRUCTION WITH MOISTURE AND DENSITY CONTROL

- A. All backfill and embankments, except rock embankments, shall be constructed using moisture and density control. All subgrade, except rock and shale in cut sections, shall be constructed using moisture and density control.
- B. Backfill, embankment and subgrade material which does not contain sufficient moisture to be compacted in accordance with the requirements of Article 3.17 of this Section shall be sprinkled with water as directed by the Engineer to bring the moisture content to within the range of optimum plus or minus three (3) percent. Water shall be thoroughly incorporated into the material by means of discs or other approved equipment.
- C. Backfill, embankment and subgrade material containing excess moisture shall be dried, prior to installation, to a moisture content not greater than three (3) percentage points above optimum, except that for material within the moisture content range specified herein that displays pronounced elasticity or deformation under the action of loaded construction equipment, the moisture content shall be reduced to optimum or below if necessary to secure stability. For subgrade material, these requirements for maximum moisture shall apply at the time of compaction of the subgrade and also at the time of placing pavement or subbase. Drying of wet soil shall be expedited by the use of plows, discs, or by other approved methods when so ordered by the Engineer.

### 3.15 COMPACTION REQUIREMENTS

- A. The bottom of excavations upon which concrete foundations or structures are to be placed shall be compacted so as to obtain 100% of maximum dry density per ASTM D-698 in the top twelve (12) inches.
- B. The top twelve (12) inches of stripped original subgrade and final subgrade shall be compacted to not less than 100% of maximum dry density per ASTM D-698.
  - 1. Subgrade under new, proposed, or future pavement shall be compacted 18 inches beyond the edge of pavement, paved shoulders or paved medians.
- C. Compaction of subgrade for sidewalks (regardless of paving material) shall be 100% of maximum dry density per ASTM D-698 in the top six (6) inches.
- D. Compaction of non-paved areas shall be 90% of maximum dry density per ASTM D-698.
- E. Aggregate pipe embedment and aggregate backfill around structures shall be compacted to not less than 100% of maximum dry density per ASTM D-4253 and ASTM D-4254.
- F. Final backfill shall be compacted to not less than 100% of maximum dry density per ASTM D-698.



- G. Fill placed within the interior of structures shall be compacted to not less than 100% of maximum dry density per ASTM D-698.
- H. Embankment shall be placed and compacted in layers until the density is not less than the percentage of maximum dry density indicated in the following table determined by ASTM D-698.

**EMBANKMENT SOIL COMPACTION REQUIREMENTS**

Maximum Laboratory Dry Weight <u>Pounds/Cubic Foot</u> 90-104.9 105-119.9 120 and more	Minimum Compaction Requirements Percent Laboratory <u>Maximum</u> 102 100 98
---	--

- I. Test Sections
  - 1. If it is determined by the Engineer that the composition of the material is such that it cannot be tested for density using a nuclear densometer or other methods; or where, in the opinion of the Engineer, in-place compaction testing is not feasible; and if approved by the Engineer, the Contractor may construct a test section to demonstrate acceptable compactive effort in lieu of in-place compaction testing. Test sections shall be constructed at no additional cost to the Owner.
  - 2. The test section shall be completed by repeatedly compacting the material until no further density is achieved. This value shall be the Minimum Test Section Density (MTSD). The compaction equipment used to complete the test section shall be of suitable size to compact the material and shall be the same equipment used to compact the in-place material.
  - 3. The test section shall be constructed with moisture density control as specified in this Section.
  - 4. The material shall be compacted to at least 98% of the MTSD.
  - 5. Each lift of in-place fill or backfill shall be densified using a compactive effort equal to or greater than the effort applied to achieve the MTSD; i.e., if six passes were required to achieve MTSD, then each lift of material shall be compacted using six or more passes.
  - 6. Construct a new test section when, in the opinion of the Engineer, the fill or backfill material has changed character or when the supporting material has changed character.

**3.16 GRADING**

- A. Uniformly grade areas to a smooth surface, free of irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and elevations indicated.

1. Provide a smooth transition between adjacent existing grades and new grades.
  2. Cut out soft spots, fill low spots, and trim high spots to comply with required surface tolerances.
- B. Site Grading
1. Slope grades to direct water away from buildings and to prevent ponding. Finish subgrades to required elevations within the following tolerances:
    - a. Lawn or unpaved areas shall be graded to plus or minus  $\frac{1}{2}$  inch.
    - b. Walks shall be graded to plus or minus  $\frac{1}{2}$  inch.
- C. Grading inside Building Lines
1. Finish subgrade to a tolerance of  $\frac{1}{2}$  inch when tested with a 10-foot straightedge.

END OF SECTION 310000

## SECTION 312323.13 – COMPACTED BACKFILL

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. The Contractor shall furnish, place and compact all the materials needed from select excavated materials or furnish additional suitable material if the excavated material is deemed unsuitable or the moisture content is not or can not be made to be within acceptable tolerances of optimum moisture to achieve the specified compaction.
- B. This specification shall be used only where backfill is not under existing or proposed pavement or within the 1:1 zone of influence.

### PART 2 - PRODUCTS

#### 2.1 MATERIALS

- A. Suitable excavated material as specified in ODOT Item 203.

### PART 3 - EXECUTION

#### 3.1 PLACING

- A. Compacted backfill shall be properly placed in layers sufficient to meet the compaction requirement of 95% of maximum laboratory dry density per ASTM D 698 throughout the entire layer and thoroughly compacted with mechanical compaction equipment with moisture adjustment as needed. Should after settlement occur, the Contractor must add and compact additional material, and he must maintain the backfill at the required finished grade or sub-grade until the project is satisfactorily completed and during the correction period.
- B. Approved mechanical compaction equipment shall be used for tamping backfill. Flooding, jetting or puddling of backfill will not be permitted.

END OF SECTION 312323.13

## SECTION 312323.14 – COMPACTED GRANULAR BACKFILL

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. The Contractor shall furnish, place and compact all the materials needed.

### PART 2 - PRODUCTS

#### 2.1 MATERIAL

- A. Aggregate shall be ODOT 304 crushed limestone. Crushed gravel or slag products are unacceptable.
- B. Contractor shall submit current test reports for the lot(s) of the material to be supplied.

### PART 3 - EXECUTION

#### 3.1 PLACING AND COMPACTING

- A. Compacted granular backfill shall be properly placed in layers sufficient to meet the compaction requirement of 100% of maximum laboratory dry density per ASTM D 698 throughout the entire layer and thoroughly compacted with mechanical compaction equipment with moisture adjustment as needed. Should after settlement occur, the Contractor must add and compact additional material, and he must maintain the backfill at the required finished grade or sub-grade until the project is satisfactorily completed and during the correction period.
- B. Approved mechanical compaction equipment shall be used for tamping backfill. Flooding, jetting or puddling of backfill will not be permitted.

END OF SECTION 312323.14

## SECTION 312333 - UNDERGROUND CONDUIT INSTALLATION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. The Construction Drawings and General Provisions of this Contract including the General and Supplementary Conditions, Specific Project Requirements, Proposal, and all referenced standard specifications apply to work defined in this section.

#### 1.2 DESCRIPTION

- A. This work shall consist of the construction or reconstruction of underground pipe conduits in accordance with these specifications and in reasonable close conformance to the lines and grades shown on the detailed plans or as otherwise established by the Engineer.
- B. This work shall include excavating for the conduit, fittings, and appurtenances; clearing and grubbing and removal of all materials necessary for placement of the conduit except any items paid for separately; furnishing and placing bedding and backfill as required; constructing and subsequently removing all necessary cofferdams, cribs and sheeting; pumping and dewatering; making all conduit joints as required; installing all necessary conduit; joining to existing and proposed appurtenances as required; performing leakage tests as required; restoration of all disturbed facilities and surfaces. The work shall also include the maintenance of existing flow and service to facilities being modified. Procedures for such maintenance shall be as approved by the Engineer prior to any work commencing.

### PART 2 - MATERIALS

#### 2.1 CONDUIT

- A. All conduit utilized shall be of one type and size specified in the proposal meeting the requirements of the detailed material specification.
- B. Shop drawings, catalog cuts, and test certifications may be required by the Engineer for all conduit, fittings, and appurtenances.
- C. Aggregate for the bedding and backfill shall conform to the requirements of the plan detail or as modified in writing by the Engineer. All aggregates shall conform to ODOT 703 for soundness and gradation.
- D. All other materials utilized as part of this work shall meet their respective ASTM requirements.

## PART 3 - EXECUTION

### 3.1 REMOVAL OF STRUCTURES AND OBSTRUCTIONS

#### A. Pavement, Sidewalks, and Curbing

1. Removal of existing pavements, sidewalks, curbing, and similar structures shall end at an existing joint or a sawed joint. Sawed joints shall be straight, neat, and free from chipped or damaged edges.
2. For non-reinforced concrete, the saw cut shall be completely through concrete.
3. For reinforced concrete, the saw cut shall be completely through the steel and concrete.
4. If the concrete is coated with a bituminous surface or other material, the saw cut shall be as specified above.

#### B. Manholes, Catch Basins, and Inlets

1. Existing drainage structures and sanitary manholes designated by the Engineer to be removed shall be completely removed.
2. Manholes designated to be abandoned shall be removed to an elevation of at least 3 ft. below the finished subgrade or ground surface. The remaining void shall be filled with backfill material in accordance with Section 312323.13 - Compacted Backfill.
3. Live sewers connected to structures removed or abandoned shall be rebuilt through the area with new conduit. Sewer flow shall be maintained between removal and replacement operations. Abandoned sewers shall be sealed and made watertight with approved precast stoppers or masonry bulkheads.
4. All castings salvaged from abandoned or removed structures shall remain the property of the Owner and shall be cleaned and transported by the Contractor to a nearby site designated by the Owner or incorporated in the work where called for on the drawings.

#### C. Guardrail and Fence

1. Where necessary, existing guardrail and fence shall be carefully dismantled and stored for reuse or for salvage by the Owner.
2. Posts and other materials not considered salvageable by the Engineer shall be disposed of by the Contractor.
3. The Contractor will be required to replace, at no cost to the Owner, material lost or damaged by negligence or by the use of improper methods.

### 3.2 METHOD OF EXCAVATION

- A. All excavation shall be in open cut unless otherwise permitted by the Engineer. Loosening of material by blasting will not be permitted without written authorization by the Owner specifying both the extent and location of the blasting to be done. If permission is granted the Contractor shall submit in writing his means and methods of blasting to the Owner for approval. Blasting shall not begin until the Owner issues written approval of the means and method of blasting.

- B. Excavation shall be made to undisturbed finish subgrade to the depth below the bottom of the conduit or structure as shown on the Contract Drawings details.
- C. Trenches shall be excavated with vertical sides from the bottom of the trench to one (1') foot above the top of the conduit from which point sides may slope to ground surface, except that, in streets or roadways, trenches shall be excavated with near vertical sides to the top of the trench. Width of trench in the vertical section shall be excavated only as wide as necessary to accommodate a safety box and to provide free working space on each side of the conduit or structure according to the size of the conduit or structure and the character of the ground. In every case there shall be sufficient space between the conduit or structure and the sides of the trench to make it possible to thoroughly ram the bedding around the conduit or structure and to secure tight conduit joints, but in no case more than twelve inches on either side of conduit. In no case, however, shall the width of the trench at the top of the conduit exceed the dimensions as shown on the contract drawings. In no case will it be permitted to excavate conduit trenches with sides sloping to the bottom.
- D. The trench bottom shall be firm and uniform for its full length. Should unstable material be encountered below plan subgrade, it shall be removed to a depth directed by the Engineer. Replacement of the additional excavation shall be with the specified bedding material or as otherwise directed by the Engineer.
- E. In the case the flow line is changed not to exceed one (1) foot or it becomes necessary to remove unstable material in an amount not to exceed one (1) foot, the same shall be done at one contract bid price or amount. When the flow line is lowered more than (1 foot) or if it becomes necessary to remove more than (1 foot) of unsuitable material below the bottom of the trench, compensation will be provide therefore in a supplemental agreement for the excavation and backfill beyond (1 foot).

### 3.3 UNAUTHORIZED EXCAVATIONS

- A. All excavations carried outside of the lines and grades given or specified, together with the disposal of such material, and all excavations and other work resulting from slides, cave-ins, swellings or upheavals shall be at the Contractor's own cost and expense. All spaces resulting from unauthorized excavations or from slides or cave-ins shall be refilled at the Contractor's expense with suitable material as specified in Section 312323.14, "Compacted Granular Backfill" in designated areas shown on the contract drawings or specified under this Section. Compaction requirements shall be in accordance with these specifications.

### 3.4 SHEETING AND SHORING

- A. The Contractor shall be responsible for supporting and maintaining all excavations required even to the extent of sheeting or shoring the sides and ends of excavations with timber or other satisfactory supports. If the sheeting, braces, shores, stringers, waling timbers, or other supports are not properly placed or are insufficient, the Contractor shall provide additional or stronger supports. The requirements of sheeting or shoring or of the addition

of supports shall not relieve the Contractor of his responsibility for their sufficiency. All trench protection and sheeting and shoring must conform to the regulations of both the Ohio State Industrial Commission (OSIC) and the Federal Occupational Safety and Health Act (OSHA) and will be subject to their respective inspections. All orders of OSIC and OSHA representatives must be complied with by the Contractor.

- B. All sheeting and shoring shall be removed where and when required and, upon its removal, all voids filled. If any sheeting or shoring is ordered to be left in place, it shall be cut-off as directed. In compensation for the sheeting and shoring left in place, if any, shall be by prior written change order.

### 3.5 REMOVAL OF WATER

- A. All conduit shall be installed in a dry and stable trench. The Contractor may pump or otherwise remove any water, sewage, or other liquid that may be found or may accumulate in the trench.
- B. If, in the opinion of the Contractor, dewatering pumps and equipment are required to maintain a dry and stable trench, suitably sized pumps shall be provided to meet the requirements. The manner and spacing of well points shall be at the Contractor's discretion.
- C. Excess water shall not be considered reason for undercut of trench bottom.
- D. The Contractor shall maintain the pumps for the duration of their need including a satisfactory discharge outlet. Power for the pumps shall be electric unless otherwise approved by the Engineer. Noise abatement may be required for any on-site generators in residential areas.

### 3.6 BEDDING FOR LAYING CONDUIT

- A. Bedding shall conform to the requirements of the plan detail unless otherwise modified by the Engineer.
- B. All granular bedding material shall be compacted to 95 percent of maximum laboratory dry density.
- C. All pipe bedding shall be of the gradation(s) specified and be limestone. Slag may not be used and gravel may be used with permission of the Engineer.

### 3.7 LAYING CONDUIT

- A. Except as otherwise permitted by the Engineer, all conduit shall be laid starting at the outlet end. Pressure conduits may be laid from either direction however the joints shall be such that the bell is upgrade or toward normal pressure.
- B. Line and grade for gravity conduits shall be established by the use of sufficient means to maintain acceptable installation tolerances and allow for reasonable checking observation by the Engineer.



- C. Line and grade shall be established and maintained over a length of fifty (50) feet minimum. Cut sheets establishing grade at fifty (50) foot intervals shall be provided to the Engineer prior to beginning work.
- D. The Contractor shall provide sufficient equipment and workers to safely handle and lay all conduit included as part of this work. All storage of materials shall be in a manner as to avoid damage to either surface prior to placement.
- E. The Contractor shall inspect each piece of conduit prior to placement in the trench and any unsatisfactory conduit shall be rejected.
- F. Conduit shall not be laid in water, mud, or any otherwise unsuitable trench. The conduit shall not be pushed into or allowed to fall to the bottom of the trench. Handling of the conduit shall be in conformance to the manufacturer's recommendations.
- G. The conduit shall be kept clean and any open ends of installed conduit shall be closed when work is not in progress.
- H. Jointing of the conduit shall be in accordance to the requirements of the manufacturers and as required by the specification material type. Any deviation from these acceptable methods requires approval of the Engineer.
- I. Testing of joints, where required, shall be done in accordance with the Specification for Testing. Should any section fail to meet test requirements, the Contractor shall make suitable corrections, at their cost, until the requirements are met.

### 3.8 SERVICE CONNECTIONS

- A. In general, and as called for on the drawings, as required or as ordered, provision shall be made in the sewers for service connections by inserting a wye branch for each service connection with a branch size called for by the contract drawings but never less than six (6) inch, in the sewer at location shown, where required or ordered, for sewers to ten (10) feet in depth. For sewers exceeding ten (10) feet in depth, or indicated on the plans, the Contractor shall construct a riser, as per detail, in such manner, that the top of the riser shall be not less than seven (7) feet below grade or at such elevation as to properly receive the required service connection, with full regard to elevation of service sewer and slope from building or structure to the sewer which shall not be less than one percent (1%). Risers are to be encased in sonotube filled with No. 57 Limestone as shown on the contract drawings.
- B. The location of service connections is shown in a general way on the contract drawings. The Owner may also increase the number of connections or delete some connections as the sewer is being built, or increase the size of connections when it deems such advisable.

### 3.9 FINAL BACKFILL

- A. Final backfill shall be installed from the top of the Pipe Embedment to the final grade. Final backfill of all conduit trenches shall conform to the requirements of the plans and details, Section 312323.13 "Compacted Backfill". All final backfill under existing or proposed pavement or structures or within the 1:1 zone of influence of existing or proposed pavement or structures shall be "Compacted Granular Backfill". All final backfill not under existing or proposed pavement or structures or within the 1:1 zone of influence of proposed pavement or structures shall be "Compacted Backfill".
- B. Unless otherwise directed, all forms, bracing and lumber shall be removed during backfilling and the cavities and voids resulting from the removal shall be backfilled and compacted to 100% of Standard Proctor.
- C. The Contractor must use special care in placing backfill so as to avoid injuring or moving the conduit or structure when compacting the backfill.
- D. In areas used for temporary maintenance of traffic the top layer of final backfill from the elevation of the existing subbase base interface to the existing or proposed surface(s), shall be ODOT Item 304 Aggregate Base to provide a temporary surface traffic course.
- E. Should after settlement occur, the Contractor must add and compact additional material.
- F. Machine mounted mechanical tamper shall be used for backfill compaction. Flooding, jetting or puddling of backfill will not be permitted.
- G. Excavated material in excess of that needed for backfilling and all unsuitable material shall be disposed of by the Contractor at his own expense and the cost of such disposal shall be included in the unit or lump sum prices bid.

### 3.10 TESTING AND ACCEPTANCE

- A. Prior to final acceptance of the conduit or the placing of the conduit into service, testing and/or televising may be required.
- B. For all sanitary, water, or other pressured conduits, pressure testing shall be required in accordance to the specifications contained herein. Televising shall be required for all sanitary sewer and may be required for storm sewers as outlined or required by plan note.
- C. Final television inspection of conduit shall be performed by an experienced company and in a format satisfactory to the Owner. Televising shall be done in the presence of the Engineer unless so waived. The Engineer shall be provided with unedited video tapes and two (2) copies of the video log.
- D. Televising shall not be done until all known repairs are completed and the line has been suitably flushed.

### 3.11 SITE RESTORATION

- A. Restoration of the disturbed project area shall begin immediately after backfilling has been completed. All excess material, debris, and excavation shall be disposed of by the Contractor.
- B. Restoration of paved surfaces and of seeded areas shall be done as soon as conditions permit. The manner in which this work shall be done is defined in other specifications or the contract plans.
- C. While payment for site restoration may be included in other items, final acceptance of the underground conduit shall not occur until all work is complete. Where no separate pay items exist for restoration work, the Engineer may determine an appropriate value for this work to be retained until its completion.

END OF SECTION 312333

## SECTION 321000 - PAVEMENT REPLACEMENT

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. The Contractor shall furnish all of the equipment, labor and materials necessary to install, replace, and/or restore existing pavement structures together with their respective appurtenances as shown on the plans and as specified herein. This work shall include all of the subgrade preparation, subbase, base, intermediate pavement course(s), and finish pavement courses together with curbing, guttering, tack and/or prime coating, sealing and other pertinent work as necessary to meet the conditions of this contract.

#### 1.3 QUALITY ASSURANCE

- A. In addition to requirements of these specifications, comply with manufacturer's instructions and recommendations for work.

#### 1.4 REPAIR OR REPLACEMENT WORK

- A. For the repair and/or replacement of all existing pavement structures and their respective appurtenances that are removed and destroyed or otherwise damaged by the Contractor in the course of his performance of the work required under this contract, the Contractor shall furnish all equipment, labor, and materials as necessary to properly restore to a condition equal to that at his entry, and to the satisfaction of the Engineer, the Ohio Department of Transportation, the County Engineer, City Engineer, all cinder, slag, gravel, water-bound macadam, bituminous macadam, asphalt and brick or concrete driveways, curbs, sidewalks and roadways in strict accordance with the drawings and as specified herein.
- B. In general, this item will include concrete, steel reinforcement, brick, stone, slag, cinders, gravel, asphalt and other bituminous materials and curbs, gutters, driveway culverts, road and curb drains and the demolition, excavation and removal of existing driveways, sidewalks and roadways.

#### 1.5 REFERENCE TO OTHER PARTS

- A. Other sections of these specifications shall apply, as and where applicable to this section and such sections will be the same as though they were included in this section.

- B. For all old work where pavement is being repaired and/or replaced as a result of damages occurring thereto during the course of the work of this contract, all clearing and grubbing, removal and storage of topsoil, excavation and/or placing of compacted fill and granular backfill, shall be done as required under other parts of these specifications.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. Generally, for all repair and replacement work, all new materials shall match the existing and adjoining work in both composition and quality unless otherwise ordered, specified herein, and/or shown on the drawings. In any stone driveway or roadway, the material used for stone fill shall conform to the existing material.

## PART 3 - EXECUTION

### 3.1 CONSTRUCTION

- A. All pavement work shall be done in strict accordance with the specifications of the governmental body concerned and the latest ODOT specifications as applicable or at the direction of the Engineer.
- B. All pavements disturbed by the Contractor's operations shall be relaid to the thickness of the adjoining pavement and, in all cases, the restoring of pavements, shall apply both to foundation courses and to the wearing surface.
- C. Should cracks or settlements appear in adjoining pavements, the paving shall be removed to the extent necessary to secure firm and undisturbed bearing and shall be replaced in a satisfactory manner.
- D. No permanent pavement shall be installed, repaired, and/or restored unless, or until, in the opinion of the Engineer, the condition of the backfill is such as to properly support the pavement.
- E. Where new or replacement concrete pavement or base is placed adjacent to existing concrete pavement or base, contraction joints shall be provided in the new or replacement pavement so as to form a continuous joint with that in the existing pavement.

### 3.2 ROADWAY SUBGRADE

- A. The entire area to be occupied by the roadways and parking areas shall be cleared, topsoil removed and stored, and the excavation or compacted fill made as required and brought to the proper cross-sections. Pipe trenches and other excavations shall be backfilled as required, and thoroughly compacted within the limits of the roadways or parking areas.

- B. After the surface of the subgrade has been properly shaped and before any stone or slag is placed, the entire subgrade shall be thoroughly rolled and compacted to a depth of 12 inches under this section. Rolling shall be done with an approved type of self-propelled roller, weighing not less than ten (10) tons. All hollows and depressions which develop during the rolling shall be filled with acceptable materials, and the subgrade rerolled. The process of filling and rolling shall be repeated until no depressions develop, and the entire subgrade has been brought to a uniform condition of stability.
- C. All places which, in the opinion of the Engineer cannot be properly rolled, shall be tamped with handheld mechanically or pneumatically powered tampers.
- D. In making the compacted fill and in doing the final subgrade rolling, the Contractor shall see that the material to be compacted and/or rolled has the proper moisture content to secure maximum compaction. When, in the opinion of the Engineer, the material is too wet, the compacting shall be delayed until the material has dried sufficiently. When, in the opinion of the Engineer, the material is too dry, the material shall be sprinkled with water in an amount to secure the proper moisture content.

### 3.3 TRAFFIC PAINT

It shall be the responsibility of the Contractor to replace all existing pavement markings in the style and at the locations that existed prior to this work. The Contractor shall make records of these markings as they exist and will supply these records to the Engineer prior to the start of any work. In the absence of such documentation, the Owner's discretion shall prevail. Unless specifically paid for in other items, the cost of pavement marking replacement shall be included in the Contractor's bid price of pavement.

END OF SECTION 321000

## SECTION 321216 - ASPHALT CONCRETE PAVING AND MATERIALS

### SECTION 1 - MATERIALS

- 1.1 The asphalt concrete mixture and installation thereof shall meet Ohio Department of Transportation (ODOT) Specifications except as modified in these specifications.
- 1.2 In the ODOT Specifications substitute "Engineer" for "Department" (except as stated below in reference to ODOT 403 for Department VA testing and acceptance).
- 1.3 No steel slag shall be used as coarse or fine aggregate for any asphalt concrete.
- 1.4 All asphalt cement utilized on this project shall meet AASHTO Provisional Standard MP1 or any superseding AASHTO specification for performance graded asphalt cement binder in conformance with PG 64-22.
- 1.5 The following exceptions shall be made for the Asphalt Concrete Surface Course:
  - A. The coarse aggregate material shall be only limestone.
  - B. No Recycled Asphalt Product (R.A.P.) will be permitted.
- 1.6 Except where designated otherwise in the plans or specifications all asphalt concrete mixes shall be designed for medium traffic volumes. Where light or heavy traffic pavements are designated in the plan, the contractor shall use an asphalt concrete mix designed for such traffic conditions.
- 1.7 Acceptance of the mixture will be based upon the certification that the mixture was produced according to the approved JMF within the production control and composition tolerances of the specifications. The Contractor shall hire and pay for an independent testing lab approved by the Engineer to perform all sampling, testing, monitoring, analysis and certification required by the Laboratory, Monitoring Team or Department in ODOT 403 and 441. All work by the independent laboratory shall be performed by personnel with ODOT Level II Bituminous Concrete certification.
- 1.8 ODOT 401.20 - "Asphalt Binder Price Adjustment" shall not apply to this contract.
- 1.9 Monument box and valve box risers shall be East Jordan Iron Works No. 8626, No. 8631, or approved equal. The Contractor shall follow the manufacturer's recommended installation procedure. New manhole frames and grate or frame and cover shall be EJIW 1710.
- 1.10 Brick used for manhole, catch basin, or inlet basin castings adjusted to grade under ODOT 611.10 Method D.1. shall be red shale or clay sewer brick meeting the requirements of ASTM C32 sewer brick, grade SM.
- 1.11 Risers used for manhole castings adjusted to grade under ODOT 611.10 Method D.2. shall be manufactured by Manhole Systems, Model MS-101TB, or approved equal.

- 1.12 All materials delivered to this project must have been weighed on a platform scale with electronic imprinter to show gross, tare, and net weights. No payment will be made for materials which are not correctly weighed as necessary. Material weight shall not exceed the current legal allowable limit.
- 1.14 Unless specified elsewhere in the specifications, material for berms shall be limestone only. Recycled concrete and asphalt concrete will not be permitted.

## SECTION 2 - PAVING EQUIPMENT

- 2.1 All spreading equipment shall be self propelled. The Contractor shall identify the make and model of the paving machine that will be used for the intermediate and surface courses for approval prior to the pre-construction meeting.
- 2.2 All equipment, tools, and machines used in the performance of this work shall be maintained in satisfactory working order at all times. The Contractor shall be prepared to furnish proof of certification that all equipment to be used on the project has been calibrated within the past six (6) months.

## SECTION 3 - GENERAL - PAVING

- 3.1 All paving shall be done on a single-lane basis.
- 3.2 If traffic loop detectors are encountered and broken, the Contractor is to repair as per local specifications. The cost for this work will be paid under the loop detector replacement bid item, if any; at negotiated unit prices; or by time and materials as directed by the Engineer.
- 3.3 Tack Coat, Item 407, shall be applied at the rate of from 0.05 to 0.15 gallons per square yard as appropriate for the surface conditions with sand cover if required.
- 3.4 Driveway aprons shall be matched to new pavement with 24" transition sections or as shown on the drawings or required by the Engineer.
- 3.5 Unless otherwise shown on the drawings, jointing of new to existing pavement shall be by milled butt joints six (6) feet in width (or as shown on the plans) from edge of pavement to edge of pavement. Depth of this milled area shall equal the total of subsequent intermediate course and surface course as specified.
- 3.6 One (1) copy of each hauled/weighed material truck load ticket (plant ticket) for materials incorporated in this project shall be provided to the project representative daily. If a partial load is used, the Contractor's foreman and the project representative shall confer and come to an agreement as to what portion of the product was used. The percent of material of this load, as reported by the project representative, is what shall be recorded as utilized.



- 3.7 For variable depth courses where tonnage tickets are used for determining quantities for payment, the conversion to cubic yards shall be number of tons verified and approved by the Engineer divided by 2.00 regardless of the actual density of the mix.
- 3.8 Positive drainage is to exist subsequent to the completion of the surface course. The Contractor shall take any necessary measures to assure positive drainage of the surface course. It shall be the responsibility of the Contractor to repair any low/puddled areas at his own cost by milling out the affected areas to a minimum depth equal to the nominal depth of the course being repaired and replacing with the specified asphalt concrete to grades that will correct the drainage problem.
- 3.9 Surface tolerances for all completed surface courses shall be as noted in ODOT 401.19. This tolerance shall apply regardless of whether or not an intermediate course is installed.
- 3.10 At the direction of the Engineer, periodic weight checks of asphalt concrete in loaded trucks shall be made by the Contractor and verified by the Engineer.
- 3.11 All quality control testing data performed on material incorporated into this project shall be forwarded to the Engineer for review as soon as it is available.
- 3.12 Quantity verification (but not necessarily payment quantity) for all asphalt concrete incorporated into the work shall be by weight tickets as produced by the plant or supplier or other means approved by the Engineer. Tack coat shall be verified by a ticket filled out and signed by the Contractor's tack truck driver based on weights taken or observations of level indicators. All verification tickets are required to be submitted to the Engineer on the day the material is incorporated into the work; however, the Engineer may, at his sole discretion, accept verification tickets for any items up to seven (7) calendar days subsequent to the work being performed. **After that date, additional verification tickets for material will not be accepted for consideration of payment.**
- 3.13 No work is to be performed without the presence of the Engineer or his designated Project Representative. Forty-eight (48) hour advance notice of work shall be given to the Engineer and Owner by the Contractor.
- 3.14 When any surface course or intermediate course is placed on a new intermediate course while that course is still clean and within ten (10) days of installation of that course, a tack coat will not be required. When any surface course or intermediate course is placed on a new intermediate course that is not clean or is not placed within ten (1) days after installation of that course, the Contractor shall provide a tack coat, Item 407, at his own expense, as directed by the Engineer.
- 3.15 All edges of surface courses abutting curbs or other appurtenances shall be sealed with hot AC-20.

END OF SECTION 321216

## SECTION 329200.19 - SEEDING AND MULCHING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. Installation of seeded areas shall be to the extent shown on Contract Drawings and shall include supplying all seed, soil conditioning materials, mulching materials and watering and the incorporation of these materials into the work as specified.
- B. The Contractor shall place stockpiled topsoil in those areas requiring seeding. If the quantity of stockpiled topsoil is insufficient, the Contractor shall furnish and install additional topsoil as required to complete the work.

#### 1.3 QUALITY ASSURANCE

- A. Any subcontract restoration shall be to a qualified firm specializing in landscape work.
- B. Topsoil: Before delivery of topsoil, furnish Architect/Engineer with written statement giving location of properties from which topsoil is to be obtained, names and addresses of owners, depth to be stripped, and crops grown during past 2 years.

Contractor shall have a soils test done at his expense and analyzed by an approved testing agency, to determine soil amendments for topsoil and provide a copy to the Engineer prior to the start of fine grading.

- C. Seed: All seed specified shall meet the current specifications of O.D.O.T. as to the percentage purity, weed seed, and germination. All seed shall be approved by the State of Ohio, Department of Agriculture, Division of Plant Industry and shall meet the requirements of these specifications.

Contractor shall provide the Engineer with a list of the seed he intends to use, including, varieties of seed, labels, and suppliers name and phone number, four (4) weeks prior to the start of seeding, for approval.

#### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Packaged Materials: Deliver packaged materials in containers showing weight, analysis, and name of manufacturer. Protect materials from deterioration during delivery, and while stored at site.

## 1.5 JOB CONDITIONS

- A. Utilities: Determine location of underground utilities and perform work in a manner which will avoid possible damage. Hand excavate, as required. Maintain grade stakes set by others until removal is mutually agreed upon by parties concerned.
- B. Excavation: When conditions detrimental to plant growth are encountered, such as rubble fill, adverse drainage conditions, or obstructions, notify Engineer before planting.
- C. Soil Stabilization: The Contractor shall provide permanent or temporary soil stabilization to denuded areas within fifteen days after final grade is reached on any portion of the site. Any such area which will not be regraded for longer than fifteen days shall also be stabilized. Soil stabilization includes any measures which protect the soil from the erosive forces of raindrop impact and flowing water. Applications include seeding and or mulching. The Contractor shall consider time of year, site conditions and estimated time of use for the project. If necessary, the Contractor shall coordinate soil stabilization practices with the local Soil and Water Conservation District.
- D. All work shall be guaranteed for one full growing season to commence upon final acceptance of lawn work.
- E. Spring-sown work shall be installed between April 1st and May 30th and Fall-sown work shall be installed between September 1st and October 15th. No permanent seeding shall take place between May 30th and September 1st and between October 15th and April 1st. The dates for seeding may be changed at the discretion of the Architect/Engineer.

## PART 2 - PRODUCTS

### 2.1 TOPSOIL

- A. Topsoil shall be furnished by the Contractor. Stockpiled material, if any, shall be utilized prior to obtaining additional topsoil.
- B. New topsoil shall conform to the U.S. Department of Agriculture soil texturing triangle. Screen topsoil from clay lumps, brush, weeds, litter, roots, stumps, stones larger than 1/2 inch in any dimension, and any other extraneous or toxic matter harmful to plant growth.

Obtain topsoil only from naturally well drained sites where topsoil occurs in a depth of not less than 4 inches. Do not obtain from bogs or marshes.

- C. Soil amendments shall be added according to the soils test requirements. Amendments can include, but are not limited to fertilizer, lime, compost and organic matter.

## 2.2 SEED

- A. Seed shall be vendor mixed, delivered in original bags and shall be proportioned as follows:

<u>Common Name</u>	<u>Proportion by Weight</u>
Kentucky Bluegrass	40%
Penn Lawn Fescue	40%
Perennial Rye	20%

1. Supplier's name and analysis of seed is to be submitted to the Engineer.

## 2.3 MULCH

- A. Mulch shall be clean straw free of seed and weed seed.
- B. If hydroseeding is used, wood fiber mulching material may be used and shall consist of virgin wood fibers manufactured expressly from whole wood chips and shall conform to the following specifications.

- Moisture content	10.0% $\pm$ 3.0%
- Organic content	99.2% $\pm$ 0.8% O.D. Basis
- pH	4.8 $\pm$ 0.5
- Water holding capacity, minimum (grams of water per 100 grams of fiber)	1,000

Wood fiber mulching material shall be processed in such a manner as to contain no growth or germination inhibiting factors, and must contain a biodegradable green dye to aid in visual metering during application.

## PART 3 - EXECUTION

### 3.1 PREPARATION - GENERAL

- A. A soils test of the topsoil shall be done by the Contractor at his expense. A copy of the test shall be submitted to the Engineer.
- B. Rough grading must be approved prior to placing topsoil.
- C. Loosen subgrade of lawn areas. Remove any stones greater than 1 inch in any dimension. Remove sticks, roots, rubbish, and other extraneous matter.
- D. Spread topsoil to a minimum depth of 4 inches, to meet lines, grades, and elevations shown on plan, after light rolling and natural settlement. Remove sticks, roots, rubbish, stones greater than 1/2" in any dimension, and other extraneous matter. Topsoil shall be tilled thoroughly by plowing, discing, harrowing, or other approved methods. Add specified soil amendments and mix thoroughly into the topsoil.

- E. Preparation of Unchanged Grades: Where seed is to be planted in areas that have not been altered or disturbed by excavating, grading, or stripping operations, prepare soil for planting as follows: Till to a depth of not less than 6 inches. Apply soil amendments and initial fertilizers as specified. Remove high areas and fill in depressions. Till soil to a homogenous mixture of fine texture, free of lumps, clods, stones, roots and other extraneous matter. Soils test requirements apply here as well.
  - 1. Prior to preparation of unchanged areas, remove existing grass, vegetation and turf. Dispose of such material outside of project limits. Do not turn existing vegetation over into soil being prepared for seed.
  - 2. If necessary, supply and install topsoil in areas where there is no topsoil left after vegetation has been removed in conformance to Section 2.01.
  - 3. Apply specified soil amendments at rates specified in the soils test and thoroughly mix into upper 2 inches of topsoil. Add topsoil if existing grade has less than 4" of topsoil. Delay application of amendments if planting will not follow within a few days.
- F. Fine grade areas to smooth, even surface with loose, uniformly fine texture. Roll, rake, and drag lawn areas, remove ridges and fill depressions, as required to meet finish grades. Remove sticks, roots, rubbish, stones greater than 1/2" in any dimension, and other extraneous matter. Limit fine grading to areas which can be planted immediately after grading.
- G. Moisten prepared areas before planting if soil is dry. Water thoroughly and allow surface moisture to dry before planting lawns. Do not create a muddy soil condition.
- H. Restore areas to specified condition, if eroded or otherwise disturbed, after fine grading and prior to planting.

### 3.2 SEEDING

- A. Do not use wet seed or seed that is moldy or otherwise damaged in transit or storage. Seed shall not be sown when the ground is frozen, muddy, or when weather conditions prevent proper soil preparation, interference with sowing and/or proper incorporation of seed into the soil.
- B. Sow seed using a spreader or hydroseeder. Do not seed when wind velocity exceeds 5 miles per hour. Distribute seed evenly over entire area by sowing 2 1/2 lbs. per 1000 s.f. at right angles to each other. Total amount to equal 5 lbs. per 1000 s.f. unless otherwise altered by the plans or Engineer.
- C. Mulch shall be spread uniformly to form a continuous blanket at a rate of 100 lbs. per 1,000 s.f. Mulch shall be 1 1/2" loose measurement over seeded areas.

Anchor mulch using an O.D.O.T. specified SS-1 at 60 gal./ton non-toxic tackifier such as Hydro-stik, or equal, or by securing with a netting such as Conwed, or equal.

- D. Unless otherwise directed by the Architect/Engineer, the seeded area shall be watered, as soon as the seed is covered, at the rate of 120 gallons per 1000 square feet. The water shall be applied by means of a hydro-seeder or a water tank under pressure with a nozzle that will produce a spray that will not dislodge the mulching material. Cost of this watering shall be included in the cost of seeding and mulching.
- E. Contractor has the option to hydroseed large lawn areas, using equipment specifically designed for such application. The rate of application of wood fiber mulching materials is 40 lbs./1,000 s.f. The Contractor shall submit data regarding the hydroseed mixture, mulch and application rates for the Engineer's review and approval prior to performing the work. Contractor shall not hydroseed within close proximity to buildings and structures when unfavorable wind conditions may blow the hydroseed material onto the structure.

### 3.3 DORMANT SEEDING METHOD

- A. Seeding shall not take place from October 15 through November 20. During this period prepare the seed bed, add the required amounts of lime and fertilizer. Then mulch and anchor.
- B. From November 20th through April 1st, when soil conditions permit, prepare the seed bed, lime and fertilize, apply the selected seed mixture, mulch, and anchor. Increase the seeding rate by 50 percent.

### 3.4 RECONDITIONING EXISTING LAWNS

- A. A soils test shall be required for existing lawns prior to any reconditioning. The soils test shall be done at the Contractors expense. A copy shall be submitted to the Engineer prior to starting.
- B. Recondition all existing lawn areas damaged by Contractors operations including storage of materials and equipment and movement of vehicles. Also recondition existing lawn areas where minor regrading is required.
- C. Provide soil amendments as called for in the soils test.
- D. Provide new topsoil, as required, to fill low spots and meet new finish grades.
- E. Cultivate bare and compacted areas according to the topsoil specifications.
- F. Remove diseased and unsatisfactory lawn areas; do not bury into soil. Remove topsoil containing foreign materials resulting from the Contractor's operations, including oil drippings, stone, gravel, and other loose building materials.
- G. All work shall be the same as for new seeding.
- H. Water newly planted seed areas. Maintenance of reconditioned lawns shall be the same as maintenance of new lawns.

### 3.5 ESTABLISHMENT

- A. Maintain work areas as long as necessary to establish a uniformly close stand of grass over the entire lawn area. A uniformly close stand of grass is defined as the seeded areas having 90%+ coverage of grass at 60 days after seeding. 90%+ coverage is defined as very little or no dirt showing when seeded area is viewed from directly overhead.
- B. Maintain lawns by watering, fertilizing, weeding, mowing, trimming, and other operations such as rolling, regrading and replanting as required to establish a smooth acceptable lawn.
  - 1. Mowing
    - a. Mow lawn areas during the period of maintenance to a height of 2 inches whenever the height of the grass becomes 3 inches. A minimum of 3 mowings is required during the period of maintenance.
  - 2. Refertilizing
    - a. Distribute fertilizer on the seeded area between August 15 and October 15, during the period when grass is dry. The fertilizer shall be as specified in the soils test.
  - 3. Reseeding
    - a. Reseed with the seed specified for the original seeding, and at the rate of 4 lbs. per 1,000 s.f. in a manner which will cause minimum disturbance to the existing stand of grass and at an angle of not less than 15 degrees from the direction of rows of prior seeding.
  - 4. Watering
    - a. The Contractor shall keep all work areas watered daily to achieve satisfactory growth unless otherwise approved by the engineer in writing. Water shall be applied at a rate of 120 gallons(m) per 1000 square feet. If water is listed as a pay item, it shall be separately paid for based on the actual amount of water used, measured in thousands of gallons. If there is no pay item for watering, then the contractor shall include the price of watering in the price per square yard of seeding.
  - 5. Any mulching which has been displaced shall be repaired immediately. Any seed work which has been disturbed or damaged from the displacement of mulch shall be repaired prior to remulching.

### 3.6 INSPECTION AND ACCEPTANCE

- A. When seeding work is complete and an acceptable stand of growth is attained, the Contractor shall request the Engineer to make an inspection to determine final acceptance.

- B. Acceptance shall be based upon achieving a vigorous uniformly stand of the specified grasses. If some areas are satisfactory and some are not, acceptance may be made in blocks, provided they are definable or bounded by readily identified permanent surfaces, structures, or other reference means. Partial acceptance decisions may be made by the Engineer and will be for no less than 75% of the total job. Excessive fragmentation into accepted and unaccepted areas shall be avoided. Unaccepted areas shall be maintained by the Contractor until acceptable.
- C. No payment shall be made until areas are accepted.
- D. All seeded areas shall be guaranteed for one full growing season to commence upon final acceptance of the areas.

END OF SECTION 329200.19



## SECTION 330130 - MISCELLANEOUS TEMPORARY FACILITIES

### PART 1 - GENERAL

#### 1.1 MAINTENANCE OF SANITARY FLOWS

- A. The Contractor for this contract shall be responsible for maintaining all sanitary flows through the existing sanitary sewerage systems. Provisions shall be made for temporary pumping and/or storage of sanitary flows during periods of sewer and manhole reconstruction, or when flows must be interrupted to make connections to the new facilities as directed by the Engineer.

END OF SECTION 330130

## SECTION 330507.23 - HORIZONTAL BORING AND PIPE JACKING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. The work under this section shall include all underground utility crossings where indicated on the contract drawings by boring a casing and placing the carrier pipe within the casing. It is intended that this section apply to all State highways, railroads, and other facilities or structures designated by the Engineer. This section shall also include all necessary excavation, water removal, casing and carrier pipe, and the furnishing of all labor, material, tools, equipment and accessories to complete the work as specified, shown on the contract drawings, or as directed by the Engineer.
- B. The Contractor shall provide all shoring, blocking or other special supports required to maintain uninterrupted traffic flow, together with all watchmen, flagmen and other services necessary to complete the work.

#### 1.3 QUALITY ASSURANCE

- A. Boring shall follow the guidelines of "The Horizontal Earth Boring and Pipe Jacking Manual" published by the National Utility Contractor's Association.

#### 1.4 JOB CONDITIONS

- A. The Contractor shall provide a safe working condition for his personnel and the public with sheeting, if required, for the receiving and boring pits and include barricades around the pits.

#### 1.5 SUBMITTALS

- A. Certificates of compliance shall be submitted for casing pipe.
- B. Plans and description of the boring arrangement to be used shall be submitted to the Engineer for approval and no work shall proceed until such approval is obtained.

## 1.6 ALTERNATIVES

- A. The Contractor is not limited to any one method for boring. The following methods can be used:
  - 1. Auger Boring.
  - 2. Slurry Boring.
  - 3. Hand Tunneling.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. Casing pipe shall conform to ASTM A139, or API 5L, Grade B, and shall be the size and have wall thickness indicated on the drawings.
- B. Carrier pipe shall conform to drawings.
- C. Drilling fluid shall consist of a mixture of water and a gel-forming colloidal material such as bentonite or approved equal.
- D. Materials used for sheeting, sheet piling, cribbing, bracking, shoring and underpinning shall be in good serviceable condition, and timbers shall be sound, free from large or loose knots and of proper dimensions, as required by the Occupational Safety and Health Administration regulations.

### 2.2 EQUIPMENT

- A. All equipment used in the execution of work covered under the utility permit shall have the built-in capacity, stability and necessary safety features required to fully comply with the specifications and requirements without showing evidence of undue stress or failure.
- B. It shall be the responsibility of the Contractor to assure that the equipment to be used in the crossing operation is in sound operating condition. Backup equipment may be required where job site conditions indicate that severe damage to the roadway or a hazardous condition may result in the event of an equipment breakdown and where the condition of the equipment to be used indicated that routine component replacement or repair will likely be necessary during the crossing.
- C. Jacks shall be hydraulic, mechanical or manual power units providing horizontal thrust for pushing casing and carrier pipe. Jacks shall have sufficient power to satisfactorily complete the proposed crossing according to manufacturer's recommendations.
- D. Dewatering equipment shall be used to evacuate ground and surface water from the boring and receiving pit areas.

1. When water is known or expected to be encountered, pumps of sufficient capacity to handle the flow shall be maintained at the site and they shall be in constantly attended operation on a 24-hour basis until their operation can be safely halted. When dewatering, close observation shall be maintained to detect any settlement or displacement of the roadway.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Excavation of the receiving and boring pits shall adequately and safely accommodate the boring equipment, materials and workmen.
- B. The face and sides of each pit shall be properly sloped or sheeted and care shall be taken to ensure the safety of the workmen, the integrity of the surface being bored and the traveling public.
- C. When augers, or similar devices, are used for pipe emplacement, the front of the pipe shall be provided with mechanical arrangements or devices that will positively prevent the auger and cutting head from leading the pipe so that there will be no unsupported excavation ahead of the pipe.
- D. The auger and cutting head arrangement shall be removable from within the pipe in the event an obstruction is encountered.
- E. The over-cut by the cutting head shall not exceed the outside diameter of the pipe by more than one-half (1/2) inch. The face of the cutting head shall be arranged to provide reasonable obstruction to the free flow of soft or poor material.
- F. Preparation of the pit floors, whether of dirt, stone or concrete slab, shall be determined by the job conditions. Dewatering provisions shall be considered and implemented as required.
- G. If an obstruction is encountered during installation to stop the forward action of the pipe, and it becomes evident that it is impossible to advance the pipe, operations will cease and the pipe shall be abandoned in place and filled completely with grout at the Contractor's expense. The new boring location, direction and depth shall be chosen by the Owner.
- H. The casing shall be bored in a straight line and on a uniform and level grade.
- I. After the casing is installed, the carrier pipe shall be pushed through on skids to prevent injury to pipe or joints. Every precaution shall be taken to insure that the joints are and will remain in perfect condition.

- J. Bored or jacked installations shall have a bore hole essentially the same as the outside diameter of the pipe. If voids should develop or if the bored hole diameter is greater than the outside of the pipe by more than approximately one (1) inch, grouting or other methods approved by the Engineer shall be employed to fill such voids. Cost of such grouting shall be at the Contractor's expense.

### 3.2 GROUTING

- A. Where grouting is required in accordance with specifications of the Owner it shall be as follows:
  - 1. A uniform mixture of grout shall be placed under pressure between the casing and carrier pipe. Grouting shall start at the lowest point and proceed upwards simultaneously on both sides of the carrier pipe. A plug shall be installed in each grout hole as the grouting is completed.
  - 2. Grouting shall be kept as close to the heading as possible. Grouting shall proceed as directed by the Engineer.

### 3.3 BLASTING

- A. Blasting will not be permitted.

### 3.4 PERMITS AND INSURANCE

- A. Permits
  - 1. The Owner will obtain all permits necessary for working within the right-of-way. The Contractor shall make, with the proper authority, satisfactory arrangements for the actual work of this Item.
- B. Insurance
  - 1. The Contractor shall be responsible for obtaining any and all insurance required by the proper authorities to perform this work at his own expense. The Contractor shall save harmless the Owner, and any all public agencies affected by this Contract for work performed under this Item from any claims, damages or injury and shall immediately make whatever repairs are necessary to correct any damage to any highway facility and/or right-of-way.

### 3.5 METHOD OF MEASUREMENT

- A. Measurement for a horizontal boring shall be along the centerline of the pipe, measured from the face of the boring pit to the face of the receiving pit. Where the boring terminates at a manhole, the measurement shall be the center of manhole.

### 3.6 BASIS OF PAYMENT

- A. The unit price per lineal foot of horizontal boring stipulated in the proposal shall include earth excavation, disposal of soil, pit construction, ventilating, lighting, pumping, and the furnishing and placing of all casing pipe and/or tunnel lining, sheeting, shoring, bracing, blocking, sealing, grout, concrete, the specified carrier pipe, joint materials, sand or grout fill, the concrete cradle required to support the installed carrier pipe for the total width and length of the pits, and the furnishing of all labor, materials, tools and appliances necessary to complete the work as specified or shown.

END OF SECTION 330507.23

## SECTION 330531.17 – PVC PIPE (ASTM D2241)

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.

#### 1.2 DESCRIPTION OF WORK

- A. The Contractor shall furnish all the materials for and shall properly place at the locations shown on the drawings or as directed, all PVC pipe of the sizes specified, shown or required for the proper completion of the work included under this contract.

#### 1.3 QUALITY ASSURANCE

- A. In addition to requirements of these specifications, comply with manufacturer's instructions and recommendations for work.

#### 1.4 SUBMITTALS

- A. Product Data: Submit manufacturer's technical data and application instructions.

### PART 2 - PRODUCTS

#### 2.1 MATERIALS

- A. All PVC pipe used, as covered under this section, shall conform to ASTM D2241, with end being designated for one of the type joints as specified herein.
- B. The minimum class for PVC pipe under this Item shall be DR 26 (PR 160 psi).

#### 2.2 JOINTS

- A. Pipe joints shall be Push-on Joints. Joints, including their respective appurtenances, shall conform to ASTM D3139.
- B. All fittings shall be Mechanical Joint C153 DIP. All Mechanical Joints shall be restrained with mechanical devices except for tees in the main no closer than 40 feet from the end of a run. Pipe stubs or nipples 30 inches or less (i.e. between Hydrant Tees and Watch Valves or between Watch Valves and Hydrants) shall be Cast Iron or Ductile Iron with restraining anchor glands.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. All trenches, when pipe laying is in progress, shall be kept dry and all pipes and specials shall be laid accurately to the required lines and grades and shall be uniformly supported along their entire lengths. The bottom of the excavation shall be properly trimmed, with holes at each joint to receive the bell and to permit the properly cementing the joints.
- B. Pipe shall be fully entered and shall abut against adjacent pipe and in such a manner that there will be no unevenness along the inverts.
- C. When pipes enter or pass through concrete walls, manholes, sewers or other structures, holes shall be provided and the pipes properly cemented in place so as to form a watertight joint.

END OF SECTION 330531.17



## SECTION 333100 - SANITARY SEWER SYSTEM

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Furnishing all labor, materials, tools, equipment, and services for all sanitary sewers as shown on the Drawings.
- B. Although such is not specifically indicated, furnish and install all supplementary or miscellaneous items, appurtenances, and devices incidental to or necessary for a functional and complete installation.

#### 1.2 RELATED DOCUMENTS AND SECTIONS

- A. Section 013319 – Field Testing Requirements
- B. Section 310000 - Earthwork
- C. Section 015713 - Temporary Erosion Control

#### 1.3 PRODUCTS INSTALLED BUT NOT FURNISHED UNDER THIS SECTION

- A. Granular pipe bedding and cover material specified in Section 310000 - Earthwork
- B. Special backfill material specified in Section 310000 - Earthwork

#### 1.4 SUBMITTALS

- A. Product Data
  - 1. PVC pipe, each type specified
  - 2. Reinforced concrete pipe
  - 3. Vitrified clay pipe
  - 4. Ductile iron pipe
  - 5. Manhole castings
  - 6. Precast concrete manholes
  - 7. Manhole steps
- B. Shop Drawings
  - 1. Precast concrete manholes showing:
    - a. Orientation plan for each manhole or inlet indicating where all pipes connect.
    - b. The size and elevation of connecting pipes.
    - c. Details of drop connections.
    - d. Invert concrete channeling details.
    - e. Pipe to manhole connection details.
    - f. Casting and step orientation.

- C. Quality Control Submittals
  - 1. Design Data
  - 2. Test Reports
  - 3. Certificates
    - a. Evidence of current membership in specified manufacturer's associations.
    - b. Evidence of ODOT precertification for the manufacturing RCP pipe.
    - c. Evidence of National Precast Concrete Association (NPCA) certification for the manufacture of precast concrete manholes.
  - 4. Manufacturers Instructions
  
- D. Contract Closeout Submittals
  - 1. Project Record Documents
  - 2. Operation and Maintenance

## 1.5 REFERENCES

- A. ASTM A-48 Standard Specification for Gray Iron Castings
- B. ASTM C-76 Standard Specification for Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
- C. ASTM C-150 Standard Specification for Portland Cement
- D. ASTM C-270 Standard Specification for Mortar for Unit Masonry
- E. ASTM C-443 Standard Specifications for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets
- F. ASTM C-478 Standard Specifications for Precast Reinforced Concrete Manhole Sections
- G. ASTM C-990 Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants
- H. ASTM C-1173 Standard Specification for Flexible Transition Couplings for Underground Piping Systems
- I. ASTM D-2321 Standard Practice for Underground Installation of Flexible Thermoplastic Sewer Pipe
- J. ASTM D-3034 Standard Specification for Type PSM Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings
- K. ASTM D-3212 Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals

- L. ASTM F-477 Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe
- M. ASTM F-679 Standard Specification for Poly(Vinyl Chloride) (PVC) Large Diameter Plastic Gravity Sewer Pipe and Fittings
- N. ANSI/AWWA C111/A21.11 American National Standard for Rubber-Gasket Joints for Ductile-Iron and Gray-Iron Pressure Pipe and Fittings
- O. ANSI/AWWA C151/A21.51 American National Standard for Ductile-Iron Pipe, Centrifugally Cast in Metal Molds or Sand-Lined Molds, for Water and Other Liquids
- P. AWWA C900 Polyvinyl Chloride (PVC) Pressure Pipe, 4 in. Through 12 in., for Water Distribution

## 1.7 QUALITY ASSURANCE

- A. Qualifications
- B. Regulatory Requirements
- C. Certifications
- D. Field Samples
- E. Pre-Installation Conference

## 1.8 PROJECT CONDITIONS

- A. Environmental Requirements
- B. Existing Conditions
  1. Verify locations of underground utilities.
  2. Protect existing structures and utilities from damage. Repair if damaged by this work.
  3. Do not change pipe sizes without securing written approval of Engineer.
- C. Field Measurements
  1. If it becomes necessary to change location of sanitary sewer lines due to underground utility interference, secure approval of Engineer.
  2. If Contractor initiated, make changes approved by the Engineer without added cost to Owner.

## 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Packing and Shipping
- B. Acceptance at Site
  - 1. All material and all equipment shall be subject to visual inspection and acceptance or rejection after delivery to the site of the work. All rejected material shall immediately be removed from the site.

## 1.10 SEQUENCING AND SCHEDULING

- A. Perform no pipe work in fill areas until embankment or fill has been completed to at least two (2) feet above proposed top of pipe and fill has been properly compacted.

## PART 2 - PRODUCTS

### 2.1 PIPE

- A. Polyvinyl Chloride Pipe (PVC) 4" - 15" Diameter
  - 1. All polyvinyl chloride pipe in this size range shall conform to ASTM D-3034 SDR 26, shall be integral bell and spigot type, with joints conforming to ASTM D-3212 and elastomeric seals conforming to ASTM F-477.
  - 2. All pipe and fittings shall be marked or stenciled in conformance with ASTM D-3034. All gaskets shall be marked or stenciled with the ASTM specification designation, name or trademark of the manufacturer, and pipe size.
  - 3. Acceptable manufacturers shall be current members of the Uni-Bell Plastic Pipe Association.

### 2.2 PRECAST CONCRETE MANHOLES

- A. All precast manhole units shall be manufactured in accordance with the provisions of ASTM C-478.
- B. Joints between manhole units shall be gasketed and shall comply with the requirements of ASTM C-443. All gaskets shall be marked or stenciled with the ASTM specification designation, name or trademark of the manufacturer, and pipe size.
- C. The standard length of riser units shall be 48 inches. Lengths of 32 inches or 16 inches shall be used to meet required dimensions.
- D. Openings for connecting pipes in riser units, bottom riser units, integral base units, and for access in flat slabs shall be preformed or cored by the manufacturer. Cut-out openings shall be made immediately after the pipe is removed from the casting form.

- E. Connectors between new precast concrete manholes and pipes shall be made by casting the connector integrally with the manhole wall. The connectors shall be composed of EPDM with stainless steel take down bands for compressing the connector against the outside diameter of the pipe. The connectors shall comply with the requirements of ASTM C-923, and shall be "Z-Lok" Type as manufactured by A-Lok Products; or an approved equivalent.
- F. All openings in existing manholes shall be field cored and shall have mechanical connectors complying with the requirements of ASTM C-923 and shall be equal to Kor-N-Seal as manufactured by NPC, Inc., Milford, NH.
- G. Annular spaces at pipe entrances shall be field sealed with a one component, hydraulic cement based, fast setting repair mortar equal to Thoro Products Waterplug as manufactured by ChemRex Inc., Shakopee, MN.
- H. The top four (4) inches to twelve (12) inches of the manhole shall provide for adjustment of casting to grade. Adjustment shall be through the use of a maximum of two (2) precast concrete adjusting collars.
- I. Where pressure tight manhole frames and covers are specified, threaded inserts shall be cast in eccentric cones or flat slab tops, and holes formed or cored in adjusting rings to match bolt size and spacing specified for manhole casting.

### 2.3 MANHOLE STEPS

- A. All steps shall be minimum of twelve (12) inches in width with safety side lugs to prevent slipping and shall conform to the latest OSHA requirements. Manhole steps shall be of polypropylene plastic reinforced with a 3/8", No. 60 grade epoxy coated reinforcing rod.
- B. Manhole steps shall conform to the requirements of ASTM C-478.
- C. Acceptable manufacturers are:
  - 1. American Step Company, Inc.
  - 2. Lane International, Inc.
  - 3. M. A. Industries, Inc.

### 2.4 CASTINGS

- A. All castings shall be true to pattern and free from cracks, gas holes, flaws and excessive shrinkage. Surfaces shall be free from burnt-on sand and shall be reasonably smooth. Runners, fins, risers and other cast-on pieces shall be removed. Castings for manhole frames and covers and for any other purpose under these specifications shall conform to all the requirements for Class No. 35B for Gray Iron Castings of the ASTM A-48. All castings shall be commercially machineable and, in the case of manholes, the frame and cover shall be so machined that it will be impossible to rock the cover after it has been seated in the proper position in the frame.

1. Manhole frames and covers shall be as detailed on the Drawings.

## 2.5 MASONRY MORTAR

- A. Mortar shall conform to ASTM C-270, Type M, but shall not contain masonry cement.
- B. Mortar shall be UltraMortar Type M as manufactured by UltraKote Products, Inc. or Lafarge Mortar Cement, Type M as manufactured by Lafarge Corporation, or approved equal.
- C. Only sufficient mortar shall be prepared for immediate use, and any mortar that has set shall not be retempered or used in the work.
- D. Setting accelerators or anti-freeze compounds shall not be used.

## 2.6 MANHOLE ENCAPSULATION MATERIALS

- A. Manhole encapsulation material shall be irradiated and cross-linked polyethylene impermeable backing, coated with protective heat-activated adhesive. Material width shall be sufficient to extend 4-inches below the cone unit-grade ring joint and 4-inches above the grade ring-frame joint.
- B. The manhole encapsulation material shall be as manufactured by Canusa, Division of Shaw Resources Inc., The Woodlands, TX or equal.
- C. Primer shall be as recommended by the manufacturer.

## 2.7 PREFORMED BUTYL MASTIC SEALANT

- A. Preformed butyl mastic sealant material shall be furnished in 1-inch wide strips conforming to the requirement of ASTM C-990.
- B. The butyl mastic sealant shall be Bidco C-56 as manufactured by Bidco Sealants, Inc., Park Hills, MO or equal.

## 2.8 COUPLINGS

- A. Couplings for connecting dissimilar pipe materials or pipe sizes shall be a rubber type coupling with a sealing "O" ring under each of two sealing clamp bands and a Type 316 stainless steel shear ring. Coupling shall be manufactured with natural and synthetic rubbers conforming to ASTM C 425 and ASTM C 1173.
- B. Coupling shall be Flex-Seal Adjustable Repair Coupling as manufactured by the Mission Rubber Company, Corona, CA, or approved equal.

## PART 3 - INSTALLATION

### 3.1 ALIGNMENT AND GRADE

- A. Horizontal and Vertical Control
  - 1. All horizontal and vertical control required for the complete layout and performance of the Work under this contract shall be done by a registered surveyor at the Contractor's expense, and any observations by the Engineer of the Contractor's methods will not relieve the Contractor of his responsibility.
  - 2. The Contractor shall be solely responsible for the accuracy of all horizontal and vertical control.
- B. Alignment and grade shall be established by means of a laser beam.
- C. The Contractor shall furnish all material and labor to establish line and grade of the generated laser beam from the benchmarks and control points indicated on the Drawings. The laser shall be securely anchored and checked periodically by the Contractor. The laser calibration shall be demonstrated when requested by the Engineer. Strict adherence to the manufacturer's operation procedure shall be observed. Only qualified and trained employees may be assigned to install, adjust, or operate laser equipment, and proof of qualifications of the equipment operator must be available at all times. Areas in which lasers are used must be posted with standard laser warning placards, and the laser beam shall be turned off when not needed. During rain, snow, dust, excessive heat, or fog the operation of laser systems shall be prohibited where practicable because of beam scatter.

### 3.2 PIPE INSTALLATION

- A. All pipe installation shall conform to the trench and bedding details shown on the Drawings.
- B. PVC pipe shall be installed in full compliance with ASTM D-2321. Clay pipe shall be installed in full compliance with ASTM C-12. All concrete pipe shall be installed in conformity with recommended practices published by the American Concrete Pipe Association in the "Concrete Pipe Installation Manual".
- C. Only one type and strength of pipe shall be used between any two consecutive manholes, unless otherwise shown on the Drawings.
- D. After the trench has been excavated and the pipe bedded, the pipe shall be laid to the line and grade as shown on the Drawings. All joints shall be made as hereinafter specified. In no case shall any material except bedding material be placed under the bell of the pipe to secure proper grade.

- E. Prior to being lowered into the trench, each pipe shall be carefully inspected and those which are damaged or not meeting the specified requirements shall be rejected and clearly marked as rejected and removed from the Work. Satisfactory means shall be used to hold the pipe in line until embedment of pipe is complete. Precautions shall be taken to insure that the spigot end of the pipe being laid is pushed the proper depth into the bell of the preceding pipe.
- F. All conduit shall be laid starting at the outlet end and laid with the bell end upstream.
- G. In no case shall more than thirty (30) feet of trench be opened in advance of the pipe laying operations.
- H. Conduit shall not be laid in water, mud, or any otherwise unsuitable trench. No drainage shall run through the newly laid pipe. All sewers shall be temporarily capped with a watertight seal at the open ends at the completion of each day's work and no drainage water shall be permitted to flow through the sewer.
- I. All trenches and excavations shall be backfilled as specified as soon as possible after the pipe is laid and jointed. Where concrete encasement or cradle is used, pipe shall not be backfilled for at least twenty four (24) hours after placing concrete except that pipe may be covered to a depth of not to exceed sixteen (16) inches over the top of the pipe.

### 3.3 JOINTING

- A. Polyvinyl Chloride (PVC) Pipe
  1. Dust, dirt and foreign matter shall be removed from joint surfaces. When jointing pipe using the required compression type joint, a lubricant recommended by the gasket manufacturer shall be used. The gasket shall be lubricated by drawing it through lubricant held in the hand of the worker, thus coating the entire surface of the gasket.
  2. When laying the pipe in concrete bedding, care shall be exercised to prevent the joint materials from coming in contact with the fresh concrete until after the joint has been completed.

### 3.4 PERMISSIBLE DEFLECTION AT JOINTS

- A. No pipe deflections or springing of joints, to effect a change in direction will be allowed, except by permission or direction of the Engineer, or as shown on the Drawings. Any permitted or directed deflection shall be a maximum of 80 percent of the allowable deflection value established by the pipe manufacturer.



### 3.5 MANHOLES

- A. Build each manhole to dimensions shown on Drawings and at such elevation that pipe sections built into wall of manhole will be true extensions of line of pipe.
- B. Set frames for manholes, within areas to be paved, to final grade. In asphalt pavement, surround frames set to grade with a ring of compacted asphalt concrete base material immediately after backfilling operations are complete. Place asphalt concrete mixture up to one (1) inch below top of frame, slope to grade, and compact with hand tamp.
- C. Precast bases shall be placed on a bed of crushed gravel or crushed limestone, meeting AASHTO M 43 gradation, having a minimum thickness of three (3) inches. The bedding shall be compacted and provide uniform support for the entire area of the base.
- D. Provision shall be made for a minimum of four (4) inches and a maximum of twelve (12) inches of precast concrete grade rings between the uppermost precast section and the bottom of the cast iron manhole frame in order to set manhole cover to grade.
- E. No more than two lifting holes or other lifting devices shall be utilized for handling the precast sections. All lifting holes shall be acceptably sealed with a hydraulic cement based, fast setting repair mortar, meeting the requirements of Article 2.2 of this Section, prior to backfilling around the manhole.
- F. Inverts shall be formed to the equivalent of half-pipes in concrete and as follows:
  - 1. Carry concrete out to the manhole wall with a slope of  $\frac{1}{2}$  in./ft. from the top of the half-pipe.
  - 2. The bottoms of all manholes shall be channeled to conduct flow in the planned direction. Channels shall be the true shape of the lower half of the sewer pipe and shall match inverts of connecting pipe at the manhole wall.

### 3.6 DROP MANHOLES

- A. Where shown on the plans, drop manholes shall be built in accordance with the Drawings.

### 3.7 BRANCH CONNECTIONS

- A. In general, provision shall be made in the sewers for service connections by inserting a wye branch in the sewer at the location shown on the Drawings, where required or ordered, for each service connection with a branch size called for by the Drawings but never less than six (6) inch, for sewers ten (10) feet or less in depth. Where indicated on the plans, the Contractor shall construct a riser, as per detail, in such manner, that the top of the riser shall be not less than seven (7) feet below grade or at such elevation as to properly receive the required service connection,

with full regard to elevation of service sewer and slope from building or structure to the sewer which shall not be less than one percent (1%).

- B. The approximate location of service connections are shown on the Drawings based upon available information. The Owner may increase the number of connections or delete some connections as the sewer is being built.
- C. Openings at the outer ends of the connections shall be closed and sealed with approved stoppers when connection is not immediately placed into service.

### 3.8 MAINTAINING SEWAGE FLOW

- A. The Contractor shall be required to maintain the flow in all existing live sewers during construction and the method employed shall be approved by the Engineer.

### 3.9 REPLACING, MOVING AND REPAIRING OF EXISTING UTILITIES

- A. The Contractor shall replace, move, support, or repair and maintain all pipes for water, steam, air or gas, and all wire conduit(s), and all other structures encountered in the work and repair all damage done to any of the said structures and appurtenances through his acts or neglect and shall keep them in repair during the life of the Contract. The Contractor shall in all cases leave them in as good condition as they were previous to the commencement of the work and to the full satisfaction of the Owner.

### 3.10 CONNECTION TO EXISTING SEWER SYSTEM

- A. The Contractor shall make connections to the existing sewer system as shown on the Drawings. The connections shall be made by the Contractor at such hours that will cause the least disturbance to the flow in the existing sewer system. The Contractor, however, shall notify the Engineer at least five working days in advance of the time he desires to make the connections and no such connections shall be made until the permission of the Engineer is obtained.

### 3.11 CLEAN-UP

- A. Before final acceptance for the Work, the Contractor shall clear the sewers of any mortar, dirt or other refuse that may have been left or accumulated in the sewers. All manholes and other structures shall be cleared of all forms, scaffolding, bulkheads, centering, surplus mortar, rubbish or dirt and left in a clean and proper condition.

### 3.12 DEFECTS TO BE MADE GOOD

- A. If, at any time before the completion of the contract, any broken pipes, or any defects, are found in the sanitary sewers or in any of their appurtenances, the Contractor shall cause the same to be removed and replaced by proper material and workmanship, without extra compensation for the labor and material required. All materials shall be carefully examined by the Contractor for defects before placing and any found defective shall not be placed in the line.

END OF SECTION 333100