

## CT Consultants

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	201E11001	CLEARING AND GRUBBING, AS PER PLAN	1	LS
2	202E23000	PAVEMENT REMOVED	49	SY
3	202E30000	WALK REMOVED	2046	SF
4	202E98100	REMOVAL MISC.: CONCRETE BUMPER BLOCK	18	EA
5	202E98100	REMOVAL MISC.: POST	2	EA
6	202E98100	REMOVAL MISC.: RELOCATE PRIVATE SIGN AND LANDSCAPE LIGHTS	1	EA
7	202E98100	REMOVAL MISC.: REMOVE AND SALVAGE EX. PRIVATE SIGN, RETURN TO OWNER	1	EA
8	*204E13000	EXCAVATION OF SUBGRADE	100	CY

## CT Consultants

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
9	*204E30010	GRANULAR MATERIAL, TYPE B	100	CY
10	*304E20000	AGGREGATE BASE (UNDERCUT - SUBGRADE REPAIR)	10	CY
11	530E99050	SPECIAL - RETAINING WALL; MODIFY EX WALL	1	LS
12	607E30000	FENCE, SNOW	500	FT
13	608E12000	5" CONCRETE WALK	12802	SF
14	608E52000	CURB RAMP WITH DETECTABLE WARNINGS	6	EA
15	*609E12001	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN	50	FT

## CT Consultants

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
16	*609E18001	COMBINATION CURB AND GUTTER, TYPE 3, AS PER PLAN	50	FT
17	*609E26001	CURB, TYP6, AS PER PLAN	50	FT
18	690E50350	SPECIAL - MAILBOX REMOVED AND RESET	17	EA
19	690E50500	SPECIAL - CONCRETE PARKING BLOCK	9	EA
20	*611E00100	4" CONDUIT, TYPE B, 707.41 (SCHEDULE 40)	50	LF
21	*611E00900	6" CONDUIT, TYPE B, 707.41 (SCHEDULE 40)	50	LF
22	*611E00901	6" CONDUIT, TYPE C, 706.01, 706.02, 706.08 W/ JOINTS AS PER 706.11 OR 706.12	50	LF
23	*611E01101	6" CONDUIT TYPE B W/ JOINTS PER 706.11 OR 706.12	50	LF

## CT Consultants

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
24	SPECIAL	MANHOLE ADJUSTED TO GRADE, SANITARY SEWER	10	EA
25	*SPECIAL	MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY SEWER MANHOLE	1	EA
26	*SPECIAL	BRICK MASONRY, MANHOLE REPAIR, SANITARY SEWER MANHOLE	1	EA
27	203E10000	EXCAVATION	938	CY
28	203E20000	EMBANKMENT	391	CY
29	254E01000	PAVEMENT PLANING, ASPHALT CONCRETE (1-1/2")	536	SY
30	304E20000	AGGREGATE BASE (6")	31	CY

## CT Consultants

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
31	304E20000	AGGREGATE BASE, AS PER PLAN	1	CY
32	407E20000	NON-TRACKING TACK COAT	43	GAL
33	411E50000	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22 (448) (1-1/2")	31	CY
34	441E50300	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 (448) (1-1/2")	9	CY
35	441E91000	ASPHALT CONCRETE, MISC.: ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	256	SY
36	452E19200	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	784	SY
37	452E19200	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 9" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	85	SY
38	653E10000	TOPSOIL FURNISHED AND PLACED	464	CY

**CT Consultants**

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
39	659E100100	SOIL ANALYSIS TEST	2	EA
40	659E10000	SEEDING AND MULCHING	4,177	SY
41	659E14000	REPAIR SEEDING AND MULCHING	208	SY
42	659E15000	INTER-SEEDING	208	SY
43	659E20000	COMMERCIAL FERTILIZER	0.56	TON
44	659E31000	LIME	0.86	ACRE
45	659E35000	WATER	23	M GAL

\* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DISCRETION

## CT Consultants

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
46	1132	FURNISH AND INSTALL WATER SERVICE CURB BOX	12	EA
47	410E12000	TRAFFIC COMPACTED SURFACE, TYPE A OR B	10	CY
48	614E11000	MAINTAINING TRAFFIC	1	LS
49	614E13000	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	10	CY
50	616E10000	WATER	10	MGAL
51	624E10000	MOBILIZATION	1	LS
52	625E25300	CONDUIT, 1-1/2", 725.04	19	LF
53	625E25900	CONDUIT, JACKED OR DRILLED (4", UNDER PAVEMENT)	43	LF

**CT Consultants**

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
54	625E30700	PULL BOX, 728.08, 18"	2	EACH
55	630E03100*	GROUND MOUNTED SUPPORT, NO. 3 POST	75	LF
56	630E08520*	STREET NAME SIGN SUPPORT, NO. 3 POST	15	LF
57	630R08600	SIGN POST REFLECTOR	17	EACH
58	630E80100	SIGN, FLAT SHEET	55	SF
59	630E83000	COVERING OF SIGN	55	SF
60	630E84900	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	2	EA

\* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DISCRETION



## CT Consultants

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
61	630E85100	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	4	EA
62	630E86002	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	2	EA
63	631E95000	SIGN LIGHTING, MISC.: SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB) SYSTEM	1	LS
64	632E70001	POWER SERVICE, AS PER PLAN	1	EA
65	632E70300	CONDUIT RISER, 1-1/2" DIAMETER	1	EA
66	642E00500	STOP LINE, TYPE 1	5	LF
67	644E00600	CROSSWALK LINE, PIANO KEY	210	LF
68	642E00690	TRANSVERSE/DIAGONAL LINE	40	LF

**CT Consultants**

PROJECT: **KEMPER RD SIDEWALK**  
**CITY OF SHARONVILLE**

BID DATE: **09/27/21**  
 PROJECT: **200866**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
69	642E01190	PARKING LOT STALL MARKING	162	LF

\* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DISCRETION