

Proposal Items - Not a Bid Form



STATE ROUTE 747 CURB AND CATCH BASIN REPAIR

CITY OF SPRINGDALE, OH

PROJECT #210124

BID DATE: January 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
1	452	* NON-REINFORCED CONCRETE PAVEMENT, MISC.: 9" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL & REPLACEMENT, AS PER PLAN	763	SY
2	601	TYPE 1-2 PAVED GUTTER, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL	10	LF
3	608	* WALKWAY, MISC.: 5" CONCRETE WALK, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL	925	SF
4	608	7" CURB RAMP, COMPLETE, AS PER PLAN, INCLUDING SAW CUTTING, EXCAVATION, DISPOSAL OF MATERIAL, BACKFILL, BASE COURSE MATERIAL, REINFORCING STEEL, EXPANSION JOINT MATERIAL, GRADING, FORMING, ALL MATERIALS, FINISHING OF CURB & WALK OF RAMP, RESTORATION, INSTALLATION OF TRUNCATED DOMES, DETECTABLE WARNING INSERTS, RAMP CURBING, AND INCIDENTALS NECESSARY TO COMPLETE THE SPECIFIED ITEMS	323	SF
5	608	* WALKWAY, MISC.: 9" CONCRETE WALK AT DRIVE APRONS, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL	1,372	SF
6	609	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN (REMOVE AND REPLACE)	6,089	LF
7	609	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL (NEW INSTALLATION)	200	LF
8	611	INLET RECONSTRUCTED TO GRADE, S.G.I., INCLUDING TIE INS (CB-3A) & TYPE L VANE GRATE AND FRAME (NOTE 2)	12	EACH

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



STATE ROUTE 747 CURB AND CATCH BASIN REPAIR

CITY OF SPRINGDALE, OH

PROJECT #210124

BID DATE: January 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
9	611	INLET RECONSTRUCTED TO GRADE, REPLACE S.G.I WITH CB-3A TOP, INCLUDING TIE INS & TYPE L VANE GRATE AND FRAME (NOTE 2)	2	EACH
10	611	INLET RECONSTRUCTED TO GRADE, D.G.I., INCLUDING TIE INS (CB-3) & TYPE L VANE GRATE AND FRAME (NOTE 2)	5	EACH
11	611	2x2 CATCH BASIN RECONSTRUCTED TO GRADE, INCLUDING TIE INS (NOTE 1)	1	EACH
12	611	* 2x2 CATCH BASIN FRAME & GRATE	1	EACH
13	611	STORM MANHOLE ADJUSTED TO GRADE	1	EACH
14	611	INLET RECONSTRUCTED TO GRADE, D.G.I., INCLUDING TIE INS (CB-3) & TYPE L VANE GRATE AND FRAME (NOTE 1)	2	EACH
15	611	INLET RECONSTRUCTED TO GRADE, S.G.I., INCLUDING TIE INS (CB-3A) & TYPE L VANE GRATE AND FRAME (NOTE 1)	2	EACH
16	SPL	MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; LABOR AND MATERIAL	1	EA
17	614	MAINTAINING TRAFFIC	1	LS

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER