



To: All Plan Holders of Record

From: CT Consultants, Inc.
For the Owner

Re: **Addendum No. 2**
Leggett Street and Wabash Avenue Improvements
Village of Lincoln Heights, OH

Date: March 25, 2022

This Addendum forms a part of the contract documents and modifies the original bidding documents dated March 2022 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

Bid Opening Date and Time: **THURSDAY, MARCH 31, 2022 @ 2:00 PM**

1. Item No.48 and Spec No. 253 – SUBGRADE REPAIR, MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3” – 304: 250 SY should be changed to Spec No. 253 – PAVEMENT REPAIR, MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3” – 304: 50 CY.
2. On Item No. 50, Spec No. 304 – SUBGRADE REPAIR (UNDERCUT): 250 SY, the unit of measure should be changed to CY.

An updated bid form is provided with this addendum.

END ADDENDUM 2

Attachment



**LEGGETT STREET AND WABASH AVENUE IMPROVEMENTS
VILLAGE OF LINCOLN HEIGHTS, OH
PROJECT #: 210279
3/8/2022 ADDENDUM #2 - 3/25/2022**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
LEGGETT STREET						
1	202	* PIPE REMOVED, 24" AND UNDER	50	FT		
2	202	CURB REMOVED	800	FT		
3	202	WALK REMOVED	2,500	SF		
4	202	REMOVE CONCRETE BLOCKOUT	14	EA		
5	204	* PROOFROLLING	1	HR		
6	204	* SUBGRADE STABILIZATION WITH GEOGRID MATERIAL	75	SY		
7	206	* CEMENT STABILIZED SUBGRADE, 12 INCHES DEEP	75	SY		
8	253	* PAVEMENT REPAIR MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3"-304	50	CY		
9	251	* PARTIAL DEPTH PAVEMENT REPAIR (AS NEEDED)	100	SY		
10	253	FULL DEPTH PAVEMENT REPAIR, AS PER PLAN	1,920	SY		

* Denotes Contingency Item



**LEGGETT STREET AND WABASH AVENUE IMPROVEMENTS
VILLAGE OF LINCOLN HEIGHTS, OH
PROJECT #: 210279
3/8/2022 ADDENDUM #2 - 3/25/2022**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
11	254	PAVEMENT PLANING, ASPHALT CONCRETE, (3")	6,862	SY		
12	407	NON-TRACKING TACK COAT AT 0.10 GAL/SY	687	GAL		
13	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1-1/2")	300	CY		
14	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22 (1-1/2")	300	CY		
15	441	MULTI-SEAL SURFACING, FIBERMAT	6,862	SY		
16	441	ASPHALT CONCRETE, MISC.: ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	68	SY		
17	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	97	SY		
18	608	*5" CONCRETE WALK	2,575	SF		
19	608	CURB RAMP WITH DETECTABLE WARNINGS	18	EA		
20	609	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN	770	FT		
21	611	* 12" CONDUIT, TYPE B	50	FT		



**LEGGETT STREET AND WABASH AVENUE IMPROVEMENTS
VILLAGE OF LINCOLN HEIGHTS, OH
PROJECT #: 210279
3/8/2022 ADDENDUM #2 - 3/25/2022**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
22	611	* 3" CONDUIT, TYPE B, 707.41 (SCHEDULE 40)	50	LF		
23	611	* 4" CONDUIT, TYPE B, 707.41 (SCHEDULE 40)	50	LF		
24	611	REPLACE EX TOP, FRAME, AND SGI GRATE WITH VANE GRATE, TYPE L	1	EA		
25	611	REPLACE EX TOP, FRAME, AND DGI GRATE WITH VANE GRATE, TYPE L (ADDENDUM #1)	14	EA		
26	611	* DGI (ACC NO 49013), RECONSTRUCTED TO GRADE, REBUILD TOP 18" USING PRECAST TOP	1	EA		
27	611	* MANHOLE, ADJUSTED TO GRADE (STORM)	5	EA		
28	611	* MANHOLE RECONSTRUCTED TO GRADE (STORM)	1	EA		
29	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	4	EA		
30	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA		
31	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA		



LEGGETT STREET AND WABASH AVENUE IMPROVEMENTS
VILLAGE OF LINCOLN HEIGHTS, OH
PROJECT #: 210279
3/8/2022 ADDENDUM #2 - 3/25/2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
32	614	MAINTENANCE OF TRAFFIC, AS PER PLAN	1	LS		
33	623	CONSTRUCTION LAYOUT STAKES	1	LS		
34	630	GROUND MOUNTED SUPPORT, NO. 3 POST	39	LF		
35	630	SIGN, FLAT SHEET	19	SF		
36	644	STOP LINE, 24"	280	FT		
37	644	CROSSWALK LINE, 12"	470	FT		
38	644	CENTER LINE 4"	600	FT		
39	644	SCHOOL SYMBOL MARKING, 72"	1	EA		
SUBTOTAL - LEGGETT STREET						



your trusted advisor
CONSULTANTS engineers
architects
planners

**LEGGETT STREET AND WABASH AVENUE IMPROVEMENTS
VILLAGE OF LINCOLN HEIGHTS, OH
PROJECT #: 210279
3/8/2022 ADDENDUM #2 - 3/25/2022**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
WABASH AVENUE						
40	202	CURB REMOVED (BASE BID)	1,700	LF		
41	202	* WALK REMOVED	10,715	SF		
42	202	REMOVE CONCRETE BLOCKOUT	13	EA		
43	204	* PROOFROLLING	1	HR		
44	204	* SUBGRADE STABILIZATION WITH GEOGRID MATERIAL	75	SY		
45	206	* CEMENT STABILIZED SUBGRADE, 12 INCHES DEEP	75	SY		
46	251	* PARTIAL DEPTH PAVEMENT REPAIR (AS NEEDED)	250	SY		
47	253	FULL DEPTH PAVEMENT REPAIR, AS PER PLAN	357	SY		
48	253	* PAVEMENT REPAIR MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3"-304 (ADDENDUM #2)	50	CY		
49	254	PAVEMENT PLANING, ASPHALT CONCRETE (3")	3,699	SY		



your trusted advisor
CONSULTANTS
engineers
architects
planners

**LEGGETT STREET AND WABASH AVENUE IMPROVEMENTS
VILLAGE OF LINCOLN HEIGHTS, OH
PROJECT #: 210279
3/8/2022 ADDENDUM #2 - 3/25/2022**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
50	304	* SUBGRADE REPAIR (UNDERCUT) - (ADDENDUM #2)	250	CY		
51	407	NON-TRACKING TACK COAT AT 0.10 GAL/SY	370	GAL		
52	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1-1/2")	160	CY		
53	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22 (1-1/2")	160	CY		
54	441	MULTI-SEAL SURFACING, FIBERMAT	3,699	SY		
55	441	ASPHALT CONCRETE, MISC.: ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	20	SY		
56	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	957	SY		
57	608	* 5" CONCRETE WALK	10,790	SF		
58	608	CURB RAMP WITH DETECTABLE WARNINGS	2	EA		
59	609	COMBINATION CURB AND GUTTER, TYPE 3, AS PER PLAN (SPOT REMOVE AND REPLACE - BASE BID)	1,675	FT		
60	609	CURB, TYPE 6	39	FT		



your trusted advisor
CONSULTANTS
engineers
architects
planners

**LEGGETT STREET AND WABASH AVENUE IMPROVEMENTS
VILLAGE OF LINCOLN HEIGHTS, OH
PROJECT #: 210279
3/8/2022 ADDENDUM #2 - 3/25/2022**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
61	611	CATCH BASIN, NO. 6, AS PER PLAN	1	EA		
62	611	* 3" CONDUIT, TYPE B, 707.41 (SCHEDULE 40)	50	LF		
63	611	* 4" CONDUIT, TYPE B, 707.41 (SCHEDULE 40)	50	LF		
64	611	REPLACE EX GRATE WITH SGI FRAME AND "L" TYPE VANE GRATE	2	EA		
65	611	REPLACE EX GRATE WITH DGI FRAME AND "L" TYPE VANE GRATE	11	EA		
66	611	DGI (ACC NO 49013), RECONSTRUCTED TO GRADE, REBUILD TOP 18" USING PRECAST TOP	2	EA		
67	611	*MANHOLE, ADJUSTED TO GRADE (STORM)	6	EA		
68	611	* MANHOLE RECONSTRUCTED TO GRADE (STORM)	1	EA		
69	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	6	EA		
70	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA		



LEGGETT STREET AND WABASH AVENUE IMPROVEMENTS
VILLAGE OF LINCOLN HEIGHTS, OH
PROJECT #: 210279
3/8/2022 ADDENDUM #2 - 3/25/2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
71	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA		
72	614	MAINTENANCE OF TRAFFIC, AS PER PLAN	1	LS		
73	623	CONSTRUCTION LAYOUT STAKES	1	LS		
74	644	STOP LINE, 24"	46	FT		
SUBTOTAL - WABASH AVENUE						
BASE BID TOTAL						
		BID ALTERNATE #1 - FULL CURB REMOVAL AND REPLACEMENT ON WABASH AVE				
75	202	CURB REMOVED	1,605	LF		
76	609	COMBINATION CURB AND GUTTER, TYPE 3, AS PER PLAN	1,605	FT		
BID ALTERNATE #1						