

Proposal to the City of Wheeling, WV
For Phase III Wastewater Collection and Treatment System Improvements
Project No. 210395 3P
Contract 3P - Delaware Street Sewer Separation - Base Bid

Ref No.	Description	Est. Quantity	Measure Units
1	201-001 Clearing & Grubbing	1	LUMP
2	204-001 Mobilization	1	LUMP
3	207-001 Unclassified Excavation, As Per Plan	300	CU YD
4	219-001 Controlled Low Strength Material, Type "B"	40	CU YD
5	307-001 Class 1 Aggregate Base Course	270	CU YD
6	401-002 Marshall Asphalt Wearing Course (Major North/South Streets Only)	60	TON
7	408-002 Asphalt Material - Tack Coat Trackless (0.13 Gal.SY)	60	GAL
8	501-001 8" Reinforced Portland Cement Concrete Pavement	1,580	SQ YD
9	601-002 Class B Concrete - Headwall ST1	1	EACH
10	604-050 12" Corrugated Polyethylene Pipe - ASTM D3212 Watertight	460	FOOT
11	604-050 18" Corrugated Polyethylene Pipe - ASTM D3212 Watertight	130	FOOT
12	604-050 24" Corrugated Polyethylene Pipe - ASTM D3212 Watertight	1,110	FOOT
13	605-001 Type A Manhole	9	EACH
14	605-070 Type A Inlet (Shallow Frame) w/ EJ 5344	15	EACH
15	605-070 Type B Inlet w/ EJ 5344	2	EACH
16	609-001 Concrete Sidewalk	470	SQ YD
17	609-002 4" Bed Course Material	60	CU YD
18	609-005 Curb Ramp	12	EACH
19	609-006 Detectable Warning Surface	14	EACH
20	610-001 Plain Concrete Curbing, Type III	730	FOOT
21	610-001 Plain Concrete Curbing, Type IV	170	FOOT
22	636-010 Traffic Control	1	LUMP
23	639-010 Construction Layout Stake	1	LUMP
24	652-010 Seed and Mulching, As Per Plan	1	LUMP
25	675-007 18" Plastic Sewer Pipe - PVC SDR 26	230	FOOT
26	675-007 6-IN Sanitary Sewer Connection with Riser - Short	1	EACH
27	675-007 6-IN Sanitary Sewer Connection with Riser - Long	1	EACH
28	675-014 Manhole Complete, Including Casting	1	EACH
29	675-014 Manhole Complete with Drop, Including Casting	1	EACH
30	Item Special - Install Owner Provided Check Valve On Storm Sewer	1	EACH
31	Item Special - Connect Sanitary Sewer to Existing Structure	2	EACH
32	Item Special - Mortar and Plug Existing Manhole EX. S2	1	LUMP
33	Item Special - Inlet Removed	13	EACH

Proposal to the City of Wheeling, WV
For Phase III Wastewater Collection and Treatment System Improvements
Project No. 210395 3P
Contract 3P - Delaware Street Sewer Separation - Base Bid

Ref No.	Description	Est. Quantity	Measure Units
34	Item Special - Remove and Replace Brick Sidewalk	17	SQ YD
35	Item Special - Sewer Flow Control	1	LUMP
36	Item Special - Utility Potholing - As Directed	3	EACH
37	Item Special - Utility Pole Support	1	LUMP

Proposal to the City of Wheeling, WV
For Phase III Wastewater Collection and Treatment System Improvements
Project No. 210395 3P

Contract 3P - Delaware Street Sewer Separation - Base Bid - Alternate A - Storm Sewer Material Alternate

Ref No.	Description	Quantity	Measure Units	Unit Price	Item Total
1	604-037 12" Reinforced Concrete Pipe, Class III w/ gasket	460	FOOT	\$ _____	\$ _____
2	604-037 18" Reinforced Concrete Pipe, Class III w/ gasket	130	FOOT	\$ _____	\$ _____
3	604-037 24" Reinforced Concrete Pipe, Class III w/ gasket	1,110	FOOT	\$ _____	\$ _____
4	604-050 12" Corrugated Polyethylene Pipe - ASTM D3212 Watertight	-460	EACH	<u>\$ From Base Bid</u>	\$ _____
5	604-050 18" Corrugated Polyethylene Pipe - ASTM D3212 Watertight	-130	EACH	<u>\$ From Base Bid</u>	\$ _____
6	604-050 24" Corrugated Polyethylene Pipe - ASTM D3212 Watertight	-1,110	EACH	<u>\$ From Base Bid</u>	\$ _____

**Proposal to the City of Wheeling, WV
For Phase III Wastewater Collection and Treatment System Improvements
Project No. 210395 3P**

Contract 3P - Delaware Street Sewer Separation - Base Bid - Alternate B - Sanitary Sewer Material Alternate

Ref No.	Description	Quantity	Measure Units	Unit Price
1	675-008 18" Ductile Iron Sewer Pipe, Class 52	240	FOOT	\$ _____
2	675-007 18" Plastic Sewer Pipe - PVC SDR 26	-240	FOOT	<u>\$ From Base Bid</u>