



To: All Plan Holders of Record

From: CT Consultants, Inc.
For the Owner

Re: *Addendum No. 2*
Geneva Memorial Field Improvements
City of Geneva

Date: March 14, 2022

This Addendum forms a part of the contract documents and modifies the original bidding documents dated March 2022 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

BID FORMS

Replace Bid Form, Pages BF.8 and BF.12 with the enclosed Bid Form, Pages BF.8A and BF.12A.

LH/RW:mep

Enclosures

H:\2021\210427\SPEC\Addenda\Addendum 02\Addendum 02.Doc

**Proposal to City of Geneva
For Geneva Memorial Field Improvements
Part A - Handicap Parking
Project No. 210427**

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
1	(202) PAVEMENT REMOVED, AS PER PLAN (DRIVEWAYS)	793.00	SY	\$	\$	\$	\$
2	(202) WALK REMOVED, AS PER PLAN	223.00	SF	\$	\$	\$	\$
3	(203) EXCAVATION, AS PER PLAN	155.00	CY	\$	\$	\$	\$
4	(204) SUBGRADE COMPACTION, AS PER PLAN	562.00	SY	\$	\$	\$	\$
5	(204) EXCAVATION OF SUBGRADE AND EMBANKMENT WITH GRANULAR MATERIAL, AS PER PLAN, CONTINGENCY, AS DIRECTED	32.00	CY	\$	\$	\$	\$
6	(304) AGGREGATE BASE, AS PER PLAN	125.00	CY	\$	\$	\$	\$
7	(407) NON-TRACKING TACK COAT, AS PER PLAN	67.00	GAL	\$	\$	\$	\$
8	(448) ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22, AS PER PLAN	39.00	CY	\$	\$	\$	\$
9	(448) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, AS PER PLAN	23.00	CY	\$	\$	\$	\$
10	(608) 4 INCH CONCRETE WALK, AS PER PLAN	1,542.00	SF	\$	\$	\$	\$
11	(630) SIGN, FLAT SHEET, WITH MOUNTING POST	4.00	EACH	\$	\$	\$	\$
12	(642) TRAFFIC PAINT, AS PER PLAN	1.00	LS	\$	\$	\$	\$
13	(690) SPECIAL - CONCRETE PARKING BLOCK	7.00	EACH	\$	\$	\$	\$
INFORMAL TOTAL BID						\$	\$

**Proposal to City of Geneva
For Geneva Memorial Field Improvements
Part C - Walking / Running Track
Project No. 210427**

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
1	(203) EXCAVATION INCLUDING EMBANKMENT CONSTRUCTION, AS PER PLAN	222.00	CY	\$	\$	\$	\$
2	(203) ROADWAY, MISC.: EXCAVATION OF EXISTING STONE RUNNING TRACK	147.00	CY	\$	\$	\$	\$
3	(204) SUBGRADE COMPACTION, AS PER PLAN	2,602.00	SY	\$	\$	\$	\$
4	(204) EXCAVATION OF SUBGRADE AND EMBANKMENT WITH GRANULAR MATERIAL, AS PER PLAN, CONTINGENCY, AS DIRECTED	50.00	CY	\$	\$	\$	\$
5	(407) NON-TRACKING TACK COAT, AS PER PLAN	312.00	GAL	\$	\$	\$	\$
6	(448) ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22, AS PER PLAN	126.00	CY	\$	\$	\$	\$
7	(448) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, AS PER PLAN	91.00	CY	\$	\$	\$	\$
8	(603) INLET BASIN/CATCH BASIN CLEANING, AS PER PLAN	6.00	EACH	\$	\$	\$	\$
9	(605) 18" PREFABRICATED EDGE UNDERDRAIN	640.00	FT	\$	\$	\$	\$
INFORMAL TOTAL BID						\$	\$