

Proposal Items - NOT A BID FORM

CT Consultants, Inc.				
Project:		2021 STREET PROGRAM ALEXANDRIA, KENTUCKY	Date:	05/13/2021
			Project No.:	210437
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
		CONSTABLE DRIVE, PETE NEISER DRIVE, WILLOW STREET, WASHINGTON STREET, RIDGWOOD DRIVE, GRANDVIEW ROAD, RIDGWAY CROSSING, CANTERBURY COURT, HARVARD COURT, POPLAR RIDGE ROAD		
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	402/403	VARIABLE THICKNESS ASPHALT PAVEMENT LEVELING (3/4" AT CURB TO 1-1/4" AT CENTER)	6,575	SY
4	402/403	1" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	6,575	SY
5	402/403	1-1/2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	8,725	SY
6	402/403	2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	4,325	SY
7	408	VARIABLE THICKNESS MILLING (1-1/2" @ CURB/EDGE OF PAVEMENT)	8,050	SY
8	408	VARIABLE THICKNESS PROFILE MILLING (2" MAXIMUM) (POPLAR RIDGE)	260	SY
9	408	CONCRETE MILLING (BUTT JOINTS)	150	SY
10	408	ASPHALT MILLING (BUTT JOINTS)	150	SY
11	SPL	FULL DEPTH PAVEMENT REPAIR (WASHINGTON STREET)	190	SY
12	SPL*	FULL DEPTH PAVEMENT REPAIR (CONTINGENCY)	500	SY

* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DIRECTION

CT Consultants, Inc.

Project:

**2021 STREET PROGRAM
ALEXANDRIA, KENTUCKY**

Date: 05/13/2021
Project No.: 210437

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	302/SPL*	GRAVEL BASE, 6" DENSE GRADED AGGREGATE FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	100	CY
14	713/714	PAVEMENT MARKING - CENTERLINE - 4" DOUBLE YELLOW	4,055	LF
15	713/714	PAVEMENT MARKING - EDGELINE - 6" WHITE	845	LF
16	713/714	PAVEMENT MARKING - CROSSWALK - 6" WHITE	90	LF
17	713/714	PAVEMENT MARKING - CHANNELIZING - 8" WHITE	300	LF
18	713/714	PAVEMENT MARKING - STOP BAR - 24" WHITE	120	LF
19	713/714	PAVEMNET MARKING - LEFT TURN ARROW - WHITE THERMO	4	EA
20	713/714	PAVEMNET MARKING - RIGHT TURN ARROW - WHITE THERMO	3	EA
21	713/714	PAVEMNET MARKING - THROUGH/LEFT TURN ARROW - WHITE THERMO	1	EA
22	713/714	PAVEMNET MARKING - THROUGH/RIGHT TURN ARROW - WHITE THERMO	2	EA
23	SPL	SPEED TABLE	2	EA
24	SPL	REMOVE AND REPLACE EXISTING TRAFFIC LOOP	2	EA
TOTAL BID				

* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DIRECTION