

Proposal Items - Not a Bid Form



HERBERT-FLORENCE-ALTA VISTA-MAYFAIR IMPROVEMENTS
CITY OF CHEVIOT, OHIO
PROJECT #: 210561
BID DATE: Jan. 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
ALTA VISTA AVENUE				
1	201	TREE REMOVAL	1	EA
2	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	77	SY
3	253	* PAVEMENT REPAIR, MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKES WITH 3" - 304	30	CY
4	253	* PAVEMENT REPAIR, AS PER PLAN	696	SY
5	254	PAVEMENT PLANING, ASPHALT CONCRETE (3.0")	3,869	SY
6	304	* SUBGRADE REPAIR - AGGREGATE BASE	30	CY
7	407	TACK COAT	42	GAL
8	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1-1/2")	161	CY
9	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 FIBER REINFORCED (1-1/2")	161	CY
10	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	535	SY
11	606	GUARDRAIL, MISC.: REMOVE & REPLACE GUARDRAIL ASSEMBLY AND DELINEATOR	1	EA
12	608	CONCRETE WALK, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL	495	SF
13	608	CURB RAMP WITH DETECTABLE WARNINGS	4	EA
14	609	CURB AND GUTTER, TYPE 2, MODIFIED, REMOVAL OF EXISTING CURB AND REPLACEMENT	1,520	LF

* Denotes Contingency Item



HERBERT-FLORENCE-ALTA VISTA-MAYFAIR IMPROVEMENTS
CITY OF CHEVIOT, OHIO
PROJECT #: 210561
BID DATE: Jan. 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
15	609	CURB, MISC.: CONCRETE CURB, TYPE 2, INCLUDING PLAIN PORTLAND CEMENT CONCRETE FILL (CLASS QC1) AND REMOVAL OF EXISTING, AS PER DETAIL	1,521	LF
16	609	CURB AND GUTTER, TYPE 3, MODIFIED, REMOVAL OF EXISTING CURB AND REPLACEMENT	384	LF
17	609	CURB, TYPE 6, MODIFIED, REMOVAL OF EXISTING CURB AND REPLACEMENT	50	LF
18	611	REMOVE AND REPLACE EX. CATCH BASIN WITH CB-3 AND "L" TYPE VANE GRATE	2	EA
19	611	REMOVE AND REPLACE EX. CATCH BASIN WITH CB-3A AND "L" TYPE VANE GRATE	4	EA
20	611	*MANHOLE ADJUSTED TO GRADE	1	EA
21	638	*VALVE BOX ADJUSTED TO GRADE	2	EA
22	644	STOP LINE, 24"	22	LF
23	644	CROSSWALK LINE, 12"	188	LF
24	644	CENTER LINE 4"	1,521	FT
25	614	MAINTENANCE OF TRAFFIC	1	LS
26	623	CONSTRUCTION LAYOUT STAKES	1	LS
27	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	3	EA
28	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	2	EA
29	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	2	EA

* Denotes Contingency Item



Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
MAYFAIR AVENUE				
30	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	102	SY
31	253	* PAVEMENT REPAIR, MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3" - 304	28	CY
32	253	* PAVEMENT REPAIR, AS PER PLAN	661	SY
33	254	PAVEMENT PLANING, ASPHALT CONCRETE (3.0")	5,081	SY
34	304	* SUBGRADE REPAIR - AGGREGATE BASE	28	CY
35	407	TACK COAT	56	GAL
36	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1-1/2")	211	CY
37	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 FIBER REINFORCED (1-1/2")	211	CY
38	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	56	SY
39	452	*NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	30	SY
40	606	GUARDRAIL, MISC.: REMOVE & REPLACE GUARDRAIL ASSEMBLY AND DELINEATOR	1	EA



HERBERT-FLORENCE-ALTA VISTA-MAYFAIR IMPROVEMENTS
CITY OF CHEVIOT, OHIO
PROJECT #: 210561
BID DATE: Jan. 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
41	608	CONCRETE WALK, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL	653	SF
42	608	CURB RAMP WITH DETECTABLE WARNINGS	4	EA
43	609	CURB, TYPE 6, MODIFIED, REMOVAL OF EXISTING CURB AND REPLACEMENT	65	LF
44	609	TYPE 6 CURB, MODIFIED, REMOVAL OF EXISTING (SEE DETAIL, SPOT REPAIR ONLY)	175	LF
45	611	REMOVE AND REPLACE EX. CATCH BASIN WITH CB-3 AND "L" TYPE VANE GRATE	5	EA
46	611	REPLACE D.G.I. GRATE WITH VANE GRATE, TYPE "L"	1	EA
47	611	*MANHOLE ADJUSTED TO GRADE	1	EA
48	638	*VALVE BOX ADJUSTED TO GRADE	2	EA
49	644	STOP LINE, 24"	88	LF
50	644	CROSSWALK LINE, 12"	356	LF
51	644	CENTER LINE 4"	1,700	FT
52	614	MAINTENANCE OF TRAFFIC	1	LS
53	623	CONSTRUCTION LAYOUT STAKES	1	LS
54	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	2	EA



HERBERT-FLORENCE-ALTA VISTA-MAYFAIR IMPROVEMENTS
CITY OF CHEVIOT, OHIO
PROJECT #: 210561
BID DATE: Jan. 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
55	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	2	EA
56	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	2	EA
FLORENCE AVENUE (& DARWIN RESURFACING)				
57	201	TREE REMOVAL	1	EA
58	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	18	SY
59	253	* PAVEMENT REPAIR, MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKES WITH 3" - 304	9	CY
60	253	* PAVEMENT REPAIR, AS PER PLAN	207	SY
61	254	PAVEMENT PLANING, ASPHALT CONCRETE (3.0")	1,622	SY
62	304	* SUBGRADE REPAIR - AGGREGATE BASE	9	CY
63	407	TACK COAT	18	GAL
64	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1-1/2")	67	CY
65	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 FIBER REINFORCED (1-1/2")	67	CY



HERBERT-FLORENCE-ALTA VISTA-MAYFAIR IMPROVEMENTS
CITY OF CHEVIOT, OHIO
PROJECT #: 210561
BID DATE: Jan. 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
66	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	50	SY
67	608	CONCRETE WALK, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL	270	SF
68	608	CURB RAMP WITH DETECTABLE WARNINGS	2	EA
69	609	TYPE 6 CURB, MODIFIED, REMOVAL OF EXISTING (SEE DETAIL, SPOT REPAIR ONLY)	20	LF
70	609	CURB AND GUTTER, TYPE 2, MODIFIED, REMOVAL OF EXISTING CURB AND REPLACEMENT	375	LF
71	609	CURB, MISC.: CONCRETE CURB, TYPE 2, INCLUDING PLAIN PORTLAND CEMENT CONCRETE FILL (CLASS QC1) AND REMOVAL OF EXISTING, AS PER DETAIL	375	LF
72	611	REMOVE AND REPLACE EX. CATCH BASIN WITH CB-3 AND "L" TYPE VANE GRATE	3	EA
73	611	REPLACE D.G.I. GRATE WITH VANE GRATE, TYPE "L"	1	EA
74	611	*MANHOLE ADJUSTED TO GRADE	1	EA
75	638	*VALVE BOX ADJUSTED TO GRADE	2	EA
76	644	STOP LINE, 24"	150	LF
77	644	CROSSWALK LINE, 12"	12	LF
78	644	CENTER LINE 4"	366	FT
79	614	MAINTENANCE OF TRAFFIC	1	LS
80	623	CONSTRUCTION LAYOUT STAKES	1	LS

* Denotes Contingency Item



HERBERT-FLORENCE-ALTA VISTA-MAYFAIR IMPROVEMENTS
CITY OF CHEVIOT, OHIO
PROJECT #: 210561
BID DATE: Jan. 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
81	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EA
82	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
83	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA
HERBERT AVENUE				
84	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	68	SY
85	253	* PAVEMENT REPAIR, MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3" - 304	26	CY
86	253	* PAVEMENT REPAIR, AS PER PLAN	617	SY
87	254	PAVEMENT PLANING, ASPHALT CONCRETE (3.0")	3,426	SY
88	304	* SUBGRADE REPAIR - AGGREGATE BASE	26	CY
89	407	TACK COAT	38	GAL
90	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1-1/2")	142	CY
91	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 FIBER REINFORCED (1-1/2")	142	CY



HERBERT-FLORENCE-ALTA VISTA-MAYFAIR IMPROVEMENTS
CITY OF CHEVIOT, OHIO
PROJECT #: 210561
BID DATE: Jan. 26, 2022

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
92	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	171	SY
93	608	CONCRETE WALK, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL	390	SF
94	609	CURB AND GUTTER, TYPE 2, MODIFIED, REMOVAL OF EXISTING CURB AND REPLACEMENT	1,756	LF
95	611	SGI FRAME AND "L" TYPE VANE GRATE	2	EA
96	611	MANHOLE ADJUSTED TO GRADE	1	EA
97	638	*VALVE BOX ADJUSTED TO GRADE	2	EA
98	644	CENTER LINE 4"	876	FT
99	614	MAINTENANCE OF TRAFFIC	1	LS
100	623	CONSTRUCTION LAYOUT STAKES	1	LS
101	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EA
102	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
103	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA

* Denotes Contingency Item