

To: All Plan Holders of Record

From: CT Consultants, Inc.  
For the Owner

**Re: Addendum No. 1  
2022 Lateral Repair Program  
City of Willowick**

Date: March 8, 2022

This Addendum forms a part of the contract documents and modifies the original bidding documents dated February 2022 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

### **BID DOCUMENTS**

**Replace Bid Form, Page BF.8, with the enclosed Bid Form, Page BF.8A**

### **QUESTIONS AND ANSWERS**

- Q.1 – Are sanitary and storm laterals to be CIPP lined at properties listed as “CIPP” in Section 011000 1.5.A.
- A.1 – Only sanitary laterals are to be lined at properties listed as “CIPP” in this section. Quantity of CIPP lining has been updated in BF.8A for Ref. No. 5 from 20 to 16. Additionally, Ref. No. 8 and 11 have been removed and No. 9 and 10 have been updated from 4 to 5 in BF.8A
- Q.2 – Will hydrophilic gaskets (also referred to as tee liners) in accordance with ASTM F3240-19 be required at the main?
- A.2 – No. Mainlines at locations of lateral repairs will potentially be CIPP lined in the future. Tee liners will be installed at that point and not during this project.
- Q.3 – Based on current televising quantity (30), how is that to be performed amongst the 21 homes?
- A.3 – Quantity has been updated in BF.8A for Ref. No. 4 from 30 to 21. Contractor shall televise the sanitary laterals at locations designated for repair or CIPP lining. If additional locations are to be added as noted in the first paragraph in Section 011000 1.5.A, the Engineer shall provide direction on where and what to televise before any work is performed.

TM:mep

Enclosures

H:\2021\210569\SPEC\Addenda\Addendum 01.Doc

**Proposal to City of Willowick  
For 2022 Lateral Program**

**Project No. 210569**

<b>REF. NO.</b>	<b>DESCRIPTION</b>	<b>QTY.</b>	<b>MEASURE UNITS</b>	<b>UNIT PRICE LABOR</b>	<b>UNIT PRICE MATERIAL</b>	<b>TOTAL UNIT PRICE</b>	<b>ITEM TOTAL</b>
1	(255) FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS QC MS, T=9", AS PER PLAN	100.00	SY	\$ _____	\$ _____	\$ _____	\$ _____
2	(452) 8 INCH NON-REINFORCED CONCRETE DRIVES AND APRONS, CLASS QC MS, INCLUDING REMOVAL, AS PER PLAN	25.00	SY	\$ _____	\$ _____	\$ _____	\$ _____
3	(603) 8 INCH X 6 INCH WYE OR TEE REPLACEMENT IN MAIN, AS PER PLAN	2.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
4	(SPC) LATERAL INTERNAL TELEVISION INSPECTION, FROM MAINLINE OR CLEAN OUT, AS PER PLAN	21.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
5	(SPC) 6 INCH CURED-IN-PLACE PIPE LINING - LATERAL, AS PER PLAN	16.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
6	(608) 4 INCH CONCRETE WALK, INCLUDING REMOVAL, AS PER PLAN	100.00	SF	\$ _____	\$ _____	\$ _____	\$ _____
7	(609) CURB, TYPE 6, QCMS CONCRETE, INCLUDING REMOVAL, AS PER PLAN	30.00	FT	\$ _____	\$ _____	\$ _____	\$ _____
8	(611) 6 INCH SANITARY AND STORM SEWER LATERAL TEST TEE/CLEAN OUT ASSEMBLY, AS PER PLAN	5.00	PAIR	\$ _____	\$ _____	\$ _____	\$ _____
9	(611) 6 INCH SANITARY AND STORM SEWER LATERAL REPLACEMENT, AS PER PLAN	5.00	PAIR	\$ _____	\$ _____	\$ _____	\$ _____
10	(SPC) CONTINGENCY/DISCRETIONARY ALLOWANCE	1.00	LS	\$ -----	\$ -----	\$ -----	\$ 10,000.00
						<b>INFORMAL TOTAL BID</b>	<b>\$ _____</b>