

ADDENDUM #1

Job #: 210581 **Project Title** Highland Avenue/N. Fort Thomas Avenue Streetscape

Client: City of Fort Thomas

Issue Date: January 6, 2022

Bid Date: January 12, 2022

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN BY VIA EMAIL TO: pbellew@ctconsultants.com.

Name / Title:

Company:

Date:

CLARIFICATION:

Attached is a revised bid tab with the descriptions for items 15 & 18. The thickness of the surface course of asphalt has be changed from 1-1/4" to 1-1/2" to reflect the detail included in the plan set. Please use the attached revised bid tab for bid submission.

CT Consultants, Inc.

Project: **HIGHLAND AVE/N FT THOMAS AVE STREETScape
FORT THOMAS, KENTUCKY**

Date: 12/16/2021
Project No.: 210581

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING	1	LS
4	212/213	EROSION & SEDIMENT CONTROL	1	LS
5	SPL	YARD RESTORATION (TOPSOIL, SEED AND MULCH)	1	LS
6	203	REMOVE EXISTING PAVEMENT (ROAD, PARKING LOT, SIDEWALK, CURB)	1,100	SY
7	203	REMOVE EXISTING LIGHTPOLE FOUNDATION (MINIMUM 1' BELOW GRADE)	4	EA
8	505/SPL	CONCRETE SIDEWALK WITH PAVER BAND	5,850	SF
9	505/SPL	PAVER SIDEWALK WITH CONCRETE BASE	170	SF

CT Consultants, Inc.

Project: **HIGHLAND AVE/N FT THOMAS AVE STREETSCAPE
FORT THOMAS, KENTUCKY**

Date: 12/16/2021
Project No.: 210581

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
10	505/SPL	CONCRETE APRON WITH PAVER BAND	1,060	SF
11	505/SPL	PAVER CROSSWALK WITH CONCRETE BASE & 1' WIDE BORDER	520	SF
12	SPL	INSTALL BRICK PAVERS (PAVER BRICK MATERIAL PROVIDED BY CITY)	1,680	SF
13	SPL	SANDBLASTED LIMESTONE WELCOME MAT WITH 4" CONCRETE BASE	1	EA
14	403	FULL DEPTH ASPHALT - ROADWAY WIDENING (8" BASE, 1-1/2" LEVELING, & 1-1/2" SURFACE)	125	SY
15	403	FULL DEPTH ASPHALT - PARKING LOT REPLACEMENT (6" BASE & 1-1/2" SURFACE)	380	SY
16	204	EXCAVATION FOR SUBGRADE	380	SY
17	207	SUBGARDE COMPACTION	380	SY
18	403	FULL DEPTH ASPHALT - PARKING LOT (SUBGRADE BY OTHERS) (6" BASE & 1-1/2" SURFACE)	2,160	SY

CT Consultants, Inc.

Project: **HIGHLAND AVE/N FT THOMAS AVE STREETScape
FORT THOMAS, KENTUCKY**

Date: 12/16/2021
Project No.: 210581

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
19	SPL	ADA CURB RAMP, Includes Whitacre-Greer Truncated Dome Pavers	7	EA
20	506	VERTICAL CURB (4" TYP)	860	LF
21	506	VERTICAL CURB (6" TYP)	1,235	LF
22	SPL	STREET LIGHT ASSEMBLY (POLES PROVIDED BY CITY) Includes ground rod, grounding wire, single fused connector and two unfused connectors	7	EA
23	SPL	PARKING LOT LIGHT ASSEMBLY (POLES PROVIDED BY CITY) Includes ground rod, grounding wire, single fused connector and two unfused connectors	4	EA
24	SPL	PARKING LOT LIGHTING BOLLARD ASSEMBLY (BOLLARD LIGHTING PROVIDED BY CITY) Includes ground rod, grounding wire, single fused connector and two unfused connectors	15	EA
25	SPL	CONCRETE LIGHT POLE FOUNDATION (42" BOLLARD LIGHTS)	13	EA
26	SPL	CONCRETE LIGHT POLE FOUNDATION (STREET LIGHT, PARKING LOT LIGHT, 96" BOLLARD LIGHT)	10	EA

CT Consultants, Inc.

Project: **HIGHLAND AVE/N FT THOMAS AVE STREETScape
FORT THOMAS, KENTUCKY**

Date: 12/16/2021
Project No.: 210581

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
27	SPL	PLINTH, AS PER PLAN	7	EA
28	SPL	ELECTRICAL CONDUIT - 2", PVC, SCH 40	40	LF
29	SPL	ELECTRICAL CONDUIT - 1-1/2", PVC, SCH 40	105	LF
30	SPL	ELECTRICAL CONDUIT - 1", PVC, SCH 40	887	LF
31	SPL	ELECTRICAL CONDUIT - 3/4", PVC, SCH 40	564	LF
32	SPL	TRENCH	1,596	LF
33	SPL	INSTALL ELECTRICAL PULL BOX, 11" X 18"	19	EA
34	SPL	8 AWG THHN WIRING	6,100	LF
35	203	REMOVE EXISTING SINGLE GRATE CURB INLET	1	EA
36	710	INSTALL STORM TRENCH DRAIN	23	LF

CT Consultants, Inc.

Project: **HIGHLAND AVE/N FT THOMAS AVE STREETScape
FORT THOMAS, KENTUCKY**

Date: 12/16/2021
Project No.: 210581

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
37	710	INSTALL NEW SINGLE GRATE CURB INLET	1	EA
38	710	INSTALL NEW STANRDARD CATCH BASIN	5	EA
39	701	STORM SEWER - 8" DIAMETER	145	LF
40	701	STORM SEWER - 12" DIAMETER	110	LF
41	SPL	ADJUST EXISTING LIMESTONE WELCOME MAT TO PROPOSED GRADE	2	EA
42	SPL	REMOVE, STORE AND REINSTALL EXISTING SPECIAL MAT	3	EA
43	SPL	ADJUST PULL BOX TO GRADE	11	EA
44	SPL	ADJUST CATCH BASIN TO GRADE	1	EA
45	SPL	ADJUST MANHOLE TO GRADE	2	EA
46	SPL	SALVAGE, STORE AND REINSTALL SIGN WITH FOUNDATION	3	EA

CT Consultants, Inc.

Project: **HIGHLAND AVE/N FT THOMAS AVE STREETSCAPE
FORT THOMAS, KENTUCKY**

Date: 12/16/2021
Project No.: 210581

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
47	713	PAVEMENT MARKING - PARKING STALL	1,150	LF
48	717	PAVEMENT MARKING - CROSSWALK	150	LF
49	717	PAVEMENT MARKING - STOP BAR (24")	12	LF
50	717	PAVEMENT MARKING - DASHED LANE LINE	50	LF
		CONSTRUCTION TOTAL		