



To: All Plan Holders of Record

From: CT Consultants, Inc.
For the Owner

Re: Addendum No. 1
SR 84 – Waterline Replacement
City of Mentor

Date: January 31, 2022

This Addendum forms a part of the contract documents and modifies the original bidding documents dated January 2022 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

PLANS

On plan sheet 12/12, TYPE C PAVEMENT REPLACEMENT detail is Bid Item No. 3: (SPC) TYPE “C” PAVEMENT REPLACEMENT (ASPHALT), ROADWAY, AS PER PLAN

On plan sheet 12/12, RESIDENTIAL ASPHALT DRIVE APRON detail is Bid Item No. 4: (SPC) TYPE “C” PAVEMENT REPLACEMENT (ASPHALT), DRIVEWAY, APRON, OR PARKING LOT

On plan sheet 04/12, Section 17 CONTINGENCY ITEMS part 17.02 WATER METER AND METER BOX, AS PER PLAN refers to an unsuitable meter being replaced with a city standard meter. Zenner PPD ¾” in cu. Ft. or a Sensus accuStream ¾” in cu. Ft.

SPECIFICATIONS

Section 2.6 MECHANICAL JOINTS Item F on page 331113.10-4 under PROJECT PHASING **Change** to the following: All bolts and nuts shall be standard T Read Bolts with Zinc anode caps.

GMS:mep

Enclosures

H:\2021\210678\SPEC\Addenda\Addendum 01\Addendum 01.Doc