



ADDENDUM #1

Job #: 210789-04 **Project Title** Highland Hills Parking Lot Improvements

Client: City of Ft. Thomas

Issue Date: April 10, 2024

Bid Date: April 18, 2024

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN VIA EMAIL TO: pbellew@ctconsultants.com.

Name / Title:

Company:

Date:

Please see revised bid tab.

CT Consultants, Inc.

CT Consultants, Inc.						
	Project:	HIGHLAND HILLS PARK PICKLEBALL COURTS FORT THOMAS, KENTUCKY	Bid Date: Project No.:	4/18/2024 210789	ADDENDUM 1	
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
		Parking Lot, Sidewalk And Grading				
1	110	MOBILIZATION	1	LS		
2	202	CLEARING AND GRUBBING	1	LS		
3	203	ASPHALT REMOVAL	540	SY		
4	204	EXCAVATION / EMBANKMENT PER GRADING PLAN	580	CY		
5	204	EXCESS EXCAVATION HAUL-OFF	380	CY		
6	207	SUBGRADE COMPACTION	3,050	SY		
7	212/213	EROSION CONTROL	1	LS		
8	214	TRI-AXIAL GEODGRID PARKING LOT	1,420	SY		
9	214	TRI AXIAL GEOGRID PICKLEBALL COURT	1,370	SY		
10	302*	12" CRUSHED STONE BASE PARKING LOT	935	TON		
11	302*	12" CRUSHED STONE BASE PICKLEBALL COURT	905	TON		
12	406	TACK COAT (0.1 GAL PER SY) PARKING LOT	142	GAL		
13	406	TACK COAT (0.1 GAL PER SY) PICKLEBALL COURT	137	GAL		
14	403*	5" ASPHALT BASE PARKING LOT	440	TON		

* Contingency Quantities Provided in Estimated Quantity

CT Consultants, Inc.

Project:		HIGHLAND HILLS PARK PICKLEBALL COURTS FORT THOMAS, KENTUCKY	Bid Date:	4/18/2024	ADDENDUM 1	
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
15	403*	1 1/2" ASPHALT SURFACE PARKING LOT	135	TON		
16	403*	1 1/2" ASPHALT SURFACE PICKLEBALL COURT	125	TON		
17	403*	2 1/2" ASPHALT BINDER PICKLEBALL COURT	229	TON		
18	505*	5" CONCRETE SIDEWALK	2,000	SF		
19	713	PAVEMENT MARKINGS AND SIGNAGE	1	LS		
20	700	RIP RAP, 6" STONE 12" DEPTH	25	CY		
21	SPL	PARKING BLOCKS PER CITY REQUIERMENTS	12	EA		
22	SPL	YARD RESTORATION (4" TOPSOIL, SEEDING, MULCH AND WATER)	2,040	SY		
					Sub-Total	
		UTILITIES				
23	710	YARD DRAIN	2	EA		
24	710	12" CONDUIT	143	LF		
25	710	ADJUST MH TO GRADE	4	EA		
26	710	CONNECT TO EX.STM MH	1	EA		

* Contingency Quantities Provided in Estimated Quantity

CT Consultants, Inc.

CT Consultants, Inc.						
	Project:	HIGHLAND HILLS PARK PICKLEBALL COURTS FORT THOMAS, KENTUCKY	Bid Date: Project No.:	4/18/2024 210789	ADDENDUM 1	
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
27	716	3/4" CONDUIT, INCLUDES TRENCHING. BACKFILL AND PULL STRING	80	LF		
28	716	18" CONCRETE POLYMER PULL BOX "LIGHTING"	4	EA		
					Sub-Total	
PICKLE BALL COURT AMENITIES						
29	SPL	10 FT. TALL CHAIN LINK FENCE W/ BLACK VINYL COATING	510	LF		
30	SPL	CHAIN LINK GATE W/ BLACK VINYL COATING	4	EA		
31	SPL	4 FT. TALL COURT DIVIDER CHAIN LINK FENCE W/ BLACK VINYL COATING	270	LF		
32	SPL	PICKLEBALL COURT STRIPING, DYNAFLEX TEXTURED LINE PAINT OR APPROVED EQUAL - 6 FULL COURTS	1	LS		
33	SPL	ACRYLIC COLOR COATING FOR COURT SURFACE. DYNAFLEX MATERIALS OR APPROVED EQUAL	1,370	SY		
					Sub-Total	
TOTAL BASE BID						

CT Consultants, Inc.

	Project:	HIGHLAND HILLS PARK PICKLEBALL COURTS FORT THOMAS, KENTUCKY	Bid Date: Project No.:	4/18/2024 210789	ADDENDUM 1	
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
		ALTERNATE ITEMS				
34	SPL	CUSHIONED BASE COATING SYSTEM DYNAFLEX MATERIALS OR APPROVED EQUAL	1,370	SY		
35	SPL	PICKLEBALL SOUND ABATMENT MATERIAL- FENCE SCREEN ACCOUSTING WRAP 850 OR EQUAL	190	SY		
		TOTAL ALTERNATE BID				
		TOTAL BID				

* Contingency Quantities Provided in Estimated Quantity