

ADDENDUM #2

Job #: 210859 **Project Title** Taylor Mill Street Program and Keavy Drive Improvements

Client: City of Taylor Mill

Issue Date: January 11, 2022

Bid Date: January 27, 2022

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN BY VIA EMAIL TO: pbellew@ctconsultants.com.

Name / Title:

Company:

Date:

CLARIFICATION:

Attached is a revised bid form that includes the following changes.

Item No. 11. Estimated quantity decreased from 728 CY to 241 CY.

Please use the attached revised bid form for bid submission.

CT Consultants, Inc.

Project:

**TAYLOR MILL 2022 STREET PROGRAM AND
KEAVY DRIVE IMPROVEMENTS**

Date: 1/11/2021
Project No.: 210859

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
PART A - 2022 STREET PROGRAM						
1	110	MOBILIZATION	1	LS		
2	112	MAINTENANCE OF TRAFFIC	1	LS		
3	202	CLEARING AND GRUBBING, (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS		
4	203	REMOVE EXISTING SIDEWALK (NO SIDEWALK RECONSTRUCTION)	49	SF		
5	203	REMOVE EXISTING CURB INLET	5	EA		
6	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	2,161	SY		
7	204	EXCAVATION FOR GRANULAR BASE	2,161	SY		
8	207	SUBGRADE RESHAPING AND COMPACTING	2,161	SY		
9	212/213	EROSION & WATER POLLUTION CONTROL	1	LS		
10	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	2,161	SY		
11	SPL	4" CRUSHED STONE BASE (LESS THAN 7% FINES)	241	CY		

CT Consultants, Inc.

Project:

**TAYLOR MILL 2022 STREET PROGRAM AND
KEAVY DRIVE IMPROVEMENTS**

Date: 1/11/2021
Project No.: 210859

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
12	302/SPL*	CONCRETE SUBGRADE REPAIR: 6" CRUSHED STONE BASE (CSB) FOR SUGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	37	CY		
13	302/SPL*	ASPHALT SUBGRADE REPAIR: 6" DENSE GRADE AGGREGATE (DGA) BASE FOR SUGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	95	CY		
14	SPL*	CONCRETE SUBGRADE REPAIR: GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	217	SY		
15	SPL	8" PCC PAVEMENT WITH INTEGRAL ROLLED CURB	2,161	SY		
15a	SPL	9" PCC PAVEMENT (HIGH EARLY MIX)	204	SY		
16	SPL	6" CONCRETE DRIVEWAY APRON REPLACEMENT	1,150	SF		
17	SPL*	FULL DEPTH PAVEMENT REPAIR AS PER PLAN	568	SY		
18	408	3" MILLING	4,662	SY		
19	408	1.5" MILLING	6,684	SY		
20	402/403/ SPL	1.5" ASPHALT SURFACE COURSE (CL2 ASPHALT SURFACE 0.38D PG64-22) WITH FIBER REINFORCEMENT	11,346	SY		
21	402/403	1.5" ASPHALT INTERMEDIATE COURSE (CL2 ASPH BIND 0.50D PG64-22)	4,662	SY		

CT Consultants, Inc.

Project:

**TAYLOR MILL 2022 STREET PROGRAM AND
KEAVY DRIVE IMPROVEMENTS**

Date: 1/11/2021
Project No.: 210859

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
22	411	ASPHALT WEDGE CURB	40	LF		
23	506 *	VERTICAL CURB AND GUTTER REPLACEMENT	75	LF		
24	506 *	ROLLED CURB AND GUTTER REPLACEMENT	75	LF		
25	SPL	CONCRETE WALK REPLACEMENT	967	SF		
26	SPL	ADA CURB RAMP	14	EA		
27	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM	1,420	LF		
28	704	4" SOLID P.V.C. FOR UNDERDRAIN OUTLET	135	LF		
29	710	STANDARD DOUBLE GRATE CURB INLET	3	EA		
30	710	DOUBLE GRATE CURB INLET W/ MOUNTABLE GRATE (NOTE 6)	2	EA		
31	710	REPLACE CURB INLET TOP W/ HOOD, FRAME AND VANE GRATE (NOTE 8)	2	EA		
32	713/714	PAVEMENT STRIPING	1	LS		

CT Consultants, Inc.						
Project:		TAYLOR MILL 2022 STREET PROGRAM AND KEAVY DRIVE IMPROVEMENTS			Date:	1/11/2021
					Project No.:	210859
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
PART A - 2022 STREET PROGRAM SUB-TOTAL:						
PART B - KEAVY DRIVE IMPROVEMENTS						
33	110	MOBILIZATION	1	LS		
34	112	MAINTENANCE OF TRAFFIC	1	LS		
35	202	CLEARING AND GRUBBING	1	LS		
36	202	REMOVE TREE / STUMP	3	EA		
36	203	REMOVE STRUCTURE (WOODEN SHED)	1	LS		
37	203	ASPHALT PAVEMENT REMOVAL	376	SY		
38	203	EXCAVATION FOR GRANULAR BASE	376	SY		
39	204/206	EARTHWORK/GRADING	1	LS		
40	207	SUBGRADE RESHAPING AND COMPACTING (RECONSTRUCTION AREA ONLY)	383	SY		

CT Consultants, Inc.

Project:

**TAYLOR MILL 2022 STREET PROGRAM AND
KEAVY DRIVE IMPROVEMENTS**

Date: 1/11/2021
Project No.: 210859

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
41	212/213	EROSION CONTROL & WATER POLLUTION CONTROL	1	LS		
42	SPL*	FULL DEPTH PAVEMENT REPAIR AS PER PLAN	92	SY		
43	302/SPL*	ASPHALT SUBGRADE REPAIR: 6" DENSE GRADE AGGREGATE (DGA) BASE FOR SUGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	16	CY		
44	302	7" CRUSHED STONE BASE	75	CY		
45	402/403	5" ASPHALT BASE	383	SY		
46	402/403	1" ASPHALT LEVELING COURSE	915	SY		
47	402/403/SPL	1.5" ASPHALT SURFACE WITH FIBER REINFORCEMENT	1,298	SY		
48	408	PAVEMENT MILLING, 2-1/2"	915	SY		
49	411	ASPHALT WEDGE CURB	15	LF		
50	703	CRUSHED AGGREGATE SLOPE PROTECTION (1' DEPTH, INCLUDES GEOTEXTILE FABRIC)	197	SY		

CT Consultants, Inc.

Project:

**TAYLOR MILL 2022 STREET PROGRAM AND
KEAVY DRIVE IMPROVEMENTS**

Date: 1/11/2021
Project No.: 210859

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
51	704	PERFORATED PIPE UNDERDRAIN-6 IN	272	LF		
52	704	NON-PERFORATED PIPE UNDERDRAIN-6 IN	44	LF		
53	704	PERFORATED PIPE HEADWALL	1	EA		
54	SPL	TURF REINFORCEMENT MAT, TYPE 1	200	SY		
55	719	GUARD RAIL, STEEL W-BEAM, SINGLE FACE, 6' POSTS TYPICAL (9' POSTS WHERE NEEDED)	113	LF		
56	719	GUARDRAIL END TREATMENT, TYPE 4A	2	EA		
57	SPL *	GRAVEL DRIVEWAY REPLACEMENT	2,582	SF		
58	SPL *	6" CONCRETE DRIVEWAY APRON REPLACEMENT	405	SF		
59	SPL *	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (MIRAFI 600X OR EQUIVALENT)	92	SY		

CT Consultants, Inc.						
Project:		TAYLOR MILL 2022 STREET PROGRAM AND KEAVY DRIVE IMPROVEMENTS			Date:	1/11/2021
					Project No.:	210859
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
PART B - KEAVY DRIVE IMPROVEMENTS SUB-TOTAL:						
PROJECT TOTAL (PART A + PART B):						