

ADDENDUM #3

Job #: **210859** **Project Title** **Taylor Mill Street Program and Keavy Drive Improvements**

Client: **City of Taylor Mill**

Issue Date: **January 25, 2022**

Bid Date: **January 27, 2022**

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #3 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN BY VIA EMAIL TO: pbellew@ctconsultants.com.

Name / Title:

Company:

Date:

CLARIFICATION:

Item 204: The City will not measure earthwork/grading. Payment for earthwork will be made at the contract lump sum price. The lump sum payment shall be full compensation for excavation of existing materials to the new subgrade elevation, subgrade preparation, fill placement, waste, borrow, hauling, and testing required to complete the item. The item shall be full compensation for all materials; for all preparation, hauling, and placing of these materials; and for all labor, equipment, tools, and incidentals necessary to complete the item.

Bidders shall be advised that the City previously contracted with others to partially clear the vegetation, temporarily relocate overhead utilities lines, and install a pier wall along Keavy Drive prior to this Contract. The existing site conditions represented in the Keavy Drive Reconstruction Plans may differ from the current conditions. It is estimated that there may be up to 625 CY of export material.

The Bidder is expected to examine carefully the site of the proposed Work before submitting a proposal. The submission of a bid shall be considered evidence that the Bidder has made such examination and is satisfied as to the conditions to be encountered in performing the Work and as to the requirements of the plans, specifications, general conditions, special provisions, addenda and Contract.