



CITY OF FORT WRIGHT 2022 STREET PROGRAM												
FT. WRIGHT, KENTUCKY												
PROJECT: 210890												
Date 3/10/2022												
BASE PROJECT												
ITEM NO.	SPEC. NO.	ITEM	Unit of Measure	MORRIS - CHEROKEE TO AMSTERDAM 890 X 24	MORRIS - AMSTERDAM TO HOWARD 1375X18	HOWARD - MORRIS TO BARRINGTON 560X18	BARRINGTON - NORTH END TO PARK 170X20, 640X17	BARRINGTON - PARK TO DIXIE HWY 1210X17	GLENGARRY 1550x20	GLASGOW 280x17	TARTAN 260x17	TOTAL
1	110	MOBILIZATION	LS	-	-	-	-	-	-	-	-	1
2	112	MAINTENANCE OF TRAFFIC	LS	-	-	-	-	-	-	-	-	1
3	SPL*	FULL DEPTH PAVEMENT REPAIR AS PER PLAN	SY	250	570	120	165	265	370	60	55	1855
4	SPL*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	CY	41.66666667	95	20	27.5	44.16666667	61.66666667	10	9.166666667	309.1666667
5	408	PAVEMENT MILLING - VARIABLE DEPTH (2.5" EDGE, 0.5" CENTER)	SY						3700	600	550	4850
6	408	2.5" PAVEMENT MILLING AND TEXTURING	SY	2500	2850	1200	1650	2650				10850
7	402/403/ SPL	1.5" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER)	SY	2500	2850	1200	1650	2650	3700	600	550	15700
8	402/403	1" ASPHALT LEVELING	SY	2500	2850	1200	1650	2650	3700	600	550	15700
9	411	ASPHALT CURB	LF			50						50
10	505	4" CONCRETE SIDEWALK REPLACEMENT	SF	0	0	0	0	0	420	0	0	420
11	505	ADA CURB RAMP W/ DETECTABLE WARNINGS	EA						4			4

CITY OF FORT WRIGHT 2022 STREET PROGRAM												
FT. WRIGHT, KENTUCKY												
PROJECT: 210890												
Date 3/10/2022												
BASE PROJECT												
ITEM NO.	SPEC. NO.	ITEM	Unit of Measure	MORRIS - CHEROKEE TO AMSTERDAM 890 X 24	MORRIS - AMSTERDAM TO HOWARD 1375X18	HOWARD - MORRIS TO BARRINGTON 560X18	BARRINGTON - NORTH END TO PARK 170X20, 640X17	BARRINGTON - PARK TO DIXIE HWY 1210X17	GLENGARRY 1550x20	GLASGOW 280x17	TARTAN 260x17	TOTAL
12	506 *	VERTICAL CURB REPLACEMENT	LF					120				120
13	506 *	VERTICAL CURB AND GUTTER REPLACEMENT	LF	90								90
14	506 *	ROLLED CURB AND GUTTER REPLACEMENT	LF		140		65		150	30	30	415
15	506*	ROLLED CURB REPLACEMENT (ON CONCRETE STREET W/ ASPHALT OVERLAY)	LF			60	20					80
16	713	4" EDGE LINE (YELLOW PAINT)	LF	60	225	135	25		115	20		580
17	714	PAVEMENT STRIPING - 24" STOP BAR (WHITE THERMO)	LF	24	10	16	10	30	0	10	10	110

	CITY OF FORT WRIGHT 2022 STREET PROGRAM		
	FT. WRIGHT, KENTUCKY		
	PROJECT: 210890		
	Date 3/10/2022		

BASE PROJECT				
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	SPL*	FULL DEPTH PAVEMENT REPAIR AS PER PLAN	2,000	SY
4	SPL*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	350	CY
5	408	PAVEMENT MILLING - VARIABLE DEPTH (2.5" EDGE, 0.5" CENTER)	5,000	SY
6	408	2.5" PAVEMENT MILLING AND TEXTURING	11,000	SY
7	402/403/ SPL	1.5" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER)	16,000	SY
8	402/403	1" ASPHALT LEVELING	16,000	SY
9	411	ASPHALT CURB	50	LF
10	505	4" CONCRETE SIDEWALK REPLACEMENT	500	SF
11	505	ADA CURB RAMP W/ DETECTABLE WARNINGS	4	EA

		CITY OF FORT WRIGHT 2022 STREET PROGRAM		
		FT. WRIGHT, KENTUCKY		
		PROJECT: 210890		
		Date 3/10/2022		
BASE PROJECT				
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	506 *	VERTICAL CURB REPLACEMENT	120	LF
13	506 *	VERTICAL CURB AND GUTTER REPLACEMENT	90	LF
14	506 *	ROLLED CURB AND GUTTER REPLACEMENT	415	LF
15	506*	ROLLED CURB REPLACEMENT (ON CONCRETE STREET W/ ASPHALT OVERLAY)	80	LF
16	713	4" EDGE LINE (YELLOW PAINT)	600	LF
17	714	PAVEMENT STRIPING - 24" STOP BAR (WHITE THERMO)	110	LF



engineers
architects
planners

Date 3/10/2022

ALERNATE 'A' - PARK ROAD (610 x 20)

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
18	110	MOBILIZATION	1	LS
19	112	MAINTENANCE OF TRAFFIC	1	LS
20	SPL*	FULL DEPTH PAVEMENT REPAIR AS PER PLAN	130	SY
21	SPL*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	20	CY
22	408	2.5" PAVEMENT MILLING AND TEXTURING	1,300	SY
23	402/403/ SPL	1.5" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORA-FI OR ACE FIBER)	1,300	SY
24	402/403	1" ASPHALT LEVELING	1,300	SY
25	411	ASPHALT CURB	125	LF
26	714	PAVEMENT STRIPING - 24" STOP BAR (WHITE THERMO)	15	LF



engineers
architects
planners

ALERNATE 'B' - CHEROKEE DRIVE (460 x 20)

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
27	110	MOBILIZATION	1	LS
28	112	MAINTENANCE OF TRAFFIC	1	LS
29	SPL*	FULL DEPTH PAVEMENT REPAIR AS PER PLAN	110	SY
30	SPL*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	20	CY
31	408	2.5" PAVEMENT MILLING AND TEXTURING	1,100	SY
32	402/403/ SPL	1.5" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER)	1,100	SY
33	402/403	1" ASPHALT LEVELING	1,100	SY
34	506 *	VERTICAL CURB AND GUTTER REPLACEMENT	50	LF
35	713	4" EDGE LINE (YELLOW PAINT)	35	LF
36	714	PAVEMENT STRIPING - 24" STOP BAR (WHITE THERMO)	10	LF