

Proposal Item List - Not a Bid Form

		FALCON RIDGE DRIVE RECONSTRUCTION INDEPENDENCE, KENTUCKY PROJECT: 211014-03		
		Date 3/16/2023		
FALCON RIDGE DRIVE RECONSTRUCTION (1040 X 28)				
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	3375	SY
5	204	REMOVE EXISTING SINGLE CURB INLET	6	EA
6	204	REMOVE EXISTING SLOTTED DRAIN	2	EA
7	204	EXCAVATION FOR GRANULAR BASE	3375	SY
8	207	SUBGRADE RESHAPING AND COMPACTING	3375	SY
9	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	500	SY
10	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
11	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	3200	SY





**FALCON RIDGE DRIVE RECONSTRUCTION
INDEPENDENCE, KENTUCKY
PROJECT: 211014-03**

Date 3/16/2023

FALCON RIDGE DRIVE RECONSTRUCTION (1040 X 28)				
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	302	4" CRUSHED STONE BASE	3375	SY
13	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	115	CY
14	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	335	SY
15	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	2400	SY
16	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB - 3 DAY MIX	950	SY
17	SPL	ASPHALT PAVEMENT JOINT	4	EA
18	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	2000	SF
19	SPL	4" CONCRETE SIDEWALK REPLACEMENT	600	SF
20	SPL	ADA CURB RAMP	4	EA
21	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	1850	LF
22	SPL	12" STORM CONDUIT (INCLUDES 4" UNDERDRAIN STUBOUT AS PER DETAIL)	440	LF



**FALCON RIDGE DRIVE RECONSTRUCTION
INDEPENDENCE, KENTUCKY
PROJECT: 211014-03**

Date 3/16/2023

FALCON RIDGE DRIVE RECONSTRUCTION (1040 X 28)				
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
23	SPL	12" SLOTTED DRAIN	40	LF
24	SPL	DOUBLE GRATE CURB INLET (VANE GRATE)	10	EA
25	SPL	DOUBLE GRATE CURB INLET WITH MOUNTABLE GRATE	1	EA
26	SPL	REMOVE/REPLACE DOUBLE CURB INLET TOP, COMPLETE w/ MOUNTABLE GRATE	1	EA