



**INDEPENDENCE 2023 RESURFACING PROGRAM**

**INDEPENDENCE, KENTUCKY**

**PROJECT: 220564**

**Date 02/02/2023**

**BASE PROJECT**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTAINING TRAFFIC	1	LS
3	203	REMOVE EXISTING PAVEMENT	90	SY
4	205/206	GRADING (LOWER GRASSY AREA @ DELAWARE/MADISON)	1	LS
5	SPL*	YARD RESTORATION (TOP SOIL, SEED, MULCH)	600	SY
6	SPL*	(9") FULL DEPTH PAVEMENT REPAIR AS PER PLAN (10%) - CHRISTOPHER, ROMAN, ARBOR, ARISTOCRAT, NOBLE	900	SY
7	SPL*	(12") FULL DEPTH PAVEMENT REPAIR AS PER PLAN (10%) - DELAWARE, DECLARATION, CENTENNIAL	2,300	SY
8	SPL*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	535	CY
9	SPL*	REMOVE, SALVAGE, AND RELOCATE STOP SIGN	1	LS
10	408	PAVEMENT MILLING - VARIABLE DEPTH (0-2.5")	425	SY
11	408	2.5" PAVEMENT MILLING AND TEXTURING	31,575	SY
12	SPL	VARIABLE DEPTH ASPHALT WEDGING (MADISON & DELAWARE INTERSECTION)	50	TONS



**INDEPENDENCE 2023 RESURFACING PROGRAM**

**INDEPENDENCE, KENTUCKY**

**PROJECT: 220564**

**Date 02/02/2023**

**BASE PROJECT**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	402/403	1" ASPHALT LEVELING	32,000	SY
14	402/403/ SPL	1.5" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORTA-FI, ACE FIBER, OR APPROVED EQUAL)	32,000	SY
15	505	4" CONCRETE SIDEWALK	1,000	SF
16	505	4" CONCRETE SIDEWALK REPLACEMENT	5,500	SF
17	505	ADA CURB RAMP W/ DETECTABLE WARNINGS	30	EA
18	SPL*	VERTICAL CURB AND GUTTER REPLACEMENT (10" GUTTER)	800	LF
19	SPL*	4" ROLLED CURB AND GUTTER (10" GUTTER)	215	LF
20	SPL*	4" ROLLED CURB AND GUTTER REPLACEMENT (10" GUTTER)	700	LF
21	SPL*	4" ROLLED CURB AND GUTTER REPLACEMENT (8" GUTTER)	850	LF
22	713	4" EDGE LINE (WHITE PAINT)	300	LF
23	714	PAVEMENT STRIPING - 24" STOP BAR (WHITE THERMO)	300	LF



**INDEPENDENCE 2023 RESURFACING PROGRAM**

**INDEPENDENCE, KENTUCKY**

**PROJECT: 220564**

**Date 02/02/2023**

**BASE PROJECT**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
24	713	PAVEMENT MARKING - 4" DOUBLE YELLOW CENTERLINE (PAINT) (INCLUDES DUAL LEFT TURN STRIPING)	7,900	LF
25	714	PAVEMENT MARKING - LEFT TURN LANE ARROW (THERMO)	10	EA
26	714	PAVEMENT MARKING - RIGHT TURN LANE ARROW (THERMO)	8	EA
27	714	PAVEMENT MARKING - THRU/LEFT LANE ARROW (THERMO)	2	EA
28	714	PAVEMENT MARKING - OPPOSING LEFT TURN LANE ARROW (THERMO)	20	EA
29	714	PAVEMENT MARKING - THRU/RIGHT LANE ARROW (THERMO)	3	EA
30	714	PAVEMENT MARKING - THRU LANE ARROW (THERMO)	2	EA
31	713	PAVEMENT MARKING - 6" WHITE CROSSWALK LINE (THERMO)	1,650	LF
32	713	PAVEMENT MARKING - 4" WHITE CHANNELIZING LINE (PAINT)	800	LF
33	SPL	REPLACE TRAFFIC SIGNAL DETECTION LOOP - NEW CONDUIT TO BE INSTALLED FROM EDGE OF PAVEMENT TO LOOP SPLICE LOCATIONS (PER KYTC REQUIREMENTS)	2	EA
33B	109*	CONTINGENCY FOR ADJUSTMENT OF THE KY AVERAGE PRICE INDEX FOR ASPHALT (109.07.01 ONLY). ANY ADJUSTMENT REQUIRED WILL BE APPLIED TO THIS NUMBER.	1	LS