

FORT HENRY RECONSTRUCTION FORT WRIGHT, KENTUCKY PROJECT: 220720

2/15/2024

FORT HENRY DRIVE - PHASE 2 GENERAL TO PICKETT, 422 TO AMSTERDAM

SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
110	MOBILIZATION	1	LS
112	MAINTENANCE OF TRAFFIC	1	LS
202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	3450	SY
204	REMOVE EXISTING STORM STRUCTURE	7	EA
204	REMOVE EXISTING STORM SEWER	35	LF
204	EXCAVATION FOR GRANULAR BASE	3400	SY
207	SUBGRADE RESHAPING AND COMPACTING	3400	SY
SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	3000	SY
SPL	EROSION & WATER POLLUTION CONTROL	1	LS
214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	3200	SY
	110 112 202 204 204 204 204 204 204 204 207 207 SPL SPL	110 MOBILIZATION 1112 MAINTENANCE OF TRAFFIC 202 CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES) 204 REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB 204 REMOVE EXISTING STORM STRUCTURE 204 REMOVE EXISTING STORM STRUCTURE 204 REMOVE EXISTING STORM SEWER 204 REMOVE EXISTING STORM SEWER 204 REMOVE EXISTING AND COMPACTING 204 EXCAVATION FOR GRANULAR BASE 204 EXCAVATION FOR GRANULAR BASE 205 SUBGRADE RESHAPING AND COMPACTING 206 EROSION & WATER POLLUTION CONTROL	SPEC. NO.ITEMQuantity110MOBILIZATION11112MAINTENANCE OF TRAFFIC1112MAINTENANCE OF TRAFFIC1202CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)1204REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB3450204REMOVE EXISTING STORM STRUCTURE7204REMOVE EXISTING STORM STRUCTURE7204REMOVE EXISTING STORM SEWER35204REMOVE EXISTING AND COMPACTING3400207SUBGRADE RESHAPING AND COMPACTING3400207SUBGRADE RESHAPING AND COMPACTING3000SPLYARD RESTORATION (4" TOPSOIL, SEED AND MULCH)3000SPLEROSION & WATER POLLUTION CONTROL1



FORT HENRY RECONSTRUCTION FORT WRIGHT, KENTUCKY PROJECT: 220720

2/15/2024

FORT HENRY DRIVE - PHASE 2 GENERAL TO PICKETT, 422 TO AMSTERDAM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	302	4" CRUSHED STONE BASE	3400	SY
13	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	340	CY
14	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	120	SY
15	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	2875	SY
16	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB - 3 DAY MIX	525	SY
17	SPL	JOINT AND CRACK SEALING FOR PORTLAND CEMENT CONCFETE STREETS (ROUT OUT EXISTING JOINT OR CRACK AND FILL WITH SEALANT SUCH THAT THE TOP OF THE SEALANT IS FLUSH WITH THE TOP OF PAVEMENT)	1600	LF
18	SPL	ASPHALT DRIVEWAY REPLACEMENT	35	SY
19	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	3500	SF
20	SPL	4" CONCRETE SIDEWALK REPLACEMENT	4900	SF
21	SPL	ADA CURB RAMP	4	EA
22	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	2500	LF



FORT HENRY RECONSTRUCTION FORT WRIGHT, KENTUCKY PROJECT: 220720

2/15/2024

FORT HENRY DRIVE - PHASE 2 GENERAL TO PICKETT, 422 TO AMSTERDAM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
23	SPL	DOWNSPOUT CONNECTION TO DOWNSPOUT COLLECTION LINE	3	EA
24	704	6" SOLID PVC DOWNSPOUT COLLECTION LINE (IN SAME TRENCH AS UNDERDRAIN)	215	LF
25	704	EDGE DRAIN EXTENSION (4" SOLID PVC UNDERDRAIN OUTLET LINE BEHIND CURB)	455	LF
26	SPL	DOUBLE GRATE CURB INLET (VANE GRATE)	5	EA
27	SPL	DOUBLE GRATE CURB INLET WITH MOUNTABLE GRATE	1	EA
28	SPL	DOUBLE GRATE CURB INLET / MANHOLE COMBO	1	EA
29	SPL	15" STORM SEWER	20	EA
30	SPL	18" STORM SEWER	10	EA
31	SPL	ADJUST SANITARY MANHOLE TO FINISHED GRADE	3	EA
			1	