



PROJECT: TAYLOR MILL 2023 STREET PROGRAM

CITY OF TAYLOR MILL, KY

PROJECT #220835

BID OPENING DATE: 03/02/2023

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART A - RESURFACING</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	408	ASPHALT MILLING (1.5" AVG.)	3,200	SY
4	402/403	1.5" ASPHALT LEVELING	4,300	SY
5	402/403	1.5" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER)	4,300	SY
6	402/403	VARIABLE THICKNESS ASPHALT WEDGING (6" MAX)	20	TON
7	SPL	MOUNTABLE ASPHALT CURB	120	LF
8	SPL*	FULL DEPTH PAVEMENT REPAIR, AS PER PLAN	650	SY
9	SPL*	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	120	SF
10	SPL	ADJUST SANITARY SEWER MANHOLE TO GRADE	4	EA
11	SPL	TOPSOIL, SEED & MULCH TO MATCH PROPOSED SURFACE	1,500	SY



PROJECT: TAYLOR MILL 2023 STREET PROGRAM

CITY OF TAYLOR MILL, KY

PROJECT #220835

BID OPENING DATE: 03/02/2023

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART B - RECONSTRUCTION</b>				
12	110	MOBILIZATION	1	LS
13	112	MAINTENANCE OF TRAFFIC	1	LS
14	202	CLEARING AND GRUBBING (INCLUDES THE REMOVAL AND REINSTALLATION OF SIGNS, MAILBOXES, AND FENCING)	1	LS
15	203	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	675	SY
16	203	REMOVE EXISTING CATCH BASIN	1	EA
17	204	EXCAVATION FOR GRANULAR BASE	675	SY
18	207	SUBGRADE RESHAPING AND COMPACTING	675	SY
19	212/213	EROSION CONTROL AND WATER POLLUTION CONTROL	1	LS
20	SPL	YARD RESTORATION (4" TOPSOIL, SEED & MULCH)	200	SY
21	214	WOVEN GEOTEXTILE FABRIC, MIRAFI 600X OR EQUIVALENT	675	SY
22	SPL*	GEOGRID (TENSAR BX 1200 OR EQUIVALENT) REINFORCEMENT FOR SUBGRADE REPAIR *	75	SY
23	302/SPL*	CRUSHED STONE BASE (LESS THAN 3% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL) *	25	CY
24	302	4" CRUSHED STONE AGGREGATE BASE	675	SY



**PROJECT: TAYLOR MILL 2023 STREET PROGRAM**

**CITY OF TAYLOR MILL, KY**

**PROJECT #220835**

**BID OPENING DATE: 03/02/2023**

<b>ITEM NO.</b>	<b>SPEC. NO.</b>	<b>ITEM</b>	<b>Estimated Quantity</b>	<b>Unit of Measure</b>
25	505	8" CONCRETE PAVEMENT WITH INTEGRAL ROLLED CURB	675	SY
26	505	CONCRETE DRIVE APRON REPLACEMENT (6")	400	SF
27	704	4" RIGID PVC UNDERDRAIN, AS PER PLAN	460	LF
28	710	INSTALL NEW STANDARD DOUBLE GRATE CURB INLET	1	EA