
	FORT WRIGHT CITY BUILDING PARKING LOT REPAIRS	
	FORT WRIGHT, KENTUCKY	
	PROJECT: 23028204	
		Date 2/1/2024

BASE PROJECT				
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	203	REMOVE EXISTING WHEEL STOP	13	EA
4	203	REMOVE EXISTING BOLLARD	16	EA
5	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	100	SY
6	402/403/SPL	1.5" ASPHALT PAVEMENT SURFACE - INCLUDES SEALING EDGES AT CURBS AND WHERE ASPHALT ABUTS CONCRETE PAVEMENT	4,200	SY
7	SPL*	FULL DEPTH PAVEMENT REPAIR (5%)	205	SY
8	408	1.5" PAVEMENT MILLING & TEXTURING	4,200	SY
9	SPL	REMOVE EXISTING CONCRETE RAMP, EXCAVATE TO PROPOSED SUBGRADE, INSTALL 9" ASPHALT PAVEMENT BASE	10	SY
10	SPL	INSTALL TEMPORARY SIDEWALK FOR ACCESS DURING SIDEWALK REPLACEMENT. REMOVE UPON COMPLETION	1	LS
11	SPL	10" REINFORCED CONCRETE PAVEMENT REPLACEMENT (REMOVE EXISTING 8" SLAB, EXCAVATE GRAVEL TO PROPOSED DEPTH, SUBGRADE RESHAPING AND COMPACTING AND GRAVEL LEVELLING AS NEEDED - SEAL ALL JOINTS)	725	SY

FORT WRIGHT CITY BUILDING PARKING LOT REPAIRS				
FORT WRIGHT, KENTUCKY				
PROJECT: 23028204				Date 2/1/2024
BASE PROJECT				
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	SPL	7" UNREINFORCED CONCRETE PAVEMENT REPLACEMENT	180	SY
13	505	4" CONCRETE SIDEWALK WITH INTEGRAL WALK REPLACEMENT	900	SF
14	505	7" CONCRETE SIDEWALK REPLACEMENT	350	SF
15	505	ADA CURB RAMP W/ DETECTABLE WARNINGS	1	EA
16	506 *	CURB AND GUTTER REPLACEMENT	130	LF
17	506*	8" VERTICAL CURB REPLACEMENT	110	LF
18	506 *	6" VERTICAL CURB REPLACEMENT	300	LF
19	SPL	CONCRETE CHANNEL (SAWCUT AND REMOVE EXISTING CURB, EXCAVATE TO PROPOSED SUBGRADE AND CONSTRUCT CHANNEL PER DETAIL	1	LS
20	SPL	REMOVE, SALVAGE, AND REINSTALL CONCRETE WHEEL STOP	6	EA
21	SPL	INSTALL BOLLARD PER DETAIL	16	EA
22	713	PAVEMENT MARKING - ADA PARKING SYMBOL WHITE PAINT	2	EA



your trusted advisor
 consultants → engineers
 architects
 planners

		FORT WRIGHT CITY BUILDING PARKING LOT REPAIRS		
		FORT WRIGHT, KENTUCKY		
		PROJECT: 23028204		
 your trusted advisor consultants	engineers architects planners		Date 2/1/2024	
	BASE PROJECT			
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
23	713	PARKING LOT MARKING - 4" WHITE PAINT (INCLUDES PARKING SPACE LINES AND CROSS HATCHING AS PER PLAN)	1	LS
24	713	PAVEMENT MARKING - DOUBLE YELLOW CENTERLINE (YELLOW PAINT)	65	LF
25	714	PAVEMENT STRIPING - 24" STOP BAR (WHITE THERMO)	15	LF
26	SPL	INSTALL HANDICAP PARKING SIGNS AS PER PLAN	2	EA