



To: All Plan Holders of Record

From: CT Consultants, Inc.
For the Owner

**Re: Addendum No. 3
Constance Avenue Lift Station Improvements
Village of Hiram**

Date: March 1, 2024

This Addendum forms a part of the contract documents and modifies the original bidding documents dated February 2024 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

QUESTIONS AND ANSWERS

Q1. Where is the location of the discharge manhole for the Constance Ave Lift Station?

A1. The discharge manhole for the Constance Avenue Lift Station is located in the southeast corner of the intersection of SR 700 and Hinsdale Street, in the front yad of Booth Hall. The Constance Avenue Lift Station has seasonal flows, and flows can be near zero for extended periods of time during a day.

SPECIFICATIONS

1. **Replace** Specification 432139 – Section 2.2.A. with the following;

A. Pump(s)

Location:	<u>Constance Avenue Pump Station</u> _____
Number Installed:	<u>2</u> _____
Impeller Type:	<u>Semi- open</u> _____
Pumped Liquid:	<u>Wastewater</u> _____
Solid Size, at least:	<u>3</u> inch sphere
Design Point #1:	<u>120</u> GPM @ <u>137</u> ft. TDH
Min. Hyd. Efficiency @ Pt.:	<u>39</u> %
Discharge Size:	<u>3</u> inches
Motor Hp:	<u>20</u> Hp
Motor Speed:	<u>1,835</u> RPM
Power Requirements:	<u>230</u> VAC, _____ Phase, 60 Hz.

EF/RS:rs/br

H:\2023\230355\SPEC\Addenda\Addendum 03\Addendum 03.Doc