

Not a Bid Form

CT Consultants, Inc.

Project:

**ROSE AVENUE ROADWAY IMPROVEMENTS
HIGHLAND HEIGHTS, KENTUCKY**

Bid Date: 03/07/2024
Project No.: 231713

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
ROSE AVENUE				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	203	REMOVE EXISTING STORM INLET	2	EA
4	203	REMOVE EXISTING PAVEMENT	90	SY
5	207	SUBGRADE RESHAPING AND COMPACTING	90	SY
6	302	6" DGA FOR SUBGRADE REPAIR	50	CY
7	408	ASPHALT MILLING (2" THICK)	2,950	SY
8	402/403	0.75" ASPHALT LEVELING	2,950	SY
9	402/403	1.25" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER)	2,950	SY
10	402/403*	VARIABLE THICKNESS ASPHALT WEDGING FOR PAVEMENT GRADE ADJUSTMENT	5	TON
11	SPL*	FULL DEPTH PAVEMENT REPAIR, AS PER PLAN	350	SY
12	505	8" CONCRETE PAVEMENT WITH INTEGRAL 3" ROLLED CURB	90	SY

CT Consultants, Inc.

Project: **ROSE AVENUE ROADWAY IMPROVEMENTS
HIGHLAND HEIGHTS, KENTUCKY**

Bid Date: 03/07/2024
Project No.: 231713

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
		ROSE AVENUE		
13	505*	4" CONCRETE SIDEWALK REPLACEMENT	200	SF
14	505*	6" CONCRETE DRIVEWAY REPLACEMENT	300	SF
15	SPL*	4" ROLLED CURB AND GUTTER REPLACEMENT	500	LF
16	701	INSTALL 12" DIAMETER STORM SEWER (RCP)	18	LF
17	710	INSTALL STANDARD DOUBLE GRATE CURB INLET	2	EA
18	SPL	YARD RESTORATION BEHIND NEW CURB (4" TOPSOIL, SEED & MULCH)	1	LS
19	SPL	MISC. UTILITY ADJUSTMENTS	1	LS