

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
1	201	CLEARING AND GRUBBING	1	LS
2	202	PAVEMENT REMOVED	35	SY
3	202	* CURB REMOVED, COMBINATION CURB AND GUTTER TYPE 3	500	LF
4	452	9" NON-REINFORCED CONCRETE DRIVEWAY APRON, AS PER PLAN	560	SY
5	608	CONCRETE WALK, AS PER PLAN (5" AND 9" AT DRIVEWAY APRON AND CURB RAMPS)	6,352	SF
6	608/SPL	CURB RAMP, AS PER PLAN	279	SF
7	609	* COMBINATION CURB AND GUTTER, TYPE 3, AS PER PLAN	500	LF
8	611	MANHOLE, ADJUSTED TO GRADE	5	EA
9	611	SPECIAL - GAS VALVE ADJUSTED TO GRADE	2	EA
10	614	MAINTENANCE OF TRAFFIC	1	LS
11	623	CONSTRUCTION LAYOUT STAKES	1	LS
12	624	MOBILIZATION	1	LS
13	630	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION, AS PER PLAN	1	EA
14	638	WATER VALVE ADJUSTED TO GRADE	1	EA

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
15	644	STOP LINE, 24" (WHITE)	18	FT
16	644	CROSSWALK LINE, 12" (WHITE)	110	LF
17	SPL	CONTIGENCY / DISCRETIONARY ALLOWANCE	1	EA
BASE BID - TRI-COUNTY PKWY SIDEWALKS SUBTOTAL:				
BID ALTERNATE #1 - TREE PLANTINGS				
18	SPL	AMERICAN LINDEN (Largest 1 ½" to 2 ½" Caliper)	5	EA
19	SPL	THORNLESS HONEYLOCUST (Largest 1 ½" to 2 ½" Caliper)	7	EA
20	SPL	BLACK GUM (Largest 1 ½" to 2 ½" Caliper)	9	EA
21	SPL	AMERICAN YELLOWWOOD (Largest 1 ½" to 2 ½" Caliper)	6	EA
BID ALTERNATE #1 - PLANTINGS, SOIL, MULCH SUBTOTAL:				