

# Not a Bid Form

 <span style="float: right;"> <b>GEORGE HUSER DRIVE SIDEWALK RECONSTRUCTION AND DRAINAGE REPAIR</b>  <b>CITY OF FORT WRIGHT</b> </span>				
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	203	REMOVE EXISTING SIDEWALK	1,050	SF
5	203	REMOVE EXISTING PAVEMENT, INCLUDING EXISTING CURB	70	SY
6	204	EXCAVATION FOR SIDEWALK	25	CY
7	205	ADDITIONAL DGA FILL TO ADJUST CHANNEL TO GRADE	50	CY
8	207	SUBGRADE RESHAPING AND COMPACTING	300	SY
9	SPL	YARD RESTORATION (4" TOP SOIL, SEED AND MULCH)	200	SY
10	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
11	302	6" DGA BASE FOR CONCRETE CHANNEL	1,300	SF
12	402/408	1-1/2" ASPHALT PAVEMENT MILLING & RESURFACING	75	SY
13	SPL	CONCRETE SIDEWALK	1,450	SF
14	SPL	ADA CURB RAMP	2	EA
15	SPL	12" TALL CURB (AT BACK OF WALK)	230	LF



**GEORGE HUSER DRIVE SIDEWALK RECONSTRUCTION AND DRAINAGE REPAIR  
CITY OF FORT WRIGHT**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
16	SPL	CONCRETE VERTICAL CURB AND GUTTER	260	LF
17	SPL	CONCRETE CHANNEL (INCLUDES ALL REINFORCING)	1,300	SF
18	SPL	REMOVE AND REPLACE CATCH BASIN	1	EA
19	SPL	ADJUST DOUBLE GRATE CURB INLET TO GRADE	1	EA
20	SPL	ADJUST WATER VALVE TO FINISHED GRADE	1	EA
21	713	PAVEMENT STRIPING - 6" CROSSWALK LINE - WHITE PAINT	65	LF
22	SPL	EXTEND 4" DOWNSPOUT LINE AND CONNECT TO CONCRETE CHANNEL	15	LF
23	SPL	EXTEND 6" DOWNSPOUT LINE AND CONNECT TO CONCRETE CHANNEL	10	LF



GEORGE HUSER DRIVE SIDEWALK RECONSTRUCTION AND DRAINAGE REPAIR  
CITY OF FORT WRIGHT

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>ALTERNATE BID - STA</b>				
24	112	MAINTENANCE OF TRAFFIC	1	LS
25	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
26	203	REMOVE EXISTING SIDEWALK	350	SF
27	203	REMOVE EXISTING PAVEMENT, INCLUDING EXISTING CURB	20	SY
28	207	SUBGRADE RESHAPING AND COMPACTING	60	SY
29	SPL	YARD RESTORATION (4" TOP SOIL, SEED AND MULCH)	50	SY
30	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
31	402/408	1-1/2" ASPHALT PAVEMENT MILLING & RESURFACING	25	SY
31	SPL	CONCRETE SIDEWALK	500	SF
32	SPL	ADA CURB RAMP	1	EA
33	SPL	CONCRETE VERTICAL CURB AND GUTTER	90	LF