



## ADDENDUM #1

**Job #:** 232586                      **Project Title**    **Ft. Thomas Tennis Court Trail**

**Client:**            **City of Ft. Thomas**

**Issue**            **March 14, 2024**  
**Date:**

**Bid Date:**    **March 27, 2024**

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN VIA EMAIL TO: [pbellew@ctconsultants.com](mailto:pbellew@ctconsultants.com).

\_\_\_\_\_  
Name / Title:

\_\_\_\_\_  
Company:

\_\_\_\_\_  
Date:

Please see revised bid tab.

**CT Consultants, Inc.**

Project:

**TOWER PARK - TENNIS COURT PATH  
FORT THOMAS, KENTUCKY**

Bid Date: 03/27/2024  
Project No.: 232586

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
1	110	MOBILIZATION	1	LS		
2	202	CLEARING AND GRUBBING	1	LS		
<b>SUBTOTAL</b>						
<b>TRAIL WIDENING/PAVING</b>						
3	204	EXCAVATION	25	CY		
4	204	EMBANKMENT	40	CY		
5	SPL	YARD RESTORATION (4" TOP SOIL, SEED AND MULCH)	400	SY		
6	207	SUBGRADE COMPACTION	652	SY		
7	302	6" CRUSHED STONE BASE	20	CY		
8	302	CRUSHED STONE BASE, VARIABLE DEPTH, SCRAPE	14	CY		
9	302	CRUSHED STONE BASE, VARIABLE DEPTH, PLACE AND COMPACT	10	CY		
10	402/403	1.5" ASPHALT BASE	60	TON		
11	402/403	1.5" ASPHALT SURFACE	60	TON		
<b>SUBTOTAL - TRAIL WIDENING/PAVING</b>						
<b>NEW TRAIL ADJACENT TO PLAYGROUND</b>						
12	204	EXCAVATION	18	CY		
13	SPL	YARD RESTORATION (4" TOP SOIL, SEED AND MULCH)	60	SY		
14	302	6" CRUSHED STONE BASE	14	CY		
15	402/403	1.5" ASPHALT BASE	4	TON		

**CT Consultants, Inc.**

Project: **TOWER PARK - TENNIS COURT PATH  
FORT THOMAS, KENTUCKY**

Bid Date: 03/27/2024  
Project No.: 232586

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
16	402/403	1.5" ASPHALT SURFACE	4	TON		
<b>SUBTOTAL - NEW TRAIL ADJACENT TO PLAYGROUND</b>						
<b>TENNIS COURT ACCESS PATH</b>						
17	204	EXCAVATION, INCLUDING EX PAVEMENT REMOVAL	27	CY		
18	SPL	YARD RESTORATION (4" TOP SOIL, SEED AND MULCH)	350	SY		
19	207	SUBGRADE COMPACTION	170	SY		
20	408	PAVEMENT PLANNING - ADD BUTT JOINT TO WEST END OF ACCESS PATH WHERE PATH MEETS EXISTING	35	SY		
21	402/403	1.5" ASPHALT SURFACE	35	TON		
22	505	6" CONCRETE PAVEMENT REPLACEMENT	1,535	SF		
<b>SUBTOTAL - TENNIS COURT ACCESS PATH</b>						
<b>TOTAL CONSTRUCTION COST</b>						