

CT Consultants, Inc.

Project:

**2024 STREET PROGRAM
SOUTHGATE, KENTUCKY**

Date: 02/22/2024
Project No.: 241022

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
		PART A - ELECTRIC AVENUE (RIDGWAY TO WALNUT)		
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	402/403	ASPHALT LEVELING (1" AVG.)	1,500	SY
4	402/403	1-1/2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	1,500	SY
5	408	ASPHALT PAVEMENT MILLING AND TEXTURING (2.5" TYP)	1,500	SY
6	SPL*	FULL DEPTH PAVEMENT REPAIR (15% OF PAVEMENT AREA)	225	SY
7	302*	DENSE GRADED AGGREGATE BASE FOR SUBGRADE REPAIR (INCLUDES EXCAVATION & DISPOSAL OF UNSUITABLE MATERIAL)	50	CY
8	505*	CONCRETE SIDEWALK REMOVE AND REPLACE	850	SF
9	505	ADA CURB RAMP	6	EA
10	505*	DRIVEWAY APRON REMOVE AND REPLACE	1,175	SF
11	506	CONCRETE VERTICAL CURB REPLACEMENT	1,075	LF
12	SPL*	RESTORATION/BACKFILL CURBS	1	LS
13	704	4" UNDERDRAIN	140	LF
14	SPL	CONNECT UNDERDRAIN TO EXISTING CATCH BASIN	2	EA

CT Consultants, Inc.

Project:

**2024 STREET PROGRAM
SOUTHGATE, KENTUCKY**

Date: 02/22/2024
Project No.: 241022

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
15	713/714	PAVEMENT MARKING	1	LS
16	SPL	ADJUST MANHOLE FRAME AND GRATE TO FINISH GRADE PER SD1 REQUIREMENTS	1	EA
17	SPL	ADJUST WATER METER/GAS VALVE	1	LS
PART B - ELECTRIC AVENUE (WALNUT TO TEMPLE)				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	402/403	ASPHALT LEVELING (1" AVG.)	2,500	SY
4	402/403	1-1/2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	2,500	SY
5	408	ASPHALT PAVEMENT MILLING AND TEXTURING (2.5" TYP)	2,500	SY
6	SPL	FULL DEPTH PAVEMENT REPAIR, AS SHOWN ON PLANS	160	SY
7	SPL*	FULL DEPTH PAVEMENT REPAIR (15% PAVEMENT AREA)	375	SY
8	302*	DENSE GRADED AGGREGATE BASE FOR SUBGRADE REPAIR (INCLUDES EXCAVATION & DISPOSAL OF UNSUITABLE MATERIAL)	70	CY
9	505*	CONCRETE SIDEWALK REMOVE AND REPLACE	350	SF

CT Consultants, Inc.

Project:

**2024 STREET PROGRAM
SOUTHGATE, KENTUCKY**

Date: 02/22/2024
Project No.: 241022

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
10	505	ADA CURB RAMP	3	EA
11	505*	DRIVEWAY APRON REMOVE AND REPLACE	50	SF
12	506	CONCRETE VERTICAL CURB REPLACEMENT	580	LF
13	SPL*	RESTORATION/BACKFILL CURBS	1	LS
14	SPL	EXTEND DOWNSPOUT THROUGH CURB	8	EA
15	713/714	PAVEMENT MARKING	1	LS
16	SPL	ADJUST MANHOLE FRAME AND GRATE TO FINISH GRADE PER SD1 REQUIREMENTS	2	EA
17	SPL	ADJSUT DRAINAGE STRUCTURE GRATE TO GRADE PER SD1 REQUIREMENTS	1	EA
18	SPL	ADJUST WATER METER/GAS VALVE	1	LS
PART C - EVERGREEN AVENUE (TEMPLE TO RETREAT)				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	402/403	ASPHALT LEVELING (1" AVG.)	1,075	SY
4	402/403	1-1/2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	1,075	SY

CT Consultants, Inc.

Project:

**2024 STREET PROGRAM
SOUTHGATE, KENTUCKY**

Date: 02/22/2024
Project No.: 241022

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
5	408	ASPHALT PAVEMENT MILLING AND TEXTURING (2.5" TYP)	1,075	SY
6	SPL*	FULL DEPTH PAVEMENT REPAIR (15% PAVEMENT AREA)	165	SY
7	302*	DENSE GRADED AGGREGATE BASE FOR SUBGRADE REPAIR (INCLUDES EXCAVATION & DISPOSAL OF UNSUITABLE MATERIAL)	30	CY
8	505*	CONCRETE SIDEWALK REMOVE AND REPLACE	50	SF
9	505	ADA CURB RAMP	1	EA
10	505*	DRIVEWAY APRON REMOVE AND REPLACE	340	SF
11	506	CONCRETE VERTICAL CURB REPLACEMENT	130	LF
12	SPL*	RESTORATION/BACKFILL CURBS	1	LS
13	713/714	PAVEMENT MARKING	1	LS
14	SPL	ADJUST MANHOLE FRAME AND GRATE TO FINISH GRADE PER SD1 REQUIREMENTS	1	EA
15	SPL	ADJUST WATER METER/GAS VALVE	1	LS
		PART D - BEECH ROAD (#229 TO NORTH STREET)		
1	110	MOBILIZATION	1	LS

CT Consultants, Inc.

Project:

**2024 STREET PROGRAM
SOUTHGATE, KENTUCKY**

Date: 02/22/2024
Project No.: 241022

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	402/403	ASPHALT LEVELING (1" AVG.)	1,275	SY
4	402/403	1-1/2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	1,275	SY
5	408	ASPHALT PAVEMENT MILLING AND TEXTURING (2.5" TYP)	1,275	SY
6	SPL*	FULL DEPTH PAVEMENT REPAIR (15% PAVEMENT AREA)	195	SY
7	302*	DENSE GRADED AGGREGATE BASE FOR SUBGRADE REPAIR (INCLUDES EXCAVATION & DISPOSAL OF UNSUITABLE MATERIAL)	40	CY
8	505*	CONCRETE SIDEWALK REMOVE AND REPLACE	425	SF
9	505	ADA CURB RAMP	1	EA
10	505*	DRIVEWAY APRON REMOVE AND REPLACE	775	SF
11	506	CONCRETE VERTICAL CURB REPLACEMENT	1,000	LF
12	SPL*	RESTORATION/BACKFILL CURBS	1	LS
13	713/714	PAVEMENT MARKING	1	LS
14	SPL	ADJUST MANHOLE FRAME AND GRATE TO FINISH GRADE PER SD1 REQUIREMENTS	1	EA
15	SPL	ADJSUT DRAINAGE STRUCTURE GRATE TO GRADE PER SD1 REQUIREMENTS	2	EA
16	SPL	ADJUST WATER METER/GAS VALVE	1	LS

CT Consultants, Inc.

Project:

**2024 STREET PROGRAM
SOUTHGATE, KENTUCKY**

Date: 02/22/2024
Project No.: 241022

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
		PART E - PUBLIC WORKS PARKING LOT		
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	402/403	ASPHALT LEVELING (2.5" AVG.)	1,375	SY
4	402/403	1-1/2" ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT	1,375	SY
5	SPL	FULL DEPTH ASPHALT PARKING LOT EXPANSION	50	SY
6	302*	DENSE GRADED AGGREGATE BASE (INCLUDES EXCAVATION & DISPOSAL OF UNSUITABLE MATERIAL)	20	CY
7	506	CONCRETE EXTRUDED CURB REPLACEMENT	520	LF
8	506	CONCRETE VERTICAL CURB REPLACEMENT	60	LF
9	SPL*	RESTORATION/BACKFILL CURBS	1	LS
10	713/714	PAVEMENT MARKING	1	LS
11	212/213	EROSION & POLLUTION CONTROL	1	LS

CT Consultants, Inc.

Project:

**2024 STREET PROGRAM
SOUTHGATE, KENTUCKY**

Date: 02/22/2024
Project No.: 241022

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure