



To: All Plan Holders of Record

From: CT Consultants, Inc.  
For the Owner

**Re: *Addendum No. 2***  
***2024 Pavement Repair Program***  
***Village of Fairport Harbor***

Date: August 20, 2024

This Addendum forms a part of the contract documents and modifies the original bidding documents dated August, 2024 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

### **BID FORMS**

Replace Bid Form, Page BF.8A, with the enclosed Bid Form, Page BF.8B.

The Village had the West end of New Fourth Street planed as part of an adjacent project on the East end of New Fourth Street.

### **SPECIFICATIONS**

**Replace** Specification Section 011100 - SUMMARY OF WORK, Pg 2 from Addendum 1 with the attached revised Pg 2 Quantity Summary Sheet.

BR:br

Enclosures

H:\2024\241495\SPEC\Addenda\02 Addm\Addendum 02.Doc

241495 QUANTITY SUMMARY AND SCOPE  
2024 PAVEMENT REPAIR PROGRAM

CT Bid Tab #s	Item No.	Item Description	Total Qty - Base Bid	Unit	Base Bid			Alternates A & B			
					General / Extra	New 4th St.	5th St. Plum St.	Total Qty Alternates	General / Extra	Paradise Ct. Vine St.	
		From									
		To									
		Centerline (ft)				400	795				283
		Width (ft)				29.4	23.8				29.8
		Calculated Area (sf)				12,350	19,870				8,860
		Area used (sf)				12,350	19,870				8,860
		Area used (sy)				1,370	2,210				980
		Proposed Average Variable Planing Thickness (in)				2.25	2.50				0.00
		Proposed Average Variable Surface Course Thickness (in)				2.25	2.50				0.00
		Proposed Intermediate Course Thickness, Scratch (in)				0.00	0.00				0.00
103s05001	SPC	BONDS & INSURANCES, AS PER PLAN	1.0	LUMP	1.0				1.0		
251E01001	251	PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN, T=2"	5.0	SY	5.0	0.0	0.0		10.0		60.3
253E01000	253	PAVEMENT REPAIR (FULL DEPTH T = 8")	18.0	SY		6.7	11.3				
254e01002	254	PAVEMENT PLANING; ASPHALT CONCRETE, VARIABLE THICKNESS, AS PER PLAN	2,310.0	SY	100.0	0.0	2,210.0				
407E20205	407	TACK COAT, TRACKLESS TACK	540.0	GAL.		210.0	330.0				
441E50001	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG64-22, AS PER PLAN	259.0	CY	20.0	86.0	153.0				
609e23002	609	COMBINATION CURB AND GUTTER, TYPE 4, INCLUDING REMOVAL, AS PER PLAN	48.5	FT.		44.5	4.0				
611e98634	611	CATCH BASIN RECONSTRUCTED TO GRADE	3.0	EACH		2.0	1.0				
611E98651	611	CATCH BASIN FRAME AND GRATE	1.0	EACH		1.0					
614E11001	614	MAINTAINING TRAFFIC, AS PER PLAN	1.0	LUMP	1.0				1.0		
624E10000	624	MOBILIZATION	1.0	LUMP	1.0				1.0		
999s99998	SPCL	CONTINGENCY/DISCRETIONARY ALLOWANCE	1.0	LUMP	1.0				0.0		0.0
		Alternate A - Chip Seal									
422E10000		SINGLE CHIP SEAL	0.0	SY	0.0				10.0		980.0
		Alternate B - Fog Seal									
422s90311		POLYMER FOG SEAL EMULSION	0.0	SY	0.0				10.0		980.0

**Proposal to Village of Fairport Harbor  
For 2024 Pavement Repair Program  
Base Bid - New 4th St & 5th St  
Project No. 241495**

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL	
1	(SPC) BONDS AND INSURANCES, AS PER PLAN	1.00	LS	\$	\$	\$	\$	
2	(251) PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	5.00	SY	\$	\$	\$	\$	
3	(253) PAVEMENT REPAIR	18.00	SY	\$	\$	\$	\$	
4	(254) PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN	2,310.00	SY	\$	\$	\$	\$	
5	(407) TACK COAT, TRACKLESS TACK	540.00	GAL	\$	\$	\$	\$	
6	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22, AS PER PLAN	259.00	CY	\$	\$	\$	\$	
7	(609) COMBINATION CURB AND GUTTER, TYPE 4, INCLUDING REMOVAL, AS PER PLAN	48.50	FT	\$	\$	\$	\$	
8	(611) CATCH BASIN RECONSTRUCTED TO GRADE	3.00	EACH	\$	\$	\$	\$	
9	(611) CATCH BASIN FRAME AND GRATE	1.00	EACH	\$	\$	\$	\$	
10	(614) MAINTAINING TRAFFIC, AS PER PLAN	1.00	LS	\$	\$	\$	\$	
11	(624) MOBILIZATION	1.00	LS	\$	\$	\$	\$	
12	(SPC) CONTINGENCY/DISCRETIONARY ALLOWANCE	1.00	LS	\$	\$	\$	\$	
<b>INFORMAL TOTAL BID</b>							<b>\$</b>	<b>\$</b>